

# SCHEDULE OF QUANTITIES

## F.A.U. 7669/HOLIDAY DRIVE

**CITY OF MATTOON**

SECTION 05-00143-00-RS

ROUTE: F.A.U. 7669

HOLIDAY DRIVE

JOB#: C-97-060-06

PROJ#: M-5042(14)

CONTRACT#: 95479

COLES COUNTY

SHEET 32 OF 43

X4066414 BIT. CONC. SFE. CSE. SP C N50

13' Lt.~14'Rt., 0+52 ~ 8+73 = 207.0 TON  
 TOTAL = 207.0 TON

40600980 BIT. SURF. REMOVAL BUTT JT.

13' Lt.~14'Rt., 7+28 ~ 8+73 = 423.0 SQ.YDs.  
 TOTAL = 423.0 SQ.YDs

44201771 CLASS D PATCHES TYPE 4 10"

4.5'~ 13' Lt., 4+34 ~ 4+65 = 29.3 SQ.YDs.  
 TOTAL = 29.3 SQ.YDs.

X4066765 LEVEL BINDER MM C N50

12' Lt.~Rt., 0+52 ~ 7+33 = 77.0 TON  
 TOTAL = 77.0 TON

40800400 INCIDENTAL BIT. SURFACING

C.E. 1+00 Rt., 14'~16' Rt. = 1.0 TON  
 C.E. 4+53 Lt., 13'~15' Lt. = 0.3 TON  
 C.E. 5+14 Lt., 13'~15' Lt. = 0.3 TON  
 TOTAL = 1.6 TON

78000200 THERMOPLASTIC PVT MK LINE 4"

C~L, 0+55 ~ 7+60 = 180.0 FOOT  
 DASHED 10' YELLOW 4"  
 12' Lt. & Rt., 0+55 ~ 6+00 = 1420.0 FOOT  
 SOLID WHITE EDGE LANE 4"  
 TOTAL = 1600.0 FOOT

40600100 BIT. MATERIALS (PRIME COAT)

Lt. ~ Rt., 0+52 ~ 8+73 = 250 GALLON  
 TOTAL = 250 GALLON

44201765 CLASS D PATCHES TYPE 2 10"

4.5' ~ 10.5' Lt., 6+21 ~ 6+41 = 13.4 SQ.YDs.  
 TOTAL = 13.4 SQ.YDs.

78000650 THERMOPLASTIC PVT MK LINE 24"

C~L ~ 12' Lt., 0+53 = 12.0 FOOT  
 C~L ~ 12' Rt., 7+65 = 12.0 FOOT  
 C~L ~ 12' Lt., 8+72 = 12.0 FOOT  
 SOLID WHITE 24" STOP BAR  
 TOTAL = 36.0 FOOT

40600300 AGGREGATE (PRIME COAT)

Lt. ~ Rt., 0+52 ~ 8+73 = 2.5 TON  
 TOTAL = 2.5 TON

44201769 CLASS D PATCHES TYPE 3 10"

9'~13' Rt., 1+14 ~ 1+49 = 15.6 SQ.YDs.  
 TOTAL = 15.6 SQ.YDs.