



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 8, 2023

SUBJECT FAP Route 338 (IL 59)
Project NHPP-RHLF(743)
Section FAP 0338 22 BJ
Will County
Contract No. 62T09
Item No. 15, September 22, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added pages 151-153 to the Special Provisions
4. Revised sheets 1, 2, 4, 5, 16, & 22 of the Plans
5. Added sheets 14A, 16A, & 23A-23E to the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) 115
BLENDED FINELY DIVIDED MINERALS (BDE)..... 116
COMPENSABLE DELAY COSTS (BDE)..... 117
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)..... 121
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 123
FUEL COST ADJUSTMENT (BDE)..... 132
PERFORMANCE GRADED ASPHALT BINDER (BDE)..... 135
PORTLAND CEMENT CONCRETE (BDE) 140
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) 140
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 141
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 141
SUBMISSION OF PAYROLL RECORDS (BDE)..... 142
TRAINING SPECIAL PROVISIONS (BDE) 143
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION..... 146
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 148
WEEKLY DBE TRUCKING REPORTS (BDE)..... 148
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 148
WORKING DAYS (BDE)..... 150
RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL 151
RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REPLACEMENT 151
TEMPORARY TRAFFIC SIGNAL TIMING 152
TEMPORARY VIDEO DETECTION 153

Revised 9/8/2023

RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL

Effective: August 1, 2023

Revised:

Description: This work shall be completed in accordance with Section 783 of the Standard Specifications for Road and Bridge Construction. This work shall consist of removing the reflector unit from existing raised reflector pavement markers that will remain in place at the end of construction activities. Existing reflectors that conflict with revised traffic patterns shall be removed immediately to facilitate a change in lane assignment. If darkness or inclement weather prohibits the removal operations, such operation shall be resumed the next morning of when weather permits.

The base casting shall remain in place in areas where no pavement rehabilitation is required, therefore only the reflector shall be removed. Debris from the removal operations shall be removed from the pavement prior to opening the roadway to traffic.

Basis of Payment: This work will be measured for payment at the contract unit price per each for RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL. Payment shall be full compensation for materials, labor and equipment required to complete this work.

RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REPLACEMENT

Effective: August 1, 2023

Revised:

Description: This work shall be completed in accordance with Section 781 of the Standard Specifications for Road and Bridge Construction. This work shall consist of reinstallation of reflectors into the raised pavement marker castings upon completion of staging in which the markers were in conflict with temporary lane usage.

Basis of Payment: This work will be measured for payment at the contract unit price per each for RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REPLACEMENT. Payment shall be full compensation for materials, labor and equipment required to complete this work.

Added 9/8/2023

TEMPORARY TRAFFIC SIGNAL TIMING

Effective: May 22, 2002

Revised: July 1, 2015

890.02TS

Description.

This work shall consist of developing and maintaining appropriate traffic signal timings for the specified intersection for the duration of the temporary signalized condition, as well as impact to existing traffic signal timings caused by detours or other temporary conditions.

All timings and adjustments necessary for this work shall be performed by an approved Consultant who has previous experience in optimizing Closed Loop Traffic signal Systems for District One of the Illinois Department of Transportation. The Contractor shall contact the Traffic Signal Engineer at (847) 705-4424 for a listing of approved Consultants.

The following tasks are associated with TEMPORARY TRAFFIC SIGNAL TIMING.

- (a) Consultant shall attend temporary traffic signal inspection (turn-on) and/or detour meeting and conduct on-site implementation of the traffic signal timings.
- (b) Consultant shall be responsible for making fine-tuning adjustments to the timings in the field to alleviate observed adverse operating conditions and to enhance operations.
- (c) Consultant shall provide monthly observation of traffic signal operations in the field.
- (d) Consultant shall provide on-site consultation and adjust timings as necessary for construction stage changes, temporary traffic signal phase changes, and any other conditions affecting timing and phasing, including lane closures, detours, and other construction activities.
- (e) Consultant shall make timing adjustments and prepare comment responses as directed by the Area Traffic Signal Operations Engineer.
- (f) Return original timing plan once construction is complete.

Basis of Payment.

The work shall be paid for at the contract unit price each for TEMPORARY TRAFFIC SIGNAL TIMING, which price shall be payment in full for performing all work described herein per intersection. When the temporary traffic signal installation is turned on and/or detour implemented, 50 percent of the bid price will be paid. The remaining 50 percent of the bid price will be paid following the removal of the temporary traffic signal installation and/or detour.

Added 9/8/2023

TEMPORARY VIDEO DETECTION

Description: This work shall consist of furnishing, installing, maintaining, and removing temporary video detection as shown on the plans.

The video vehicle detection system shall be approved by IDOT prior to Contractor furnishing and installing. The Contractor shall install, wire, and adjust the alignment of the video vehicle detection system in accordance with the manufacturer's recommendations and requirements. The Contractor shall be responsible for adjusting the alignment of the video vehicle detection system for all construction staging changes and for maintaining proper alignment throughout the project. An equipment supplier shall be present and assist the Contractor in setting up and maintaining the video vehicle detection system. An in-cabinet video monitor shall be provided with all video vehicle detection systems and shall be included.

Basis of Payment: This work shall be paid for at the contract unit price each for TEMPORARY VIDEO DETECTION the price of which shall include the cost for all of the work and material described herein and includes furnishing, installing, maintaining, all appurtenances and mounting hardware necessary, and removal of all equipment at the end of the contract.

Added 9/8/2023