

SUMMARY OF QUANTITIES

F.A.I. RYE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
62300		* (B18, ETC. 2324.6-1)PR-8		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	90% FEDERAL / 10% STATE						
				ROADWAY	SIGNING	SURVEILLANCE	SN 016-2625	SN 016-0142 SN 016-1148		
				J000-2A	Y002-1C	Y032-1F	X928-2A	SFTY-2A		
* 81400200	HEAVY-DUTY HANDHOLE	EACH	13			13				
* 81400205	HEAVY-DUTY HANDHOLE (SPECIAL)	EACH	2			2				
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	305			305				
* 84200800	POLE FOUNDATION, REMOVED	EACH	130	130						
□ K1003660	MOWING CYCLE	EACH	6	6						
	X0320870 BRACED EXCAVATION	CU YD	6,621	6,621						
	X0322256 TEMPORARY INFORMATION SIGNING	SQ FT	625	625						
	X0323221 PLUG AND ABANDON EXISTING PIPE	CU YD	251	251						
□ X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	209	209						
	X0323988 TEMPORARY SOIL RETENTION SYSTEM	SA FT	52,802	52,802						
	X0324112 BARRIER BASE	FOOT	27,958	27,958						
	X0324431 TEMPORARY SOIL RETENTION SYSTEM (TO REMAIN IN PLACE)	SQ FT	763	763						
	X0324697 SOIL STABILIZERS	POUND	65,508	65,508						
	X0324698 APPLYING DUST SUPPRESSION AGENT	UNIT	110	110						
	X4210400 LUG SYSTEM REMOVAL	EACH	3	3						
	X4834090 PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	52,802	52,802						
	X6063401 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	248	248						
	X6063600 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	951	951						
	X6370910 CONCRETE BARRIER, SINGLE FACE 32" HEIGHT	FOOT	1,742	1,742						
	X6370925 CONCRETE BARRIER SINGLE FACE 42" (SPECIAL)	FOOT	21,414	21,414						
	X6370930 CONCRETE BARRIER, DOUBLE FACE, 32"	FOOT	2,715	2,715						
	X6700410 ENGINEER'S FIELD OFFICE TYPE A (SPECIAL)	CAL MO	15	15						
	X7011015 TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1						
	X7013820 TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	303	303						
	X7015000 CHANGEABLE MESSAGE SIGN	CAL MO	59	59						
	X7040600 FURNISH TEMPORARY CONCRETE BARRIER	FOOT	17,081	17,081						
* X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	100		100					
	XX001854 STABILIZED SUB-BASE, 6"	SQ YD	213,296	213,296						
	XX004201 PAVEMENT REINFORCEMENT 14"	SQ YD	148,867	148,867						
* XX004812	VIDEO TAPING OF SEWERS	FOOT	1,191	1,191						
	Z0002600 BAR SPLICERS	EACH	257			257				
	Z0013798 CONSTRUCTION LAYOUT	L SUM	1	1						
□ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	50	50						
△ Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	6	6						
△ Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3	EACH	3	3						
△ Z0030090	IMPACT ATTENUATORS (SEVERE USE, WIDE), TEST LEVEL 3	EACH	1	1						
△ Z0030150	IMPACT ATTENUATORS, (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1						
△ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	6						
	Z0040530 PIPE UNDERDRAIN REMOVAL	FOOT	290	290						

* SPECIALITY ITEM □ NON-PARTICIPATING

△ INDICATES PAY CODE TYPE SFTY-3N

S00-5



ONE NORTH FRANKLIN
CHICAGO, IL 60606
PHONE: (312) 251-3000
FAX: (312) 251-3015
WEB: WWW.EKCORP.COM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: TAI
DATE: 7/1/05 CHECKED BY: PJM

06/28/2005 12:46:05 PM