

SCHEDULE OF STORM SEWERS

F.A.I. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	143
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
62300		• (1818, ETC, 2324.6-1P/R-8		

FROM STRUCTURE	TO STRUCTURE	SLOPE %	SS CL A T1 12	SS CL A T1 15	SS CL A T1 18	SS CL A T1 21	SS CL A T2 12	SS CL A T2 15	SS CL A T2 18	SS CL A T2 21	SS CL A T2 24	SS CL A T2 27	SS CL A T2 30	SS CL A T2 33	SS CL A T2 36	SS CL A T2 42	SS CL A T2 48	SS CL A T3 12	SS CL A T3 21	SS CL A T3 24	SS CL A T3 30	SS CL A T3 36	SS CL A T3 42	SS CL B T1 12	SS CL B T1 15	TRENCH BACKFILL
20-02	JC T2 20-01*	0.50	5																							0.8
20-03	20-01	2.00	5																							0.8
20-12	20-01	0.30													76											114.6
20-05	20-04	0.61	54																							8.8
20-06	20-04	1.30	2																							0.5
20-04	20-12	0.20													107											186.5
EXIST.	20-12	1.00	5																							0.9
20-08	20-07	1.00						54																		15.0
20-09	20-07	5.00	15																							0.5
EXIST.	20-09	2.50					80																			12.0
20-07	20-04	0.15													184											326.8
20-11	20-10	0.16																								16.1
20-10	20-07	0.35										65		97												130.6
EXIST.	20-11	1.00	2																							0.5
21-01	20-11	0.25								41																56.6
21-02	21-01	0.50	55																							7.3
21-03	21-01	1.30	2																							0.5
21-04	21-01	0.50								188																266.8
21-05	21-04	0.51	59																							9.0
21-06	21-04	0.60	20																							3.0
EXIST.	21-04	0.50	2																							0.5
22-01	22-03	4.00	4																							0.6
22-02	22-03	0.78		3																						0.8
22-04	22-03	0.55	55																							9.7
22-05	22-06	1.10	45																							6.8
22-03	22-07	0.45								202																302.2
22-06	22-07	1.33	3																							0.6
22-08	22-07	0.57	55																							9.7
22-07	22-09	0.30												157												245.4
22-10	22-09	2.50	4																							0.7
22-11	22-09	0.51	40																							6.9
22-09	JC T2 22-01	0.30												51												72.8
22-12	JC T2 22-01	1.08	26																							4.5
22-14	JC T2 22-01	0.50	45																							8.7
23-01	23-02	3.50	6																							0.9
23-02	23-03	1.29						7																		1.2
23-04	23-03	0.60	55																							9.5
23-03	23-05	0.12													203											293.4
23-06	23-05	2.51	4																							0.7
23-09	23-05	0.23								185																126.9
23-05	JC T2 23-01*	0.10														49										66.7
23-08	JC T2 23-01*	1.44	7																							1.2
23-10	23-09	0.54	57																							9.9
23-11	23-09	0.92		11																						2.0
24-02	24-01	1.68	6																							1.0
24-03	24-01	0.51	60																							10.4
24-01	24-04	0.40		78																						18.4
24-06	24-04	1.00		3																						0.5
24-05	24-06	0.50	11																							1.7
24-07	24-06	0.50	11																							1.7
24-09	24-10	0.50	11																							1.7
24-10	24-11	0.50		11																						2.1
24-11	24-12	0.50		47																						11.1
24-12	JC T2 24.01*	0.70						4																		0.9
24-04	24-13	0.42					51																			14.0
24-08	24-14	1.00	88																							4.0
24-15	24-13	0.15													51											23.5
24-13	JC T2 24.01*	0.11														60										46.3
24-16	24-15	4.00	2																							0.5
24-17	24-15	0.15													151											146.1
24-18	24-17	0.15													18											21.8
24-19	24-17	0.70	20																							3.5
24-14	24-18	1.00	1																							0.5
24-20	24-18	0.50	44																							10.4
24-21	24-18	0.18													95											82.3
25-01	24-21	0.32											83													122.3
EXIST.	24-21	0.50	20																							3.5
25-02	25-01	0.50	23																							3.6
25-03	25-01	0.50	52																							9.0
25-04	25-05	0.50	42																							9.0
25-05	25-06	0.50		23																						3.8
25-07	JC T2 25-01	0.62	26																							4.0

NOTE: \* INDICATED STRUCTURE BEEN CONSTRUCTED IN CONTRACT 62302



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
 31ST STREET TO 71ST STREET  
 NB EXPRESS LANE RECONSTRUCTION  
 DRAINAGE SCHEDULE  
 PROPOSED STORM SEWERS  
 SCALE: 1" = N.T.S. DRAWN BY: MJO  
 DATE: 7/1/05 CHECKED BY: LPN

DS-28

I:\030019\0305\001\4815\CA\01\405\400328.SW  
 07-14-07 FH