

SCHEDULE OF STORM SEWERS

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	144
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
62300		* (1818, ETC, 2324.6-1P1R-8		

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 1, 12	SS CL A 1, 15	SS CL A 1, 18	SS CL A 1, 21	SS CL A 1, 24	SS CL A 2, 12	SS CL A 2, 15	SS CL A 2, 18	SS CL A 2, 21	SS CL A 2, 24	SS CL A 2, 27	SS CL A 2, 30	SS CL A 2, 33	SS CL A 2, 36	SS CL A 2, 42	SS CL A 2, 48	SS CL A 3, 12	SS CL A 3, 21	SS CL A 3, 24	SS CL A 3, 27	SS CL A 3, 30	SS CL A 3, 36	SS CL A 3, 42	SS CL B 1, 12	SS CL B 1, 15	TRENCH BACKFILL (CU. YD.)	
29-13	DMH29-01	42.1	36	0.10%																										42.1	76.4
29-16	29-13	55.4	30	0.13%												55.4															31.9
30-03	29-16	127.7	30	0.15%												127.7															100.4
30-07	30-03	97.7	27	0.17%												97.7															81.4
30-11	30-07	97.7	27	0.21%												97.7															92.9
30-16	30-11	98.2	24	0.43%										98.2																	38.6
29-15	29-16	0.8	12	1.00%						0.8																					
29-17	29-16	44.8	12	1.00%						44.8																					16.1
EX P	29-14	3.0	12	0.43%																								3.0		0.5	
EX CB	29-17	1.0	12	1.00%						1.0																					
30-02	30-03	0.8	12	1.00%						0.8																					
30-04	30-03	44.7	12	1.00%						44.7																					11.5
EX P	30-01	3.8	12	9.20%																								3.8		0.4	
30-06	30-07	0.8	12	1.00%						0.8																					
30-08	30-07	44.8	12	1.00%						44.8																					10.1
EX P	30-05	5.0	12	0.43%																								5.0		0.3	
30-10	30-11	0.8	12	1.00%						0.8																					16.1
30-12	30-11	46.2	12	1.00%						46.2																					1.0
EX P	30-09	5.6	12	4.73%																								5.6		6.3	
30-13	30-12	35.7	12	1.00%						35.7																					
EX P	30-13	1.0	12	1.00%						1.0																					
30-15	30-16	1.3	12	1.00%						1.3																					
29-11	29-13	65.0	27	0.16%																				65.0							106.7
29-07	29-11	120.0	27	0.18%											120.0																142.7
29-03	29-07	122.5	27	0.21%											122.5																74.0
29-02	29-03	1.3	12	1.00%						1.3																					
EX P	29-01	5.7	12	0.55%																								5.7		0.1	
29-04	29-03	43.7	12	1.00%						43.7																					11.1
29-06	29-07	0.8	15	1.00%							0.8																				4.0
29-08	29-07	44.8	12	1.00%						44.8																					1.5
EX P	29-05	6.0	15	0.32%																								6.0			
29-10	29-11	0.8	12	1.00%																	0.8										4.6
29-12	29-11	44.9	12	1.00%						44.9																					
30-21	DMH30-01	39.2	30	0.13%																						39.2				65.6	
30-23	30-21	97.7	30	0.17%																						97.7				172.2	
30-22	30-23	35.2	30	0.17%																						35.2				61.5	
31-02	30-22	95.4	30	0.17%																						95.4				169.6	
31-05	31-02	85.1	30	0.21%																						85.1				133.2	
31-08	31-05	90.0	21	0.21%										90.0																	97.1
31-13	31-08	115.5	18	0.32%									115.5																		33.2
30-24	30-23	42.5	12	1.00%						42.5																					27.0
31-01	31-02	5.0	12	1.00%																	5.0										3.9
31-03	31-05	30.6	12	1.00%						30.6																					20.6
31-04	31-05	4.9	12	1.00%						4.9																					3.3
31-07	31-08	0.8	12	1.00%						0.8																					

DS-29

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
 31ST STREET TO 71ST STREET
 NB EXPRESS LANE RECONSTRUCTION
 DRAINAGE SCHEDULES
 PROPOSED STORM SEWER PIPES
 SCALE: 1"=N.T.S. DRAWN BY: JAM
 DATE: 07/07/05 CHECKED BY: DDM

BOWMAN, BARRETT & ASSOCIATES INC.
 CONSULTING ENGINEERS
 Chicago, Illinois
 312.228.0100
 www.bbainc.com



12/28/2005 12:46:07 PM