

SCHEDULE OF STORM SEWERS

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	556	147
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
62300		• (1818, ETC. 2324.6-1PIR-8		

FROM STR. NO.	TO STR. NO.	LENGTH (FEET)	DIAMETER (INCHES)	SLOPE (%)	SS CL A 1, 12	SS CL A 1, 15	SS CL A 1, 18	SS CL A 1, 21	SS CL A 1, 24	SS CL A 2, 12	SS CL A 2, 15	SS CL A 2, 18	SS CL A 2, 21	SS CL A 2, 24	SS CL A 2, 27	SS CL A 2, 30	SS CL A 2, 33	SS CL A 2, 36	SS CL A 2, 42	SS CL A 2, 48	SS CL A 3, 12	SS CL A 3, 21	SS CL A 3, 24	SS CL A 3, 27	SS CL A 3, 30	SS CL A 3, 36	SS CL A 3, 42	SS CL B 1, 12	SS CL B 1, 15	TRENCH BACKFILL (CU. YD.)
35-07	35-11	7.5	12	1.00%						7.5																				1.9
35-14	35-11	9.5	12	1.00%						9.5																				0.7
EX CB	35-07	1.0	12	1.00%						1.0																				
EX CB	35-05	1.7	15	1.00%																								1.7	0.0	
35-16	35-17	0.8	12	1.00%						0.8																				
35-18	JC35-01	5.6	12	1.00%						5.6																				1.3
EX CB	35-15	1.8	12	1.00%																								1.8	0.0	
36-05	DMH36-01	49.6	21	0.21%																										72.6
36-06	36-05	153.0	21	0.44%									153.0																	150.4
36-03	36-05	13.0	18	0.25%								13.0																		9.7
36-02	36-03	1.3	12	1.00%						1.3																				
36-04	36-03	55.0	12	1.00%						55.0																				6.5
EX CB	36-01	2.1	12	1.00%																								2.1	0.2	
EX MH	36-01	13.2	12	1.00%																								13.2	4.5	
EX P	36-06	12.2	12	1.00%						12.2																				6.9
37-05	JC37-01	49.4	36	0.10%														49.4												74.4
37-08	37-05	143.2	24	0.17%										143.2																146.0
37-15	37-08	40.0	21	0.21%									40.0																	30.9
37-22	37-15	130.5	21	0.44%									130.5																	41.8
37-07	37-08	0.8	12	1.00%						0.8																				
37-09	37-08	54.5	12	1.00%						54.5																				6.3
EX CB	37-06	2.3	12	1.00%																								2.3	0.1	
37-14	37-15	0.8	15	1.00%							0.8																			
37-13	37-14	3.2	15	1.00%							3.2																			0.3
37-16	37-15	54.5	15	1.00%							54.5																			8.7
37-11	37-14	11.0	12	1.00%						11.0																				1.3
37-18	37-14	11.0	15	1.00%							11.0																			3.7
37-17	37-18	1.9	15	1.00%							1.9																			0.1
EX CB	37-17	1.7	15	1.00%																								1.7	0.0	
37-12	37-16	11.0	12	1.00%						11.0																				0.8
37-19	37-16	11.0	12	1.00%						11.0																				0.8
37-21	37-22	1.3	12	1.00%						1.3																				
37-23	37-22	55.0	12	1.00%						55.0																				6.4
EX P	37-20	2.0	12	2.10%																								2.0	0.0	
EX CB	37-20	6.5	12	1.00%																								6.5	0.3	
37-03	37-05	26.8	30	0.15%												26.8														19.7
36-11	37-03	205.1	30	0.21%												205.1														241.3
36-07	36-11	135.4	21	0.44%									135.4																	113.0
36-08	36-07	8.1	15	1.00%							8.1																			5.1
EX P	36-08	1.2	15	0.32%																								1.2		
36-10	36-11	0.8	12	1.00%						0.8																				
36-12	36-11	64.1	12	1.00%						64.1																				9.9
36-09	36-10	2.8	12	1.00%						2.8																				1.1
EX CB	36-09	2.8	12	1.00%																								2.8	0.4	
37-02	37-03	0.8	12	1.00%						0.8																				

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
31ST STREET TO 71ST STREET
NB EXPRESS LANE RECONSTRUCTION
DRAINAGE SCHEDULES
PROPOSED STORM SEWER PIPES
SCALE: 1"=N.T.S. DRAWN BY: JAM
DATE: 07/07/05 CHECKED BY: DDM

DS-32

12/4/2005 12:46:03 PM