

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TAPE, TYPE III 5" (FOOT)
MOT-20 WB I-94/90	10D-30S	2626+00	2638+00	311
MOT-21 WB I-94/90	10D-30S	2638+00	75+94	436
MOT-22 WB I-94/90	10D-30S	75+94	87+94	300
MOT-23 WB I-94/90	10D-30S	87+94	99+94	300
MOT-24 WB I-94/90	10D-30S	99+94	111+94	300
MOT-25 WB I-94/90	10D-30S	111+94	125+39	300
MOT-27 WB I-94/90	10D-30S	125+39	137+39	300
MOT-28 WB I-94/90	10D-30S	137+39	149+39	300
MOT-29 WB I-94/90	10D-30S	149+39	161+39	300
MOT-30 WB I-94/90	10D-30S	161+39	173+25	300
MOT-31 WB I-94/90	10D-30S	173+25	184+51	300
MOT-32 WB I-94/90	10D-30S	184+51	196+51	160
MOT-46 WB I-94/90	10D-30S	173+25	184+51	683
MOT-47 WB I-94/90	10D-30S	184+51	196+51	298
TOTAL				4,587

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TAPE, TYPE III 8" (FOOT)
MOT-20 WB I-94/90	SOLID	2626+00	2638+00	566
MOT-21 WB I-94/90	SOLID	2638+00	75+94	1,991
MOT-22 WB I-94/90	SOLID	75+94	87+94	418
MOT-25 WB I-94/90	SOLID	111+94	125+39	878
MOT-27 WB I-94/90	SOLID	125+39	137+39	2,080
MOT-29 WB I-94/90	SOLID	149+39	161+39	1,740
MOT-31 WB I-94/90	SOLID	173+25	184+51	100
MOT-32 WB I-94/90	SOLID	184+51	196+51	1,497
MOT-39 WB I-94/90	SOLID	99+94	111+94	1,700
MOT-43 WB I-94/90	SOLID	137+39	149+39	916
MOT-44 WB I-94/90	SOLID	149+39	161+39	230
MOT-46 WB I-94/90	SOLID	173+25	184+51	2,073
MOT-47 WB I-94/90	SOLID	184+51	196+51	1,983
TOTAL				16,172

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TAPE, TYPE III 12" (FOOT)
MOT-21 WB I-94/90	SOLID	2638+00	75+94	128
MOT-22 WB I-94/90	SOLID	75+94	87+94	96
MOT-25 WB I-94/90	SOLID	111+94	125+39	136
MOT-27 WB I-94/90	SOLID	125+39	137+39	156
MOT-29 WB I-94/90	SOLID	149+39	161+39	242
MOT-32 WB I-94/90	SOLID	184+51	196+51	178
MOT-39 WB I-94/90	SOLID	99+94	111+94	402
MOT-43 WB I-94/90	SOLID	137+39	149+39	91
MOT-46 WB I-94/90	SOLID	173+25	184+51	630
MOT-47 WB I-94/90	SOLID	184+51	196+51	210
TOTAL				2,269

SHEET NUMBER	STATION	TO STATION	TEMPORARY CONCRETE BARRIER (FOOT)
MOT-04 WB I-94/90 EB I-94/90	87+94	99+94	1,120 1,060
MOT-05 WB I-94/90 EB I-94/90	99+94	111+94	1,200 1,200
MOT-06 WB I-94/90 EB I-94/90 RAMP	111+94	125+39	1,200 1,200 580
MOT-08 WB I-94/90 EB I-94/90 RAMP	125+39	137+39	1,200 1,200 1,150
MOT-09 WB I-94/90 EB I-94/90 RAMP	137+39	149+39	1,200 1,200 1,180
MOT-10 WB I-94/90 EB I-94/90	149+39	161+39	1,200 1,200
MOT-11 WB I-94/90 EB I-94/90	161+39	173+25	1,200 1,200
MOT-12 WB I-94/90 EB I-94/90	173+25	184+51	1,200 1,200
MOT-13 EB I-94/90	184+51	196+51	470
MOT-21	2638+00	2641+60	360
TOTAL			22,720

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

REVISIONS	
NAME	DATE
ADDENDUM 1	9/6/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
NB DAN RYAN ELEVATED BRIDGE
REPAIR FROM 15TH TO 28TH STREETS
CIVIL SCHEDULES

SCALE: =NTS
DATE: 9/12/2005
DRAWN BY: RA
CHECKED BY: RS

CSCH-02

10-6582 AM
9/2/2005