F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	* 2003-028F	COOK	419	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62580

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TAPE, TYPE III 5" (FOOT)
MOT-20		2626+00	2638+00	
WB I-94/90	10D-30S			311
MOT-21		2638+00	75+94	
WB I-94/90	10D-30S			436
MOT-22		75+94	87+94	
WB I-94/90	10D-30S			300
MOT-23		87+94	99+94	
WB I-94/90	10D-30S			300
MOT-24		99+94	111+94	
WB I-94/90	10D-30S			300
MOT-25		111+94	125+39	
WB I-94/90	10D-30S			300
MOT-27		125+39	137+39	
WB I-94/90	10D-30S			300
MOT-28		137+39	149+39	
WB I-94/90	10D-30S			300
MOT-29		149+39	161+39	
WB I-94/90	10D-30S			300
MOT-30		161+39	173+25	
WB I-94/90	10D-30S			300
MOT-31		173+25	184+51	
WB I-94/90	10D-30S			300
MOT-32		184+51	196+51	
WB I-94/90	10D-30S			160
MOT-46		173+25	184+51	
WB I-94/90	10D-30S			683
MOT-47		184+51	196+51	
WB I-94/90	10D-30S			298
			TOTAL	4,587

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TAPE, TYPE III 8" (FOOT)
MOT-20		2626+00	2638+00	
WB I-94/90	SOLID			566
MOT-21		2638+00	75+94	
WB I-94/90	SOLID			1,953
MOT-22		75+94	87+94	
WB I-94/90	SOLID			418
MOT-25		111+94	125+39	
WB I-94/90	SOLID			878
MOT-27		125+39	137+39	
WB I-94/90	SOLID			2,080
MOT-29		149+39	161+39	
WB I-94/90	SOLID			1,740
MOT-31		173+25	184+51	
WB I-94/90	SOLID			100
MOT-32		184+51	196+51	
WB I-94/90	SOLID			1,497
MOT-39		99+94	111+94	
WB I-94/90	SOLID			1,700
MOT-43		137+39	149+39	
WB I-94/90	SOLID			916
MOT-44		149+39	161+39	
WB I-94/90	SOLID			230
MOT-46		173+25	184+51	
WB I-94/90	SOLID			2,073
MOT-47		184+51	196+51	
WB I-94/90	SOLID			1,983
			TOTAL	16,134

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TAPE, TYPE III 12" (FOOT)
MOT-21		2638+00	75+94	
WB I-94/90	SOLID			89
MOT-25		111+94	125+39	
WB I-94/90	SOLID			136
MOT-27		125+39	137+39	
WB I-94/90	SOLID			156
MOT-29		149+39	161+39	
WB I-94/90	SOLID			242
MOT-32		184+51	196+51	
WB I-94/90	SOLID			178
MOT-39		99+94	111+94	
WB I-94/90	SOLID			402
MOT-43		137+39	149+39	
WB I-94/90	SOLID			91
MOT-46		173+25	184+51	
WB I-94/90	SOLID			630
MOT-47		184+51	196+51	
WB I-94/90	SOLID			210
			TOTAL	2,134

SHEET NUMBER	STATION	TO STATION	TEMPORARY CONCRETE BARRIER (FOOT)
MOT-04	87+94	99+94	
WB I-94/90			1,120
EB I-94/90			1,060
MOT-05	99+94	111+94	
WB I-94/90			1,200
EB I-94/90			1,200
MOT-06	111+94	125+39	
WB I-94/90			1,200
EB I-94/90			1,200
RAMP			580
MOT-08	125+39	137+39	
WB I-94/90			1,200
EB I-94/90			1,200
RAMP			1,150
MOT-09	137+39	149+39	
WB I-94/90			1,200
EB I-94/90			1,200
RAMP			1,180
MOT-10	149+39	161+39	
WB I-94/90			1,200
EB I-94/90			1,200
MOT-11	161+39	173+25	
WB I-94/90			1,200
EB I-94/90			1,200
MOT-12	173+25	184+51	
WB I-94/90			1,200
EB I-94/90			1,200
MOT-13	184+51	196+51	
EB I-94/90			470
MOT-21	2638+00	2641+60	360
		TOTAL	22,720

CSCH-02

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
NB DAN RYAN ELEVATED BRIDGE
REPAIR FROM 15TH TO 28TH STREETS
CIVIL SCHEDULES

SCALE: =NTS
DATE: 8/12/2005

DRAWN BY: RA
CHECKED BY: RS

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

N:\660\contract\civil\SITE1FT5\660_1SCPL-SCH01.dgn
3:38:51 PM
8/11/2005