

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2003-118 GRR	WILL	14	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
D -91 -074 -05		CONTRACT 62884		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		90% FED. 10% STATE URBAN SFTY-3J				
X0324589	PIPE UNDERDRAIN OUTLET EXTENSION FOR 4" PIPE	EACH	16	16				
20200100	EARTH EXCAVATION	CU YD	437	437				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2332	2332				
20400800	FURNISHED EXCAVATION	CU YD	1897	1897				
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	12590	12590				
* 25000210	SEEDING, CLASS 2A	ACRE	2.60	2.60				
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	235	235				
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	235	235				
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	235	235				
* 25100630	EROSION CONTROL BLANKET	SQ YD	12590	12590				
48101100	AGGREGATE SHOULDERS, TYPE A 12"	SQ YD	5830	5830				
48202800	BITUMINOUS SHOULDERS SUPERPAVE 10"	SQ YD	55	55				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2				
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2	2				
54248515	CONCRETE COLLAR	EACH	32	32				
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	8	8				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	4				
63000145	STEEL PLATE BEAM GUARD RAIL, TYPE D (SPECIAL)	FOOT	8235	8235				
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1				
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1	1				
63304390	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1A	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4				
67100100	MOBILIZATION	L SUM	1	1				
78200405	GUARDRAIL MARKERS	EACH	30	30				
X0301893	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAIN	EACH	16	16				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		90% FED. 10% STATE URBAN SFTY-3J				
X6330105	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1 SPECIAL	EACH	1	1				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	3	3				
Δ Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1	1				
Δ Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1				
Δ Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1				

* SPECIALTY ITEMS

Δ SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 55/ I-55
CATON FARM ROAD TO N/O BLACK ROAD

PLOT DATE: 6/14/2005

: 07:29:33 06/14/2005

6/14/2005 10:03:48 AM C:\PROJECTS\I-55\I-55.DWG