

| | | | | |
|-----------------------|--------------|----------|-----------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 55 | 2004-119 GRR | WILL | 15 | 3 |
| FED. ROAD DIST. NO. 1 | | ILLINOIS | HIGHWAY PROJECT | |

CONTRACT NO. 62885

| SUMMARY OF QUANTITIES | | | 90% FED. 10% STATE TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | | |
|-----------------------|--|--------|--|--|--|--|--|--|--|
| CODE NO | ITEM | UNIT | | URBAN WILL CO. I-55 STATE 100% SFTY-3J | | | | | |
| X0324589 | PIPE UNDERDRAIN OUTLET EXTENSION FOR 4" PIPE | EACH | 18 | 18 | | | | | |
| 20200100 | EARTH EXCAVATION | CU YD | 844 | 844 | | | | | |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 3407 | 3407 | | | | | |
| 20400800 | FURNISHED EXCAVATION | CU YD | 1716.6 | 1716.6 | | | | | |
| * 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 12947 | 12947 | | | | | |
| * 25000210 | SEEDING, CLASS 2A | ACRE | 2.7 | 2.7 | | | | | |
| * 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 243 | 243 | | | | | |
| * 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 243 | 243 | | | | | |
| * 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 243 | 243 | | | | | |
| * 25100630 | EROSION CONTROL BLANKET | SQ YD | 12947 | 12947 | | | | | |
| 48101100 | AGGREGATE SHOULDERS, TYPE A 12" | SQ YD | 8514 | 8514 | | | | | |
| 48202800 | BITUMINOUS SHOULDERS SUPERPAVE 10" | SQ YD | 55 | 55 | | | | | |
| 54248515 | CONCRETE COLLAR | EACH | 36 | 36 | | | | | |
| 60100060 | CONCRETE HEADWALL FOR PIPE DRAINS | EACH | 2 | 2 | | | | | |
| 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 290 | 290 | | | | | |
| 63000145 | STEEL PLATE BEAM GUARD RAIL, TYPE D (SPECIAL) | FOOT | 11927 | 11927 | | | | | |
| 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 1 | 1 | | | | | |
| 63304395 | TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 2 | EACH | 1 | 1 | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 4 | 4 | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | |
| 78200405 | GUARDRAIL MARKERS | EACH | 35 | 35 | | | | | |
| X0301508 | REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAIN | EACH | 18 | 18 | | | | | |
| X7011015 | TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) | L SUM | 1 | 1 | | | | | |
| X7015000 | CHANGEABLE MESSAGE SIGN | CAL MO | 3 | 3 | | | | | |
| Δ Z0030030 | IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH | 1 | 1 | | | | | |

| SUMMARY OF QUANTITIES | | | 90% FED. 10% STATE TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | | |
|-----------------------|--|------|--|--|--|--|--|--|--|
| CODE NO | ITEM | UNIT | | URBAN WILL CO. I-55 STATE 100% SFTY-3J | | | | | |
| Δ Z0030330 | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3 | EACH | 1 | 1 | | | | | |
| X6330105 | TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1 (SPECIAL) | EACH | 1 | 1 | | | | | |

Δ SFTY-BN
* SPECIALTY ITEMS

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 55 (INTERSTATE 55)
SOUTH OF IL 126 TO RENWICK

PLOT DATE: 5/26/2005

5/26/2005 10:00 AM