

PROJECT: MEDIAN PLANTERS ALONG 75TH & 76TH STREETS
 COOK COUNTY / CITY OF CHICAGO

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	39	3
STA. 2210+00.00		TO STA. 2356+00.00		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
* (1516.1, 1717 & 1818) T-5				62934

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	100% STATE		100% CITY OF CHICAGO	
				DAN RYAN Y003		DAN RYAN Y003	
20101000	TEMPORARY FENCE	FOOT	825	825			
* 31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	230	230			
* 35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	91	91			
* 40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1			
* 42001300	PROTECTIVE COAT	SQ YD	814	814			
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	120	120			
* 42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	211	211			
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	20	20			
* 44000600	SIDEWALK REMOVAL	SQ FT	331	331			
56104600	WATER VALVES 2"	EACH	4			4	
56200900	WATER SERVICE LINE 2 1/2"	FOOT	125			125	
60618390	CONCRETE MEDIAN SURFACE (CORRUGATED)	SQ FT	971	971			
67100100	MOBILIZATION	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1			
70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	12	12			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1700	1700			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	565	565			
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	75	75			
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	65	65			
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	25	25			
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	45	45			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	110	110			
X0325108	BACKFLOW PREVENTER (RP2), 2 INCH	EACH	4			4	
X0325102	INSPECTION PIPE, 4 INCH	EACH	4			4	
X0325105	IRRIGATION SYSTEM	SQ YD	779			779	
X0325106	IRRIGATION SYSTEMS FALL SHUT-DOWN	EACH	4			4	
X0325107	IRRIGATION SYSTEMS SPRING START-UP	EACH	4			4	
X0325109	POROUS GRANULAR MATERIAL	CU YD	205	205			
C2009965	SHRUB, SPIREA X BULMADA MAGIC CARPET (MAGIC CARPET BULMAD SPIREA), 5 GALLON CONTAINER	EACH	419	419			
C2013265	SHRUB, WEIGELA FLORIDA MIDNIGHT WINE (MIDNIGHT WINE OLD FASHIONED WEIGELA), 5 GALLON CONTAINER	EACH	258	258			
A2002010	TREE, AESCULUS FLAVA (YELLOW BUCKEYE), 3" CALIPER, BALLED AND BURLAPPED	EACH	7	7			
A2008750	TREE, ULMUS X PATRIOT (PATRIOT ELM), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5			
X0325103	WATER METER IN VAULT, 2 INCH	EACH	4			4	
X0325104	WATER TAP, 2 INCH	EACH	4			4	
K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	4	4			

* - SPECIALTY ITEMS

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94 (DAN RYAN EXPRESSWAY)
 SUMMARY OF QUANTITIES
 SHEET 1 OF 2

SCALE: NONE
 DATE: JULY 8, 2005
 DRAWN BY: RTM
 CHECKED BY: JPM

07/11/2005 02:53:17 PM