

<b>ROUTE</b>	<b>SECTION</b>	<b>COUNTY</b>	<b>TOTAL SHEETS</b>	<b>SHEET NUMBER</b>
FAP 344	2005-016PCC-PP	LAKE	14	4

CONTRACT 62939

**SUMMARY OF QUANTITIES**

CODE NUMBER	DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE
			URBAN - J000
		UNIT	TOTAL
42001200	PAVEMENT FABRIC	SQ YD	485.3
42001300	PROTECTIVE COAT	SQ YD	1105.3
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	600.0
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	272.0
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	213.3
44213200	SAW CUTS	FOOT	5174
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	465
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	50
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	66
x0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48
Z0017202	DOWEL BARS, 1 1/2"	EACH	1760
Z0075300	TIE BARS	EACH	208

\* SPECIALITY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 US RTE. 45  
 SUMMARY OF QUANTITIES