

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN I000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3				
40600300	AGGREGATE (PRIME COAT)	TON	13	13				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	159	159				
40600990	TEMPORARY RAMP	SQ YD	159	159				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	66	66				
42001300	PROTECTIVE COAT	SQ YD	62	62				
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	6285	6285				
44000124	BITUMINOUS REMOVAL OVER PATCHES 6"	SQ YD	195	195				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	80	80				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	100	100				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	9	9				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1023	1023				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	391	391				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2547	2547				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	362	362				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	131	131				
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	391	391				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2901	2901				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN I000-2A				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1797	1797				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	391	391				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2547	2547				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	362	362				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	131	131				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	58	58				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	53	53				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	186	186				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X400546	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	616	616				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	264	264				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. RTE. 375 (TOUHY AVE.)
AT U.S. 12/45 (MANNHEIM RD.)