

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
412	(62-2VB)I	MARSHALL	19	3
FED. ROAD DIST. NO. -	ILLINOIS	PROJECT		

# SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

CODE NO.	ITEM	UNIT	SFTY-2A
			100% STATE TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	19
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	16
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	175
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	30
31102900	SUB-BASE GRANULAR MATERIAL (SPECIAL)	CU YD	96
42001300	PROTECTIVE COAT	SQ YD	615
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	137
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	479
44000700	APPROACH SLAB REMOVAL	SQ YD	272
44002100	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL	SQ YD	89
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	252
48101200	AGGREGATE SHOULDERS, TYPE B	TON	10
50102400	CONCRETE REMOVAL	CU YD	10
50200100	STRUCTURE EXCAVATION	CU YD	16
50300120	PREFORMED JOINT SEAL 2 1/2"	FOOT	44
50300225	CONCRETE STRUCTURES	CU YD	12
50300300	PROTECTIVE COAT	SQ YD	12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1436
51205200	TEMPORARY SHEET PILING	SQ FT	105

Date: 04/26/2005  
File: c:\projects\cm308\details.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
FAI 412 (I-39)  
SECTION (62-2VB)I  
STA. 165+90.23  
MARSHALL COUNTY

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_  
DATE: 04/26/2005  
DRAWN BY: RLW  
CHECKED BY: \_\_\_\_\_