

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(53-1,32-3)1-3	GRUNDY & LIVINGSTON	11	3
FED. ROAD DIST. NO. - ILLINOIS		PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE	
				LIVINGSTON COUNTY	GRUNDY COUNTY
				SECTION (53-1) J000	SECTION (32-3) J000
42101020	WIDE FLANGE BEAM TERMINAL JOINT, COMPLETE 24'	EACH	4	4	
44200541	CLASS A PATCHES, TYPE II, 9 INCH	SQ YD	625	328	297
44200545	CLASS A PATCHES, TYPE III, 9 INCH	SQ YD	120	80	40
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	608	495	113
44213000	PATCHING REINFORCEMENT	SQ YD	1354	903	451
44213200	SAW CUTS	FOOT	6156	3706	2450
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	4	4
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	55	37	18
* 78005110	EPOXY PAVEMENT MARKING LINE 4"	FOOT	1260	920	340
* 78005130	EPOXY PAVEMENT MARKING LINE 6"	FOOT	315	230	85
* 78005140	EPOXY PAVEMENT MARKING LINE 8"	FOOT	800	400	400
X4210300	WIDE FLANGE BEAM JOINT REMOVAL	EACH	4	4	
Z0075310	TIE BARS 3/4"	EACH	226	184	42

* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE 06/09/2005

DRAWN BY RLW
 CHECKED BY _____

Date: 06/15/2005
File: c:\projects\main06\cm321\details.dgn