

district
 6/29/2005
 ::\projects\74098d\02605pa.dgn
 GN & I

| FAP NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------------------|---------|--------|----------------------|-----------|
| 322 | 26-JI | MARION | 6 | 2 |
| FED. ROAD DIST. NO. 1 | | BLANKS | FED. AID PROJECT NO. | |

CONTRACT NO. 74098

GENERAL NOTES

THE WORK INCLUDED IN THIS SECTION 26JI CONSISTS OF NEW GUARDRAIL, CHANNEL CLEANING, RIPRAP AND ANY OTHER WORK NECESSARY TO COMPLETE THE SECTION.

ANY SPOIL MATERIAL EXCAVATED, DREDGED OR OTHERWISE PRODUCED MUST NOT BE RETURNED TO THE WATERWAY BUT MUST BE DEPOSITED IN A SELF-CONTAINED AREA IN COMPLIANCE WITH ALL STATE STATUTES, REGULATIONS AND PERMIT REQUIREMENTS WITH NO DISCHARGE TO WATERS OF THE STATE UNLESS A PERMIT HAS BEEN ISSUED BY THE ILLINOIS EPA.

DUE TO A PETROLEUM PIPELINE AT STA. 733+22 AND AT STA. 815+36, NO MACHINERY IS ALLOWED IN THE STREAM IN ORDER TO EXCAVATE MATERIAL. ALL WORK WILL BE DONE FROM THE SHOULDER ABOVE THE STREAM CHANNEL.

RIPRAP SHALL BE PLACED THE SAME DAY THE EXCAVATION OF THE STREAM CHANNEL OCCURS IN ORDER TO MINIMIZE ANY EROSION.

ALL ERODABLE BARE EARTH AREAS DISTURBED DURING CONSTRUCTION SHALL BE FERTILIZED, SEEDED, AND MULCHED WHEN CONSTRUCTION IS COMPLETE. SEEDING SHALL BE CLASS 2 (SPECIAL) AND IS NOT TO BE PAID FOR SEPERATLEY, BUT SHALL BE INCLUDED WITH THE COST OF CHANNEL EXCAVATION.

THE LOCATIONS AND/OR DEPTHS OF UNDERGROUND UTILITIES SHOWN HAVE BEEN TAKEN FROM INFORMATION FURNISHED BY THE UTILITY OWNERS AND MUST BE CONSIDERED APPROXIMATE. FIELD MARKINGS OF FACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800-892-0123.

THE CONTRACTOR SHALL REPAIR THE AGGREGATE SHOULDER TO ITS EXISTING CONDITION WHEN CONSTRUCTION IS COMPLETE. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE PROJECT.

EXCAVATION FOR RIPRAP IS INCLUDED IN THE COST OF CHANNEL EXCAVATION.

INDEX OF SHEETS

| SHEET NO. | DESCRIPTION |
|-----------|--|
| 1 | COVER SHEET |
| 2 | GENERAL NOTES, INDEX OF SHEETS & LIST OF STANDARDS |
| 3 | SUMMARY OF QUANTITIES |
| 4 | DETAILS |
| 5-6 | PLAN SHEETS |
| | STANDARDS |

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER THE STANDARDS

| STD. NO. | DESCRIPTION |
|-----------|--|
| 000001-04 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 001006 | DECIMAL OF AN INCH AND OF A FOOT |
| 630001-05 | STEEL PLATE BEAM GUARDRAIL |
| 630301-03 | SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS |
| 635006-02 | REFLECTOR AND TERMINAL MARKER PLACEMENT |
| 635011-01 | REFLECTOR MARKER AND MOUNTING DETAILS |
| 701001-01 | OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 4.5 m (15') AWAY |
| 701006-02 | OFF-ROAD OPERATIONS 2L, 2W, 4.5 m (15') TO 600 mm (24") FROM PAVEMENT EDGE |
| 701201-02 | LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS >= 45 MPH |
| 702001-05 | TRAFFIC CONTROL DEVICES |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

**GENERAL NOTES
&
INDEX OF SHEETS**

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____