

SUMMARY OF QUANTITIES

CODE	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 20% STATE - 80% FEDERAL			
				RURAL SECTION STA 149+00 - 292+57		URBAN SECTION STA 292+57 - 336+00	
				I000-2A	SFTY-3N	I000-2A	SFTY-3N
60108300	PIPE UNDERDRAINS 8" (SPECIAL)	FOOT	34	34			
60218400	MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	1		2	
60218500	MANHOLES, TYPE A, 4' - DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2			2	
60219540	MANHOLES, TYPE A, 4' - DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1			1	
60220105	MANHOLES, TYPE A, 4' - DIAMETER, WITH MEDIAN INLET (604106)	EACH	3	3			
60223800	MANHOLES, TYPE A, 6' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2	
60223810	MANHOLES, TYPE A, 6' - DIAMETER, TYPE 3 FRAME AND GRATE	EACH	4			4	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	6			6	
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	5			5	
60240366	INLETS, TYPE B, WITH MEDIAN INLET (604106)	EACH	6	5		1	
60246605	MEDIAN INLET (604101)	EACH	5	5			
60246805	MEDIAN INLET (604106)	EACH	3	3			
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3			3	
60500040	REMOVING MANHOLES	EACH	3			3	
60500060	REMOVING INLETS	EACH	4	2		2	
60600605	CONCRETE CURB, TYPE B	FOOT	530			530	
60600805	CONCRETE CURB, TYPE B (DOWELLED)	FOOT	1284	1284			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3209	954		2255	
60617800	PAVED FLUME	FOOT	10			10	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	11683	11683			
60619000	CONCRETE MEDIAN, TYPE SB (MODIFIED)	SQ FT	3606	1500		2106	
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	512.5	512.5			
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2			
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2			
63200310	GUARDRAIL REMOVAL	FOOT	2803	2803			
63500105	DELINEATORS	EACH	162	162			
64200105	SHOULDER RUMBLE STRIPS	FOOT	59327	50950		8377	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	172	140		32	
66700045	PERMANENT SURVEY MARKERS	EACH	29	24		5	
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	349	349			
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1			
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	30	30			
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	30	30			
67100100	MOBILIZATION	L SUM	1	1			
70100304	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	EACH	3	3			
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1			1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	35			35	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	15322	11816		3506	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	625	435		190	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	139240	102425		36815	

SUMMARY OF QUANTITIES

CODE	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 20% STATE - 80% FEDERAL			
				RURAL SECTION STA 149+00 - 292+57		URBAN SECTION STA 292+57 - 336+00	
				I000-2A	SFTY-3N	I000-2A	SFTY-3N
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	165	165			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	431	226		205	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	362	326		36	
70300290	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1360	1170		190	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17615	14114		3501	
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	1140	950		190	
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	430	300		130	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	1064	902		162	
* 72000200	SIGN PANEL - TYPE 2	SQ FT	234	208		26	
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	6	3		3	
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	11	7		4	
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	343	235		108	
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	34	34			
* 72500100	OBJECT MARKER - TYPE 1	EACH	15	15			
* 72900200	METAL POST - TYPE B	FOOT	580	555		25	
* 73000100	WOOD SIGN SUPPORT	FOOT	2313	1961		352	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	960	702		258	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	135899	115573		20326	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	997	739		258	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	650	482		168	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	604	484		120	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1510	1238		272	
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	11	11			
* 78200300	PRISMATIC CURB REFLECTOR	EACH	60	60			
* 78200405	GUARDRAIL MARKERS	EACH	20	20			
* 78200500	BARRIER WALL MARKERS	EACH	342	285		57	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	12824	7674		5150	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	382	262		120	
X5400650	PRECAST CONCRETE BOX CULVERT 3.5' X 1.5'	FOOT	190			190	
X0325111	PAVED DITCH (MODIFIED)	FOOT	250			250	
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	1	1			
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	710	710			
* A2001014	TREE, ACER RUBRUM (RED MAPLE), 1 - 3/4" CALIPER, BALLED AND BURLAPPED	EACH	14	14			

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 3 OF 4 SHEETS
 F.A.P. 103 (IL. RTE. 13/15)
 SECTION 27-1R - ST. CLAIR CO.
 SCALE: _____ DRAWN BY YBA
 DATE March 21, 2005 CHECKED BY RCY