

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	27-1R	ST. CLAIR	382	83
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 76300				

STAGE 2

TEMPORARY PAVEMENT MARKINGS								REMARKS	
STATION	TO STATION	ALIGNMENT	SIDE	TEMP PVMT MARKING LINE 4" WHITE FOOT	TEMP PVMT MARKING LINE 4" YELLOW FOOT	TEMP PVMT MARKING LINE 24" WHITE FOOT	TEMP PVMT MARKING L & S SQ FT		
161+25	165+50	FAP 103	CL		850			DOUBLE YELLOW	
165+50	191+50	FAP 103	CL		650			YELLOW SKIP-DASH	
183+60	191+50	FAP 103	CL		790			YELLOW CENTERLINE	
191+50	205+75	FAP 103	CL		2850			DOUBLE YELLOW	
207+00	230+00	FAP 103	CL		2300			DOUBLE YELLOW	
262+00	265+00	FAP 103	CL		300			YELLOW CENTERLINE	
262+00	292+57	FAP 103	CL		764			YELLOW SKIP-DASH	
266+25	278+25	FAP 103	CL		1200			YELLOW CENTERLINE	
151+10		FAP 103	LT				13.6	1 LEFT TURN ARROW	
156+00	180+10	FAP 103	LT	2410				WHITE EDGE LINE	
181+25	206+00	FAP 103	LT	2475				WHITE EDGE LINE	
207+20	226+00	FAP 103	LT	1880				WHITE EDGE LINE	
262+00	276+25	FAP 103	LT	1425				WHITE EDGE LINE	
291+00	292+57	FAP 103	LT	157				WHITE EDGE LINE	
150+25	151+10	FAP 103	LT	85				WHITE LANE LINE	
148+85	156+00	FAP 103	LT	179				WHITE SKIP-DASH	
150+00	161+25	FAP 103	LT		1125			YELLOW EDGE LINE	
181+00		AR	RT			39		STOP BAR	
206+50		AR	RT			29		STOP BAR	
217+00		AR	RT			30		STOP BAR	
252+00		AR	RT			33		STOP BAR	
148+85	179+75	FAP 103	RT	3090				WHITE EDGE LINE	
181+25	205+75	FAP 103	RT	2450				WHITE EDGE LINE	
207+00	226+00	FAP 103	RT	1900				WHITE EDGE LINE	
262+00	292+57	FAP 103	RT	3057				WHITE EDGE LINE	
148+85	161+25	FAP 103	RT		1240			YELLOW EDGE LINE	
TOTALS (RURAL)					19108	12069	131	13.6	
292+57	294+68	FAP 103	CL		53			YELLOW SKIP-DASH	
294+68	304+50	FAP 103	CL		1964			DOUBLE YELLOW	
304+50	336+00	FAP 103	CL		788			YELLOW SKIP-DASH	
313+80	319+00	FAP 103	CL		520			YELLOW CENTERLINE	
292+57	297+50	FAP 103	LT	493				WHITE EDGE LINE	
298+50	336+00	FAP 103	LT	3750				WHITE EDGE LINE	
292+57	304+75	FAP 103	RT	1218				WHITE EDGE LINE	
306+00	336+00	FAP 103	RT	3000				WHITE EDGE LINE	
TOTALS (URBAN)					8461	3272			

STAGE 2

PAVEMENT MARKING REMOVAL							
STATION	TO STATION	ALIGNMENT	SIDE	PAVEMENT MARKING REMOVAL SQ FT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	REMARKS	
149+00	153+00	FAP 103	RT		133	WHITE EDGE LINE	
148+85	149+50	FAP 103	LT		22	WHITE LANE LINE	
150+00	158+50	FAP 103	LT		283	YELLOW EDGE LINE	
150+25	151+20	FAP 103	LT		24	DOTTED LINE	
158+50	160+00	FAP 103	LT		100	DOUBLE YELLOW	
154+00	158+50	FAP 103	LT		150	YELLOW EDGE LINE	
158+50	161+00	FAP 103	LT		83	WHITE EDGE LINE	
222+00	226+00	FAP 103	RT	133		WHITE EDGE LINE	
222+50	226+00	FAP 103	CL	233		DOUBLE YELLOW	
231+50	233+00	FAP 103	LT	50		WHITE EDGE LINE	
251+25	252+25	FAP 103	RT	33		WHITE EDGE LINE	
262+00	265+00	FAP 103	CL	100		YELLOW CENTERLINE	
262+00	265+00	FAP 103	CL	25		YELLOW SKIP-DASH	
262+00	266+00	FAP 103	RT	133		WHITE EDGE LINE	
276+25	277+50	FAP 103	LT	42		WHITE EDGE LINE	
276+30	277+40	FAP 103	LT	37		WHITE EDGE LINE	
TOTALS (RURAL)					786	795	
297+50	298+40	FAP 103	CL	30		YELLOW CENTERLINE	
297+50	298+50	FAP 103	RT	33		WHITE EDGE LINE	
297+50	298+40	FAP 103	CL	8		YELLOW SKIP-DASH	
302+00	336+00	FAP 103	RT	1133		WHITE EDGE LINE	
306+00	307+00	FAP 103	CL	67		DOUBLE YELLOW	
307+00	314+00	FAP 103	CL	933		2 DOUBLE YELLOW LINES	
307+00	314+00	FAP 103	CL	380		DIAGONAL LINES	
314+00	336+00	FAP 103	CL	183		YELLOW SKIP-DASH	
TOTALS (URBAN)					2767	0	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
TRAFFIC CONTROL - STAGE 2 SCHEDULE
 F.A.P. 103 (IL. RTE. 13/15)
 SECTION 27-1R - ST. CLAIR CO.
 SCALE: NONE DRAWN BY CRO
 DATE February 11, 2005 CHECKED BY RCY