F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	27-1R	ST. CLAIR	382	91
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 76300

STAGE 3

TEMPORARY PAVEMENT MARKINGS

STATION	TO STATION	ALIGNMENT	SIDE	TEMP PVMT MARKING LINE 4" WHITE FOOT	TEMP PVMT MARKING LINE 4" YELLOW FOOT	TEMP PVMT MARKING LINE 12" WHITE FOOT	TEMP PVMT MARKING LINE 24" WHITE FOOT	TEMP PVMT MARKING L & S SQ FT	REMARKS
181+75	183+25	F.A.P. 103	LT.					40.8	3 LEFT TURN ARROWS
207+25	209+75	F.A.P. 103	LT.					40.8	3 LEFT TURN ARROWS
202+00	205+25	F.A.P. 103	RT.					40.8	3 LEFT TURN ARROWS
207+25	209+75	F.A.P. 103	LT.					40.8	3 RIGHT TURN ARROWS
224+00	237+25	F.A.P. 103	LT.		2650				DOUBLE YELLOW
224+00	225+25	F.A.P. 103	LT.		250				DOUBLE YELLOW
244+75	248+00	F.A.P. 103	LT.		650				DOUBLE YELLOW
255+75	260+00	F.A.P. 103	LT.		850				DOUBLE YELLOW
180+25		AR	LT.				30		STOP BAR
206+25		JEFF	LT.				30		STOP BAR
232+00		AR	LT.				33		STOP BAR
276+75		AR	LT.				28		STOP BAR
184+00	186+50	F.A.P. 103	LT.	63					WHITE DOTTED LINE
209+86	212+61	F.A.P. 103	LT.	69					WHITE DOTTED LINE
209+86	212+61	F.A.P. 103	LT.	69					WHITE DOTTED LINE
174+75	177+25	F.A.P. 103	RT.	63					WHITE DOTTED LINE
200+00	202+60	F.A.P. 103	RT.	65					WHITE DOTTED LINE
190+50	201+50	F.A.P. 103	LT.	1100					WHITE EDGE LINE
206+50	231+50	F.A.P. 103	LT.	2500					WHITE EDGE LINE
226+75	231+50	F.A.P. 103	LT.	475					WHITE EDGE LINE
232+75	251+00	F.A.P. 103	LT.	1825					WHITE EDGE LINE
233+00	272+00	F.A.P. 103	LT.	3900					WHITE EDGE LINE
252+25	272+00	F.A.P. 103	LT.	1975					WHITE EDGE LINE
277+25	292+57	F.A.P. 103	LT.	1532					WHITE EDGE LINE
285+00	292+57	F.A.P. 103	LT.	757					WHITE EDGE LINE
219+00	226+75	F.A.P. 103	RT.	775					WHITE EDGE LINE
206+50	209+86	F.A.P. 103	LT.	303		70			WHITE EDGE LINE AND ISLAND
148+85	149+50	F.A.P. 103	LT.	65					WHITE LANE LINE
181+00	184+00	F.A.P. 103	LT.	300					WHITE LANE LINE
206+83	209+86	F.A.P. 103	LT.	303					WHITE LANE LINE
205+30	205+75	F.A.P. 103	RT.	45					WHITE LANE LINE
167+40	205+90	F.A.P. 103	LT.	963					WHITE SKIP-DASH
206+75	224+00	F.A.P. 103	LT.	431					WHITE SKIP-DASH
162+00	205+75	F.A.P. 103	RT.	1094					WHITE SKIP-DASH
237+25	244+75	F.A.P. 103	LT.		750				YELLOW CENTERLINE
248+00	250+00	F.A.P. 103	LT.		200				YELLOW CENTERLINE
254+75	255+75	F.A.P. 103	LT.		100				YELLOW CENTERLINE
260+00	265+00	F.A.P. 103	LT.		500				YELLOW CENTERLINE
266+00	272+00	F.A.P. 103	LT.		600				YELLOW CENTERLINE
153+50	167+40	F.A.P. 103	LT.		1390				YELLOW EDGE LINE
167+40	180+00	F.A.P. 103	LT.		1260				YELLOW EDGE LINE
181+25	205+75	F.A.P. 103	LT.		2450				YELLOW EDGE LINE
207+00	224+00	F.A.P. 103	LT.		1700				YELLOW EDGE LINE
161+25	162+00	F.A.P. 103	RT.		75				YELLOW EDGE LINE
162+00	180+00	F.A.P. 103	RT.		1800				YELLOW EDGE LINE
181+25	205+75	F.A.P. 103	RT.		2450				YELLOW EDGE LINE
206+75	224+00	F.A.P. 103	RT.		1725				YELLOW EDGE LINE
237+25	244+75	F.A.P. 103	LT.		188				YELLOW SKIP-DASH
248+00	255+75	F.A.P. 103	LT.		194				YELLOW SKIP-DASH
260+00	292+50	F.A.P. 103	LT.		813				YELLOW SKIP-DASH
TOTALS (RURAL)				18672	20,595	70	121	163.2	
305+75	336+00	F.A.P. 103	CL					152.0	20 LEFT TURN ARROWS
292+57	297+00	F.A.P. 103	LT.		886				DOUBLE YELLOW
297+75		F.A.P. 103	LT.				36		STOP BAR
292+57	297+50	F.A.P. 103	LT.	493					WHITE EDGE LINE
292+57	297+50	F.A.P. 103	LT.	493					WHITE EDGE LINE
298+50	332+75	F.A.P. 103	LT.	3425					WHITE EDGE LINE
333+25	338+10	F.A.P. 103	LT.	485					WHITE EDGE LINE
297+50	304+50	F.A.P. 103	RT.	700					WHITE EDGE LINE
305+75	338+10	F.A.P. 103	RT.	3235					WHITE EDGE LINE
305+75	317+75	F.A.P. 103	LT.	300					WHITE SKIP-DASH
305+75	327+50	F.A.P. 103	RT.	544					WHITE SKIP-DASH
298+25	304+50	F.A.P. 103	LT.		625				YELLOW EDGE LINE
298+25	304+50	F.A.P. 103	LT.		625				YELLOW EDGE LINE
305+75	336+00	F.A.P. 103	LT.		757				YELLOW SKIP DASH
305+75	336+00	F.A.P. 103	RT.		757				YELLOW SKIP DASH
305+75	336+00	F.A.P. 103	LT.		3025				YELLOW LANE LINE
305+75	336+00	F.A.P. 103	RT.		3025				YELLOW LANE LINE
TOTALS (URBAN)				9675	9700		36	152.0	

STAGE 3

PAVEMENT MARKING REMOVAL

STATION	TO STATION	ALIGNMENT	SIDE	PAVEMENT MARKING REMOVAL SQ FT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	REMARKS
161+00	190+50	FAP 103	LT	983		WHITE EDGE LINE
201+50	205+75	FAP 103	LT	175		WHITE EDGE LINE
207+00	217+40	FAP 103	LT	347		WHITE EDGE LINE
217+75	218+50	FAP 103	LT	25		WHITE EDGE LINE
201+50	206+00	FAP 103	LT	300		DOUBLE YELLOW
201+50	204+20	FAP 103	LT	450		MEDIAN
206+50	210+00	FAP 103	LT	528		MEDIAN
210+00	221+00	FAP 103	LT	733		DOUBLE YELLOW
276+00	278+00	FAP 103	LT	67		WHITE EDGE LINE
276+25	277+50	FAP 103	LT	42		WHITE EDGE LINE
183+75	190+50	FAP 103	LT	225		YELLOW CENTERLINE
161+00	190+50	FAP 103	LT	246		YELLOW SKIP-DASH
204+85	206+00	FAP 103	LT	38		WHITE LANE LINE
200+50	204+85	FAP 103	LT	36		WHITE DOTTED LINE
203+25	206+00	FAP 103	LT	27		2 LEFT TURN ARROWS
159+00	161+25	FAP 103	LT		75	YELLOW LINE
156+00	160+50	FAP 103	LT		150	WHITE EDGE LINE
161+25	165+50	FAP 103	RT		283	DOUBLE YELLOW
165+50	191+50	FAP 103	RT		217	YELLOW SKIP-DASH
191+50	205+75	FAP 103	RT		950	DOUBLE YELLOW
207+00	223+00	FAP 103	RT		1066	DOUBLE YELLOW
162+00	177+25	FAP 103	RT		508	WHITE EDGE LINE
179+50	180+00	FAP 103	RT		50	WHITE EDGE LINE
181+25	202+60	FAP 103	RT		712	WHITE EDGE LINE
205+40	205+90	FAP 103	RT		50	WHITE EDGE LINE
206+80	223+00	FAP 103	RT		540	WHITE EDGE LINE
183+50	191+50	FAP 103	RT		267	YELLOW CENTERLINE
TOTALS (RURAL)				4222	4868	
297+50	300+00	FAP 103	LT	83		WHITE EDGE LINE
300+00	336+00	FAP 103	LT	1200		WHITE EDGE LINE
297+50	300+00	FAP 103	LT	83		YELLOW CENTERLINE
297+50	300+00	FAP 103	LT	21		YELLOW SKIP-DASH
300+00	305+10	FAP 103	RT	680		2 DOUBLE YELLOW
300+00	305+10	FAP 103	RT	240		DIAGONAL LINES
300+00	336+00	FAP 103	RT		1200	WHITE EDGE LINE
300+00	304+50	FAP 103	RT		300	DOUBLE YELLOW
313+75	319+00	FAP 103	RT		175	YELLOW CENTERLINE
305+85	307+00	FAP 103	RT	38		YELLOW LANE LINE
305+85	307+00	FAP 103	RT	38		YELLOW LANE LINE
304+50	336+00	FAP 103	RT		263	YELLOW SKIP-DASH
TOTALS (URBAN)				2383	1938	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL - STAGE 3 SCHEDULE

F.A.P. 103 (IL. RTE. 13/15)
SECTION 27-1R - ST. CLAIR CO.

SCALE: NONE DRAWN BY CRO
DATE Febuary 11, 2005 CHECKED BY RCY

J:\2002\02056\000\civil\dgn\traffic_controlschedule_stage_3.dgn 3/9/2005 12:26:13 PM