



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 9, 2005

SUBJECT: FAI Route 55 (I-55)  
Section 60-(1,2) I-2  
Madison County  
Contract No. 76940  
Item No. 53, September 23, 2005 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Revised pages 6 and 7 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine  
Engineer of Design  
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Mary Lamie, Region 5, District 8; Roger Driskell; Estimates; Design & Environment File

DB/dp

## TABLE OF CONTENTS

LOCATION OF PROJECT .....	4
DESCRIPTION OF PROJECT.....	4
MOW STRIP .....	4
HIGH TENSION CABLE MEDIAN BARRIER SYSTEM (EXPERIMENTAL, BRIFEN).....	5
PAYROLLS AND PAYROLL RECORDS (BDE) .....	6
MONTHLY LABOR SUMMARY AND ACTIVITY REPORTING SYSTEM .....	7
SEEDING .....	10
D-8 TEMPORARY EROSION CONTROL .....	10
TRAFFIC CONTROL PLAN .....	11
CONSTRUCTION AND MAINTENANCE SIGN SUPPORTS .....	12
STATUS OF UTILITIES TO BE ADJUSTED .....	13
CONCRETE ADMIXTURES (BDE) .....	13
CURING AND PROTECTION OF CONCRETE CONSTRUCTION (BDE) .....	18
FLAGGER VESTS (BDE) .....	26
FREEZE-THAW RATING (BDE).....	27
MINIMUM LANE WIDTH WITH LANE CLOSURE (BDE).....	27
MULCHING SEEDED AREAS (BDE) .....	27
PARTIAL PAYMENTS (BDE).....	28
PAYMENTS TO SUBCONTRACTORS (BDE) .....	29
PERSONAL PROTECTIVE EQUIPMENT (BDE) .....	30
PORTABLE CHANGEABLE MESSAGE SIGNS (BDE) .....	30
PORTLAND CEMENT (BDE).....	31
PORTLAND CEMENT CONCRETE (BDE) .....	31
PUBLIC CONVENIENCE AND SAFETY (BDE) .....	32
RAP FOR USE IN BITUMINOUS CONCRETE MIXTURES (BDE).....	32
STABILIZED SUBBASE AND BITUMINOUS SHOULDERS SUPERPAVE (BDE).....	36
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) .....	41
SUBGRADE PREPARATION (BDE) .....	42
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) .....	48
TRUCK BED RELEASE AGENT (BDE) .....	49
WEIGHT CONTROL DEFICIENCY DEDUCTION.....	49
WORK ZONE PUBLIC INFORMATION SIGNS (BDE) .....	51
WORK ZONE SPEED LIMIT SIGNS (BDE) .....	51
WORK ZONE TRAFFIC CONTROL (BDE) .....	52
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) .....	53
WORKING DAYS (BDE) .....	54
STEEL COST ADJUSTMENT (BDE).....	54

## CONSTRUCTION REQUIREMENTS

General. The dynamic deflection of the system, per NCHRP 350 Test Number 3-11, shall have a working range of 1.5 to 2.4 m (5 to 8 ft). Where the dynamic deflection of the system must be limited, those locations will be shown on the plans and the post spacing shall be adjusted as required to provide the specified deflection.

The posts shall be placed in sockets set in either precast or cast-in-place portland cement concrete foundations. When the barrier system will be placed in a paved area, holes shall be cored prior to placing the post foundations or driving the posts.

Upon completion of the installation, an on-site, hands-on, presentation shall be made for the Department. This presentation shall be scheduled at the convenience of the Engineer and shall include instruction for the inspection, maintenance, emergency opening, and repair of the system.

Replacement Parts. The following replacement parts shall be furnished to the Department for system maintenance: two spools of cable, each 1000 ft (610 m); splicing/swaging hardware for 12 cable splices; posts and necessary hardware to replace 50 posts per mile of system installed; and material and hardware, exclusive of cable and ground anchors, to completely replace two cable terminals from the end of the system to the point where the post and cable assembly becomes uniform.

Method of Measurement. This work will be measured for payment in place, in meters (feet). The length will be measured along the top cable from anchorage to anchorage.

Basis of Payment. This work will be paid for at the contract unit price per meter (foot) for HIGH TENSION CABLE MEDIAN BARRIER SYSTEM.

### **PAYROLLS AND PAYROLL RECORDS (BDE)**

Effective: August 10, 2005

FEDERAL AID CONTRACTS. Add the following State of Illinois requirements to the Federal requirements contained in Section V of Form FHWA-1273:

"The payroll records shall include each worker's name, address, telephone number, social security number, classification, rate of pay, number of hours worked each day, starting and ending times of work each day, total hours worked each week, itemized deductions made, and actual wages paid.

The Contractor and each subcontractor shall submit payroll records to the Engineer each week from the start to the completion of their respective work. The submittals shall be on the Department's form SBE 48, or an approved facsimile. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate box ("No Work", "Suspended", or "Complete") checked on the form."

Revised 9/9/05

STATE CONTRACTS. Revise Section IV of Check Sheet #5 of the Recurring Special Provisions to read:

**“IV. COMPLIANCE WITH THE PREVAILING WAGE ACT**

1. **Prevailing Wages.** All wages paid by the Contractor and each subcontractor shall be in compliance with The Prevailing Wage Act (820 ILCS 130), as amended, except where a prevailing wage violates a federal law, order, or ruling, the rate conforming to the federal law, order, or ruling shall govern. The Contractor shall be responsible to notify each subcontractor of the wage rates set forth in this contract and any revisions thereto. If the Department of Labor revises the wage rates, the Contractor will not be allowed additional compensation on account of said revisions.
2. **Payroll Records.** The Contractor and each subcontractor shall make and keep, for a period of three years from the date of completion of this contract, records of the wages paid to his/her workers. The payroll records shall include each worker’s name, address, telephone number, social security number, classification, rate of pay, number of hours worked each day, starting and ending times of work each day, total hours worked each week, itemized deductions made, and actual wages paid. Upon two business days’ notice, these records shall be available, at all reasonable hours at a location within the State, for inspection by the Department or the Department of Labor.
3. **Submission of Payroll Records.** The Contractor and each subcontractor shall submit payroll records to the Engineer each week from the start to the completion of their respective work. The submittals shall be on the Department’s form SBE 48, or an approved facsimile. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate box (“No Work”, “Suspended”, or “Complete”) checked on the form.

Each submittal shall be accompanied by a statement signed by the Contractor or subcontractor which avers that: (i) such records are true and accurate; (ii) the hourly rate paid to each worker is not less than the general prevailing rate of hourly wages required by the Act; and (iii) the Contractor or subcontractor is aware that filing a payroll record that he/she knows to be false is a Class B misdemeanor.

4. **Employee Interviews.** The Contractor and each subcontractor shall permit his/her employees to be interviewed on the job, during working hours, by compliance investigators of the Department or the Department of Labor.”

**MONTHLY LABOR SUMMARY AND ACTIVITY REPORTING SYSTEM**

Effective: 1-1-1995

Revised June 2001

**I. Monthly Labor Summary Report, Form SBE 148**

The prime contractor and each first and second tier sub-contractor, (hereinafter referred to as “subcontractor”) shall submit a certified Monthly Labor Summary Report directly to the District Engineer.

This report is in lieu of submittal of the Monthly Workforce Analysis Report, Form SBE 956.

This report must be received in District Eight no later than the tenth day of the next month.

This Report shall be submitted by the prime contractor and each subcontractor, for each consecutive month, from the start, to the completion of their work on the contract.

Revised 9/9/05