

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
05-F3000-01-BT	COOK	92	3
STA. TO STA.			
IDOT PROJECT NO. CMM-8003(498)			
SALT CREEK GREENWAY TRAIL			
CONTRACT NO. 83667			

CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY	FOREST PRES. DIST. COOK COUNTY BUSSE WOODS (1)		FOREST PRES. DIST. COOK COUNTY (2)		VILLAGE OF LYONS (3)	
				BIKEWAY	SIGNALS	BIKEWAY	SIGNALS	BIKEWAY	SIGNALS
				Y047	Y03IF	Y047	Y03IF	Y047	Y03IF
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	3,073	48		3025			
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,185			1185			
20101200	TREE ROOT PRUNING	EACH	9			9			
M2020010	EARTH EXCAVATION	CU M	473	10		463			
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	8,357	1073		7204		80	
M2040800	FURNISHED EXCAVATION	CU M	6,972	1311		5613		48	
M2070420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU M	960	120		820		20	
M2080150	TRENCH BACKFILL	CU M	34	6		28			
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	22,158	2693		19120		345	
M2113150	TOPSOIL FURNISH AND PLACE, 150 MM	SQ M	31,666	2724		28809		133	
M2500115	SEEDING, CLASS 1B	HA	1.8	0.1		1.6		0.1	
M2500312	SEEDING, CLASS 4A	HA	1.6	0.2		1.3		0.1	
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	319	28		289		2	
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	319	28		289		2	
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	319	28		289		2	
M2510105	MULCH, METHOD 1	HA	3.3	0.3		2.9		0.1	
M2510630	EROSION CONTROL BLANKET	SQ M	1,500	200		1300			
M2520110	SODDING, SALT TOLERANT	SQ M	100			100			
M2520200	SUPPLEMENTAL WATERING	UNIT	7	1		5		1	
28000300	TEMPORARY DITCH CHECKS	EACH	21	4		17			
M2800400	PERIMETER EROSION BARRIER	METER	2,687	455		2232			
28000500	INLET AND PIPE PROTECTION	EACH	17	3		14			
M3511150	AGGREGATE BASE COURSE, TYPE B 150 MM	SQ M	15,844	1941		13674		229	
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	42,839	1941		40669		229	
M4205200	PROTECTIVE COAT	SQ M	78	10		54		14	
M4240150	PORTLAND CEMENT CONCRETE SIDEWALK 150MM	SQ M	140	6		116		18	
M4402000	PAVEMENT REMOVAL	SQ M	27,895			27895			
M4402045	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	METER	71	11		45		15	
M4402050	SIDEWALK REMOVAL	SQ M	134			14		120	
M5010522	PIPE CULVERT REMOVAL	METER	28			28			
M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	12			12			
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	20	6		14			
M542H020	PIPE CULVERTS, CLASS A, TYPE 1 300MM	METER	34			34			
M542H030	PIPE CULVERTS, CLASS A, TYPE 1 450MM	METER	70	22		48			
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2			2			
60255500	MANHOLES TO BE ADJUSTED	EACH	1			1			
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1			1			
M6320030	GUARDRAIL REMOVAL	METER	17			17			
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	12			12			
67100100	MOBILIZATION	L SUM	1			1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1			1			
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1			1			
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	1			1			

REVISIONS		
NO.	NAME	DATE

URS 1701 GOLF ROAD, SUITE 1000 TEL (847) 228-0707
ROLLING MEADOWS, IL 60008 FAX (847) 228-1115

FOREST PRESERVE DISTRICT OF COOK COUNTY
SALT CREEK GREENWAY TRAIL

SUMMARY OF QUANTITIES

DATE: 7/01/05 DRAWN BY: XXX
DESIGNED BY: MIA CHECKED BY: DDL