

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
---	---	---	12	3
STA. -----		TO STA. -----		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

## SUMMARY OF QUANTITIES

### VARIOUS ROUTES

LOC. 1	LOC. 2	LOC. 3
ILL 142	ILL 13/US 45	ILL 146/MAIN ST.
RURAL	URBAN (HARRISBURG)	URBAN (ANNA)
100% STATE		
ROADWAY		
J000		

•VARIOUS  
 •D9 CONT MAINT FY 06-1  
 •••VARIOUS

PAY CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY
X4200830	PORTLAND CEMENT CONCRETE INLAY 3 INCH	SQ YD	108		45	63
X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	160	160		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1			1
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	485	485		
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10 INCH	SQ YD	445	445		
42001200	PAVEMENT FABRIC	SQ YD	445	445		
42001300	PROTECTIVE COAT	SQ YD	445	445		
44000100	PAVEMENT REMOVAL	SQ YD	427	427		
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	108		45	63
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	25	25		
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	977	977		
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	20	20		
44213200	SAW CUTS	FOOT	835		351	484
48101200	AGGREGATE SHOULDERS, TYPE B	TON	243	243		
48202880	BITUMINOUS SHOULDERS, SUPERPAVE 14"	SQ YD	815	815		
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	25	25		
67100100	MOBILIZATION	L SUM	1	0.4	0.3	0.3
70100450	TRAFFIC CONTROL & PROTECTION 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL & PROTECTION 701306	L SUM	1	1		
70102635	TRAFFIC CONTROL & PROTECTION 701701	L SUM	1		0.5	0.5
* 78008210	POLYUREA PAVEMENT MARKING, TYPE I - LINE 4"	FOOT	501	501		
* 78008270	POLYUREA PAVEMENT MARKING, TYPE I - LINE 24"	FOOT	12		12	

\*SPECIALTY ITEMS

PLOT DATE = 7/7/2005  
 FILE NAME = c:\prow\proj\98923\9892305.dwg  
 PLOT SCALE = 1/8" = 1'-0"  
 USER NAME = mcdonald