

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9477	05-00051-00-RP	FRANKLIN	23	3
CITY OF WEST FRANKFORT		CLEVELAND STREET		

CONTRACT NO. 99234

SUMMARY OF QUANTITIES

J000

CODE NO.	PAY ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	135
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	118
20200100	EARTH EXCAVATION	CU YD	3,150
20800150	TRENCH BACKFILL	CU YD	282.1
*25000900	SEEDING, CLASS 1 (SPECIAL)	ACRE	0.6
25100630	EROSION CONTROL BLANKET	SQ YD	2,910
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150
28000300	TEMPORARY DITCH CHECKS	EACH	1
28000400	PERIMETER EROSION BARRIER	FOOT	700
28000500	INLET AND PIPE PROTECTION	EACH	30
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	1,200
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	300
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	235.7
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1,124
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	114.8
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	345
44000600	SIDEWALK REMOVAL	SQ FT	908
50300225	CONCRETE STRUCTURES	CU YD	5
50800105	REINFORCEMENT BARS	POUND	20
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	488
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	138
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	347
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	327
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	103
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	65
55100400	STORM SEWER REMOVAL 10"	FOOT	10
55100500	STORM SEWER REMOVAL 12"	FOOT	402
55100900	STORM SEWER REMOVAL 18"	FOOT	192
55101200	STORM SEWER REMOVAL 24"	FOOT	205
55101400	STORM SEWER REMOVAL 30"	FOOT	12
Δ 56100600	WATER MAIN 6"	FOOT	920
Δ*56104900	WATER VALVES 6"	EACH	2
Δ*56108710	TAPPING VALVES AND SLEEVES 4"	EACH	1
Δ*56108800	TAPPING VALVES AND SLEEVES 6"	EACH	2
Δ 56200200	WATER SERVICE LINE 3/4"	FOOT	600
*60223100	MANHOLE, TYPE A, SPECIAL, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
*60242900	INLET, SPECIAL, TYPE 1	EACH	4
*60243300	INLET, SPECIAL, TYPE 3, 5'	EACH	24
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4
60500060	REMOVING INLETS	EACH	7
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12
67100100	MOBILIZATION	L SUM	1
Δ 72000100	SIGN PANEL - TYPE 1	SQ FT	66.75
Δ 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	170

J000

CODE NO.	PAY ITEM	UNIT	QUANTITY
Δ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	320
Δ 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	199
Δ 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	150
*LR420125	PORTLAND CEMENT CONCRETE PAVEMENT 7" (SPECIAL) WITH INTEGRAL CURB	SQ YD	4,875
*Z0075300	TIE BARS	EACH	22
Δ*XX005889	12" PVC WATERMAIN ENCASEMENT	FOOT	60
Δ*XX005890	DETECTION WIRE	FOOT	920
Δ*XX005891	WATER SERVICE RECONNECTIONS	EACH	11
*XX005893	REINFORCED CONCRETE PIPE TEE, 21" WITH 15" RISER	EACH	1
42400800	DETECTABLE WARNING	SQ FT	72

Δ SPECIALTY ITEMS * SEE SPECIAL PROVISIONS

TEMPORARY BENCHMARKS

NUMBER	LOCATION	ELEVATION
1	McClellan & Cleveland Intersection, F.H.	402.18
2	Cleveland & Lincoln Intersection, F.H.	407.48
3	Cleveland & Madison Intersection, RR Spike in U.P.	402.59
4	Cleveland & Van Buren Intersection, RR Spike in U.P.	402.61

SIGNING SCHEDULE

APPROXIMATE LOCATION	TYPE	NO.	SIGN SQ. FT.	POSTS FOOT
4+64, 17' RT.	STOP	R1-1 (30")	6.25	11.5
4+74, 32' LT.	STOP	R1-1 (30")	6.25	11.5
4+26, 17' LT.	STOP	R1-1 (30")	6.25	11.5
5+81, 25' RT.	STOP	R1-1 (30")	6.25	11.5
6+25, 17' RT.	NO PARKING THIS SIDE	R7-(12X18)	1.50	9.5
6+90, 18' LT.	NO PARKING THIS SIDE	R7-(12X18)	1.50	9.5
8+02, 28' LT.	STOP	R1-1 (30")	6.25	11.5
9+00, 18' RT.	NO PARKING THIS SIDE	R7-(12X18)	1.50	9.5
10+50, 18' LT.	NO PARKING THIS SIDE	R7-(12X18)	1.50	9.5
10+70, 25' RT.	STOP	R1-1 (30")	6.25	11.5
11+30, 39' LT.	STOP	R1-1 (30")	6.25	11.5
12+40, 17' RT.	NO PARKING THIS SIDE	R7-(12X18)	1.50	9.5
14+25, 18' LT.	NO PARKING THIS SIDE	R7-(12X18)	1.50	9.5
14+94, 30' LT.	STOP	R1-1 (30")	6.25	11.5
15+23, 25' RT.	STOP	R1-1 (30")	6.25	11.5
15+75, 17' RT.	NO PARKING THIS SIDE	R7-(12X18)	1.50	9.5

TOTAL SIGN AND POST QUANTITIES 66.75 170