



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 22, 2011

SUBJECT: FAP Route 330 (IL 21)  
Section 128 R-3  
Lake County  
Contract No. 60953  
Item No. 57, September 23, 2011 Letting  
Addendum C

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 15 and 15B of the Plans.
3. Revised page 318 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger P.E.", with a small "P.E." written to the right of the signature.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; D.Carl Puzey;  
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2000120	T-ACERX FREM AB 2-1/2	EACH	10.000				
A2002616	T-CARYA CORD 2	EACH	2.000				
A2002920	T-CELTIS OCCID 2-1/2	EACH	4.000				
A2005120	T-JUGLANS NIGRA 2-1/2	EACH	12.000				
A2005520	T-NYSSA SYLVAT 2-1/2	EACH	2.000				
A2005620	T-OSTRYA VIRG 2-1/2	EACH	13.000				
A2006420	T-QUERCUS ALBA 2-1/2	EACH	10.000				
A2006520	T-QUERCUS BICOL 2-1/2	EACH	3.000				
A2006720	T-QUERCUS MACR 2-1/2	EACH	21.000				
A2016818	T-QUERC SCH SBO 1-3/4	EACH	4.000				
B2000766	T-AMEL X GF AB SF 6'	EACH	3.000				
B2001666	T-CRATAE CRU-I SF 6'	EACH	10.000				
C2C01524	S-CORNUS RACEMOSA 2'C	EACH	20.000				
C2C05824	S-RHUS AROMA GRO 2'C	EACH	750.000				
C2C11830	S-VIBURN D MR 2-1/2'C	EACH	20.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
C2C12724	S-VIBURN PRUN 2'C	EACH	12.000				
XX000610	RELOCATE EX MAILBOX	EACH	18.000				
XX001186	PLANTER REMOVAL	EACH	3.000				
XX005940	REMOTE CONTR VIDEO SY	EACH	1.000				
XX006655	LYR II DATALINK SWTCH	EACH	1.000				
XX007023	STAIN CONC STRUCTURES	SQ YD	1,023.000				
XX008253	VIDEO ENCODER	EACH	1.000				
X0301797	GATE REMOVAL	EACH	2.000				
X0324455	DRILL/SET SOLD P SOIL	CU FT	4,445.000				
X0325751	DRIVE SOLDIER PILES	FOOT	1,763.000				
X0325796	GATES REM & RE-ERECT	EACH	1.000				
X0326309	RELO R-C VIDEO SYS SP	EACH	1.000				
X0326310	RELO EX SWITCH SPL	EACH	1.000				
*REV X0326658	CUR-IN-PL PIPE LNR 10	FOOT	777.000				
X0326713	SANITARY SEWER CONN	EACH	7.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0327351	AGG SUBGRADE 12 SPL	SQ YD	116,970.000				
X0327352	TS WOOD POLE 60 CL 4	EACH	20.000				
X0327353	STORMWTR TRTMT SYS L1	L SUM	1.000				
X0327354	STORMWTR TRTMT SYS L2	L SUM	1.000				
X0327355	SPLIT RL FEN WIREMESH	FOOT	823.000				
X0487800	SAN SEW REMOV 12	FOOT	486.000				
X2070304	POROUS GRAN EMB SPEC	CU YD	749.000				
*REV X2080250	TRENCH BACKFILL SPL	CU YD	1,102.000				
X2501800	SEEDING CL 4 MOD	ACRE	4.890				
X2501820	SEEDING CL 5 MOD	ACRE	0.560				
X2510635	HD EROS CONT BLANK SP	SQ YD	5,490.000				
X2520701	SODDING TYPE 1	SQ YD	782.000				
X2520702	SODDING TYPE 2	SQ YD	350.000				
X2520703	SODDING TYPE 3	SQ YD	1,053.000				
X4021000	TEMP ACCESS- PRIV ENT	EACH	11.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X4022000	TEMP ACCESS- COM ENT	EACH	33.000				
X4023000	TEMP ACCESS- ROAD	EACH	8.000				
X4402020	CONC MEDIAN SURF REM	SQ FT	554.000				
X4402800	ISLAND PAVEMENT REM	SQ YD	90.000				
X5539700	SS CLEANED	FOOT	600.000				
*REV X5610004	D I WTR MN FITTINGS	POUND	2,385.000				
*REV X5610706	WATER MAIN REMOV 6	FOOT	496.000				
*REV X5610708	WATER MAIN REMOV 8	FOOT	935.000				
X5610710	WATER MAIN REMOV 10	FOOT	27.000				
*REV X5610712	WATER MAIN REMOV 12	FOOT	250.000				
X6020096	MH TA 6D W/2 T1FCL RP	EACH	3.000				
*REV X6022820	MAN SAN 5 DIA T1F CL	EACH	6.000				
X6023508	INLETS TA W/SPL F&G	EACH	2.000				
X6026054	SAN MAN REMOVED	EACH	3.000				
*REV X6026622	VV REMOVED	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6060052	COMB CC&G TB6.24 SPL	FOOT	12,563.000				
**REV X6700410	ENGR FLD OFF A SPL	CAL MO	27.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7030025	WET REF TEM TP T3 L&S	SQ FT	1,161.600				
X7030030	WET REF TEM TAPE T3 4	FOOT	86,695.000				
X7030040	WET REF TEM TAPE T3 6	FOOT	6,515.000				
X7030055	WET REF TEM TPE T3 24	FOOT	800.000				
X7240600	REM RE-ERECT EX SIGN	EACH	2.000				
X8211070	UNDERPASS LUM 70W MH	EACH	32.000				
X8301236	LT P WD 60CL4 15MA IO	EACH	17.000				
X8301237	LT P WD 60C4 2-15MAIO	EACH	3.000				
X8570225	FAC T4 CAB SPL	EACH	2.000				
X8710029	FIB OPT CBL 24F SM	FOOT	27,837.000				
X8711100	TAFOC62.5/125MM12SM12	FOOT	3,553.000				
*REV X8730250	ELCBL C 20 3C TW SH	FOOT	1,702.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X8730800	ELCBL C VIDEO 20 4C	FOOT	314.000				
X8900030	REM EX TEMP TS EQUIP	EACH	1.000				
*REV Z0004638	PAVT BREAKING	SQ YD	19,475.000				
*ADD Z0004640	PAVD SHOULDR BREAKING	SQ YD	4,946.000				
Z0005216	HMA STAB 6 AT SPBGR	SQ YD	1,433.000				
Z0007118	UNTREATED TIMBER LAG	SQ FT	5,468.000				
Z0007430	TEMP SIDEWALK	SQ FT	3,000.000				
Z0013302	SEGMENT CONC BLK WALL	SQ FT	1,120.000				
Z0013797	STAB CONSTR ENTRANCE	SQ YD	1,678.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0018500	DRAINAGE STR CLEANED	EACH	10.000				
Z0022800	FENCE REMOVAL	FOOT	2,700.000				
Z0026402	FUR SOLDIER PILES HP	FOOT	2,905.000				
Z0026407	TEMP SHT PILING	SQ FT	3,775.000				
Z0030260	IMP ATTN TEMP FRN TL3	EACH	16.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0030332	IMP ATTN REL FRN TL3	EACH	6.000				
Z0030850	TEMP INFO SIGNING	SQ FT	1,000.000				
*REV Z0033020	LUM SFTY CABLE ASMBLY	EACH	46.000				
Z0033028	MAINTAIN LIGHTING SYS	CAL MO	18.000				
*ADD Z0033046	RE-OPTIMIZE SIG SYS 2	EACH	1.000				
Z0033050	COAXIAL CABLE IN CON	FOOT	314.000				
*DELETE Z0033056	<del>OPTIM TRAF SIGNAL SYS</del>	<del>EACH</del>	<del>1.000</del>				
Z0042002	POROUS GRAN EMB SUBGR	CU YD	28,780.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	1,553.000				
Z0056608	STORM SEW WM REQ 12	FOOT	100.000				
Z0056610	STORM SEW WM REQ 15	FOOT	100.000				
Z0056612	STORM SEW WM REQ 18	FOOT	100.000				
Z0056800	SAN SEW 6	FOOT	70.000				
Z0057100	SAN SEW 12	FOOT	466.000				
Z0062456	TEMP PAVEMENT	SQ YD	5,740.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0064800	SELECTIVE CLEARING	UNIT	5.000				
Z0073002	TEMP SOIL RETEN SYSTM	SQ FT	15,585.000				
Z0073345	SLEEPER SLAB	FOOT	401.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	2.000				
*REV 20100110	TREE REMOV 6-15	UNIT	1,659.000				
*REV 20100210	TREE REMOV OVER 15	UNIT	2,233.000				
20101000	TEMPORARY FENCE	FOOT	14,170.000				
20101200	TREE ROOT PRUNING	EACH	10.000				
20101300	TREE PRUN 1-10	EACH	50.000				
20101350	TREE PRUN OVER 10	EACH	50.000				
20200100	EARTH EXCAVATION	CU YD	53,164.000				
20201200	REM & DISP UNS MATL	CU YD	7,421.000				
20400800	FURNISHED EXCAVATION	CU YD	54,104.000				
20800150	TRENCH BACKFILL	CU YD	13,180.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	24,532.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
21101505	TOPSOIL EXC & PLAC	CU YD	13,724.000				
25000100	SEEDING CL 1	ACRE	0.070				
25000210	SEEDING CL 2A	ACRE	11.070				
25000300	SEEDING CL 3	ACRE	1.140				
25000400	NITROGEN FERT NUTR	POUND	1,729.000				
25000600	POTASSIUM FERT NUTR	POUND	1,729.000				
25100105	MULCH METHOD 1	ACRE	5.000				
25100115	MULCH METHOD 2	ACRE	5.000				
25100125	MULCH METHOD 3	ACRE	5.000				
25100135	MULCH METHOD 4	ACRE	5.000				
25100630	EROSION CONTR BLANKET	SQ YD	53,597.000				
25100900	TURF REINF MAT	SQ YD	508.000				
25200110	SODDING SALT TOLERANT	SQ YD	6,011.000				
25200200	SUPPLE WATERING	UNIT	100.000				
28000200	EARTH EXC - EROS CONT	CU YD	550.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000250	TEMP EROS CONTR SEED	POUND	2,682.000				
28000305	TEMP DITCH CHECKS	FOOT	93.000				
28000400	PERIMETER EROS BAR	FOOT	31,147.000				
28000500	INLET & PIPE PROTECT	EACH	215.000				
28000510	INLET FILTERS	EACH	218.000				
28001000	AGGREGATE - EROS CONT	TON	60.000				
28100101	STONE RIPRAP CL A1	SQ YD	518.000				
28100103	STONE RIPRAP CL A2	SQ YD	22.000				
28100105	STONE RIPRAP CL A3	SQ YD	518.000				
28100203	STONE RIPRAP CL A2	TON	6.000				
28200200	FILTER FABRIC	SQ YD	540.000				
31200502	STAB SUBBASE HMA 4.5	SQ YD	112,173.000				
35101400	AGG BASE CSE B	TON	1,666.000				
35501316	HMA BASE CSE 8	SQ YD	4,705.000				
40300100	BIT MATLS PR CT	GALLON	5,236.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600300	AGG PR CT	TON	13.000				
40603080	HMA BC IL-19.0 N50	TON	2,500.000				
40603085	HMA BC IL-19.0 N70	TON	200.000				
40603310	HMA SC "C" N50	TON	1,133.000				
40603335	HMA SC "D" N50	TON	396.000				
42000416	PCC PVT 9 3/4 JOINTD	SQ YD	89,602.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	1,402.000				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	312.000				
42400200	PC CONC SIDEWALK 5	SQ FT	100,110.000				
42400300	PC CONC SIDEWALK 6	SQ FT	160.000				
42400800	DETECTABLE WARNINGS	SQ FT	16.000				
44000100	PAVEMENT REM	SQ YD	56,761.000				
44000165	HMA SURF REM 4	SQ YD	2,159.000				
44000200	DRIVE PAVEMENT REM	SQ YD	8,621.000				
44000500	COMB CURB GUTTER REM	FOOT	11,806.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44000600	SIDEWALK REM	SQ FT	5,362.000				
44004250	PAVED SHLD REMOVAL	SQ YD	3,245.000				
44200144	PAVT PATCH T2 12	SQ YD	60.000				
48101100	AGGREGATE SHLDS A 12	SQ YD	50.000				
48300415	PCC SHOULDERS 9 3/4	SQ YD	608.000				
50100300	REM EXIST STRUCT N1	EACH	1.000				
50100400	REM EXIST STRUCT N2	EACH	1.000				
50100500	REM EXIST STRUCT N3	EACH	1.000				
50100600	REM EXIST STRUCT N4	EACH	1.000				
50100700	REM EXIST STRUCT N5	EACH	1.000				
50101500	REM EXIST SUP-STR	EACH	1.000				
50102400	CONC REM	CU YD	81.000				
50104400	CONC HDWL REM	EACH	7.000				
50105220	PIPE CULVERT REMOV	FOOT	1,528.000				
50200100	STRUCTURE EXCAVATION	CU YD	3,159.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50200450	REM/DISP UNS MATL-STR	CU YD	7,925.000				
50300100	FLOOR DRAINS	EACH	8.000				
50300225	CONC STRUCT	CU YD	1,254.600				
50300255	CONC SUP-STR	CU YD	617.500				
50300260	BR DECK GROOVING	SQ YD	529.000				
50300285	FORM LINER TEX SURF	SQ FT	9,154.000				
50300300	PROTECTIVE COAT	SQ YD	1,544.000				
50500305	ERECT STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	6,997.000				
50800105	REINFORCEMENT BARS	POUND	70,540.000				
50800205	REINF BARS, EPOXY CTD	POUND	278,010.000				
50800515	BAR SPLICERS	EACH	841.000				
50901750	PARAPET RAILING	FOOT	638.000				
51200958	FUR M S PILE 14X0.250	FOOT	2,535.000				
51202305	DRIVING PILES	FOOT	2,535.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
51203200	TEST PILE MET SHELLS	EACH	2.000				
51204650	PILE SHOES	EACH	149.000				
51500100	NAME PLATES	EACH	3.000				
52000110	PREF JT STRIP SEAL	FOOT	190.000				
52100210	ERECT ELAS BRG ASY T1	EACH	11.000				
52100520	ANCHOR BOLTS 1	EACH	22.000				
54003000	CONC BOX CUL	CU YD	386.000				
54010402	PCBC 4X2	FOOT	184.000				
54010503	PCBC 5X3	FOOT	99.000				
54010706	PCBC 7X6	FOOT	222.000				
54010803	PCBC 8X3	FOOT	116.000				
*DELETE 54010804	<del>PCBC 8X4</del>	<del>FOOT</del>	<del>407.000</del>				
*ADD 54010805	PCBC 8X5	FOOT	107.000				
542A1057	P CUL CL A 2 12	FOOT	72.000				
542A1063	P CUL CL A 2 18	FOOT	366.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A1069	P CUL CL A 2 24	FOOT	461.000				
542A1075	P CUL CL A 2 30	FOOT	123.000				
5421A042	P CUL CL A 1 42 TEMP	FOOT	32.000				
54213657	PRC FLAR END SEC 12	EACH	7.000				
54213663	PRC FLAR END SEC 18	EACH	10.000				
54213666	PRC FLAR END SEC 21	EACH	1.000				
54213669	PRC FLAR END SEC 24	EACH	9.000				
54213675	PRC FLAR END SEC 30	EACH	2.000				
54213681	PRC FLAR END SEC 36	EACH	2.000				
54247130	GRATING-C FL END S 24	EACH	9.000				
54247150	GRATING-C FL END S 30	EACH	2.000				
54247170	GRATING-C FL END S 36	EACH	2.000				
550A0040	STORM SEW CL A 1 10	FOOT	158.000				
550A0050	STORM SEW CL A 1 12	FOOT	672.000				
550A0070	STORM SEW CL A 1 15	FOOT	537.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A0090	STORM SEW CL A 1 18	FOOT	174.000				
550A0110	STORM SEW CL A 1 21	FOOT	92.000				
550A0120	STORM SEW CL A 1 24	FOOT	162.000				
550A0160	STORM SEW CL A 1 36	FOOT	147.000				
550A0180	STORM SEW CL A 1 42	FOOT	105.000				
550A0340	STORM SEW CL A 2 12	FOOT	6,685.000				
550A0360	STORM SEW CL A 2 15	FOOT	2,000.000				
550A0380	STORM SEW CL A 2 18	FOOT	814.000				
550A0400	STORM SEW CL A 2 21	FOOT	1,195.000				
550A0410	STORM SEW CL A 2 24	FOOT	2,754.000				
550A0430	STORM SEW CL A 2 30	FOOT	592.000				
550A0450	STORM SEW CL A 2 36	FOOT	1,366.000				
550A0470	STORM SEW CL A 2 42	FOOT	128.000				
550A2320	SS RG CL A 1 12	FOOT	100.000				
550A2330	SS RG CL A 1 15	FOOT	100.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A2340	SS RG CL A 1 18	FOOT	100.000				
55100500	STORM SEWER REM 12	FOOT	3,076.000				
55100900	STORM SEWER REM 18	FOOT	512.000				
55101200	STORM SEWER REM 24	FOOT	1,285.000				
*REV 56103000	D I WATER MAIN 6	FOOT	463.000				
*REV 56103100	D I WATER MAIN 8	FOOT	746.000				
*REV 56103200	D I WATER MAIN 10	FOOT	353.000				
*REV 56103300	D I WATER MAIN 12	FOOT	212.000				
56104900	WATER VALVES 6	EACH	1.000				
*REV 56105000	WATER VALVES 8	EACH	6.000				
*REV 56105100	WATER VALVES 10	EACH	1.000				
*REV 56105200	WATER VALVES 12	EACH	1.000				
*REV 56200700	WATER SERV LINE 2	FOOT	610.000				
*REV 56201800	CORP STOPS 2	EACH	14.000				
*REV 56400500	FIRE HYDNNTS TO BE REM	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*REV 56400820	FIRE HYD W/AUX V & VB	EACH	3.000				
*REV 56500800	DOM WAT SER BOX	EACH	14.000				
58700300	CONCRETE SEALER	SQ FT	2,197.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	918.000				
*ADD 59300100	CONTR LOW-STRENG MATL	CU YD	50.000				
60100060	CONC HDWL FOR P DRAIN	EACH	4.000				
60107600	PIPE UNDERDRAINS 4	FOOT	2,633.000				
60200105	CB TA 4 DIA T1F OL	EACH	1.000				
60200805	CB TA 4 DIA T8G	EACH	21.000				
60201105	CB TA 4 DIA T11F&G	EACH	2.000				
60201340	CB TA 4 DIA T24F&G	EACH	89.000				
60206905	CB TC T1F OL	EACH	1.000				
60218400	MAN TA 4 DIA T1F CL	EACH	74.000				
60221100	MAN TA 5 DIA T1F CL	EACH	11.000				
60223800	MAN TA 6 DIA T1F CL	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60236200	INLETS TA T8G	EACH	3.000				
60236600	INLETS TA T9F&G	EACH	7.000				
60236800	INLETS TA T11F&G	EACH	8.000				
60237470	INLETS TA T24F&G	EACH	81.000				
*REV 60248900	VV TA 5 DIA T1F CL	EACH	9.000				
60250200	CB ADJUST	EACH	6.000				
60252800	CB RECONST	EACH	1.000				
60255500	MAN ADJUST	EACH	19.000				
60257900	MAN RECONST	EACH	6.000				
60260100	INLETS ADJUST	EACH	7.000				
60266100	VV RECONST	EACH	1.000				
60500040	REMOV MANHOLES	EACH	14.000				
60500050	REMOV CATCH BAS	EACH	13.000				
60500060	REMOV INLETS	EACH	21.000				
60600605	CONC CURB TB	FOOT	2,616.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60602800	CONC GUTTER TB	FOOT	410.000				
60603500	COMB CC&G TB6.06	FOOT	72.000				
60603800	COMB CC&G TB6.12	FOOT	1,935.000				
60605000	COMB CC&G TB6.24	FOOT	24,983.000				
60608600	COMB CC&G TM6.06	FOOT	72.000				
60620000	CONC MED TSB6.24	SQ FT	27,790.000				
60622000	CONC MED TSM2.12	SQ FT	21,072.000				
60623200	CONC MED TSM6.24	SQ FT	1,260.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	138.000				
63000003	SPBGR TY A 9FT POSTS	FOOT	3,571.000				
63100045	TRAF BAR TERM T2	EACH	13.000				
63100085	TRAF BAR TERM T6	EACH	4.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	16.000				
63200310	GUARDRAIL REMOV	FOOT	897.000				
**REV 66900200	NON SPL WASTE DISPOSL	CU YD	40,000.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*ADD 66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
*ADD 66900530	SOIL DISPOSAL ANALY	EACH	5.000				
67100100	MOBILIZATION	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	400.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	96.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	363.000				
70300220	TEMP PVT MK LINE 4	FOOT	50,820.000				
70300240	TEMP PVT MK LINE 6	FOOT	1,270.000				
70300280	TEMP PVT MK LINE 24	FOOT	119.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	50,629.000				
70400100	TEMP CONC BARRIER	FOOT	7,975.000				
70400200	REL TEMP CONC BARRIER	FOOT	1,375.000				
72000100	SIGN PANEL T1	SQ FT	764.500				
72000200	SIGN PANEL T2	SQ FT	76.300				
72800100	TELES STL SIN SUPPORT	FOOT	270.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72900100	METAL POST TY A	FOOT	758.000				
72900200	METAL POST TY B	FOOT	689.000				
73100100	BASE TEL STL SIN SUPP	EACH	20.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	9.200				
78000200	THPL PVT MK LINE 4	FOOT	1,710.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	671.000				
78008210	POLYUREA PM T1 LN 4	FOOT	19,066.000				
78008230	POLYUREA PM T1 LN 6	FOOT	7,764.000				
78008240	POLYUREA PM T1 LN 8	FOOT	2,231.000				
78008250	POLYUREA PM T1 LN 12	FOOT	969.000				
78008270	POLYUREA PM T1 LN 24	FOOT	539.000				
78100100	RAISED REFL PAVT MKR	EACH	825.000				
78100105	RAISED REF PVT MKR BR	EACH	10.000				
78200410	GUARDRAIL MKR TYPE A	EACH	113.000				
78200530	BAR WALL MKR TYPE C	EACH	400.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78201000	TERMINAL MARKER - DA	EACH	27.000				
78300100	PAVT MARKING REMOVAL	SQ FT	11,042.000				
80400100	ELECT SERV INSTALL	EACH	2.000				
80400200	ELECT UTIL SERV CONN	L SUM	1.000		6,000.000		6,000.000
80500020	SERV INSTALL POLE MT	EACH	2.000				
81000300	CON T 1 GALVS	FOOT	100.000				
*REV 81000600	CON T 2 GALVS	FOOT	16,357.000				
*REV 81000700	CON T 2 1/2 GALVS	FOOT	79.000				
81000800	CON T 3 GALVS	FOOT	87.000				
81000900	CON T 3 1/2 GALVS	FOOT	14.000				
81001000	CON T 4 GALVS	FOOT	60.000				
*REV 81018500	CON P 2 GALVS	FOOT	2,333.000				
*REV 81018600	CON P 2 1/2 GALVS	FOOT	98.000				
81018700	CON P 3 GALVS	FOOT	790.000				
81018900	CON P 4 GALVS	FOOT	1,389.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81200100	CON EMB STR 1 GALVS	FOOT	220.000				
*ADD 81200120	CON EMB STR 2 GALVS	FOOT	231.000				
81400100	HANDHOLE	EACH	36.000				
81400200	HD HANDHOLE	EACH	6.000				
*REV 81400300	DBL HANDHOLE	EACH	5.000				
81603110	UD 4#4#6GXLPUSE 1 1/2	FOOT	3,529.000				
81700110	EC C EPR RHW 1C 10	FOOT	960.000				
81701115	EC C EPR USE 1C 2	FOOT	255.000				
81800320	A CBL 3-1C4 MESS WIRE	FOOT	4,118.000				
*REV 81900200	TR & BKFIL F ELECT WK	FOOT	19,036.000				
*REV 82102400	LUM SV HOR MT 400W	EACH	46.000				
82500330	LT CONT PEDM 240V 60	EACH	1.000				
82500350	LT CONT BASEM 240V100	EACH	1.000				
*REV 83050810	LT P A 47.5MH 15MA	EACH	17.000				
*REV 83600200	LIGHT POLE FDN 24D	FOOT	119.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*REV 83800205	BKWY DEV TR B 15BC	EACH	17.000				
84100110	REM TEMP LIGHT UNIT	EACH	18.000				
*REV 84200500	REM LT UNIT SALV	EACH	9.000				
84200804	REM POLE FDN	EACH	9.000				
84500110	REMOV LIGHTING CONTR	EACH	1.000				
84500120	REMOV ELECT SERV INST	EACH	1.000				
84500130	REMOV LTG CONTR FDN	EACH	1.000				
85000200	MAIN EX TR SIG INSTAL	EACH	3.000				
86200120	UNINTER POWER SUPPLY	EACH	2.000				
87200400	SPAN WIRE	FOOT	3,043.000				
87300925	ELCBL C TRACER 14 1C	FOOT	27,837.000				
87301215	ELCBL C SIGNAL 14 2C	FOOT	3,692.000				
87301225	ELCBL C SIGNAL 14 3C	FOOT	5,949.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	5,386.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	3,133.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87301305	ELCBL C LEAD 14 1PR	FOOT	9,785.000				
87301805	ELCBL C SERV 6 2C	FOOT	64.000				
87301900	ELCBL C EGRDC 6 1C	FOOT	1,270.000				
87502440	TS POST GALVS 10	EACH	1.000				
87502500	TS POST GALVS 16	EACH	6.000				
87702596	S MAA & P DMA 38 & 40	EACH	1.000				
87702940	STL COMB MAA&P 42	EACH	1.000				
*ADD 87703030	STL COMB MAA&P 60	EACH	1.000				
87703050	STL COMB MAA&P 64	EACH	2.000				
87703070	STL COMB MAA&P 66	EACH	1.000				
*DELETE 87703090	STL COMB MAA&P 70	EACH	1.000				
87800100	CONC FDN TY A	FOOT	28.000				
87800150	CONC FDN TY C	FOOT	8.000				
87800415	CONC FDN TY E 36D	FOOT	13.000				
*REV 87800420	CONC FDN TY E 42D	FOOT	109.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route  
 FAP 330

\* REVISED: SEPT 12, 2011  
 \*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*REV 87900200	DRILL EX HANDHOLE	EACH	4.000				
88030020	SH LED 1F 3S MAM	EACH	14.000				
88030050	SH LED 1F 3S BM	EACH	1.000				
88030100	SH LED 1F 5S BM	EACH	2.000				
88030110	SH LED 1F 5S MAM	EACH	5.000				
88030240	SH LED 2F 1-3 1-5 BM	EACH	5.000				
88102717	PED SH LED 1F BM CDT	EACH	4.000				
88102747	PED SH LED 2F BM CDT	EACH	4.000				
88102757	PED SH LED 3F BM CDT	EACH	2.000				
88200210	TS BACKPLATE LOU ALUM	EACH	19.000				
88500100	INDUCTIVE LOOP DETECT	EACH	28.000				
*DELETE 88600100	DET LOOP T1	FOOT	66.000				
*REV 88600700	PREFORM DETECT LOOP	FOOT	1,832.000				
88700200	LIGHT DETECTOR	EACH	6.000				
88700300	LIGHT DETECTOR AMP	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60953

State Job # - C-91-199-00  
 PPS NBR - 1-71388-0200  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 128R-3

Project Number

Route

FAP 330

\* REVISED: SEPT 12, 2011

\*\* REVISED: SEPT 22, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
88800100	PED PUSH-BUTTON	EACH	20.000				
89000100	TEMP TR SIG INSTALL	EACH	2.000				
*REV 89502300	REM ELCBL FR CON	FOOT	25,211.000				
89502375	REMOV EX TS EQUIP	EACH	1.000				
89502380	REMOV EX HANDHOLE	EACH	17.000				
89502385	REMOV EX CONC FDN	EACH	8.000				

- A) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage and dispose of all soils excavated within the following areas as classified below. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less. Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. Phase I Preliminary Engineering information is available through the District's Environmental Studies Unit.
1. Station **461+50** to Station 463+00 0 to 70 feet RT (Mobil, Site 223V-26, 1790 North Milwaukee Avenue) – non-special waste. Contaminants of concern sampling parameters: BETX and Arsenic.
  2. Station 450+50 to Station 453+00 0 to 70 feet LT (Ben's Volvo Repair, Site 223V-16, 178 Peterson Road) – non-special waste. Contaminants of concern sampling parameters: BETX, Arsenic, and Lead.
- B) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage any excavated soils **within the construction limits of this project as fill**. Although the soil concentrations exceed a residential property's Tier 1 soil remediation objective for the ingestion exposure pathway, they can be utilized within the construction limits as fill because the roadway is not considered a residential property. All storm sewer excavated soils can be placed back into the excavated trench as backfill unless trench backfill is specified. If the soils cannot be utilized within the construction limits as fill then they must be managed off-site as a non-special waste. The following areas can be managed within the construction limits as fill.
1. Station 273+00 to Station 292+00 0 to 60 feet LT (Numerous Sites in PESA 223V) – non-special waste. Contaminants of concern sampling parameters: Arsenic, Lead, and Nickel.
  2. Station 175+00 to Station 292+00 0 to 100 feet RT (Numerous Sites in PESA 223V) – non-special waste. Contaminants of concern sampling parameters: Arsenic, Lead, and Nickel.
  3. Station 453+00 to Station 460+00 0 to 80 feet LT (Numerous Sites in PESA 223V) – non-special waste. Contaminants of concern sampling parameters: Arsenic, Lead, and Nickel.
  4. Station 453+00 to Station 461+50 0 to 70 feet RT (Numerous Sites in PESA 223V) – non-special waste. Contaminants of concern sampling parameters: Arsenic, Lead, and Nickel.
  5. Station 463+00 to Station 472+00 0 to 80 feet RT (Numerous Sites in PESA 223V) – non-special waste. Contaminants of concern sampling parameters: Arsenic, Lead, and Nickel.

#### **TEMPORARY AERIAL FIBER OPTIC CABLE, NO. 62.5/125, MM12F, SM12F**

This work shall consist of providing and installing an aerial fiber optic cable, No. 62.5/125, MM12F, SM12F, on span wire mounted between wood poles. The cable shall meet the requirements of Article 871.01 of the Standard Specifications, except that it shall be installed aerially. The cable shall be installed as shown on the plans and as directed by the Engineer.

Revised 09/22/2011