



RADIO INTERCONNECTION SCHEMATIC

**NOTE:**

1. THE TEMPORARY INTERCONNECT WORK SHALL BE PERFORMED AS SHOWN IN THE PLANS AND AS DIRECTED BY THE ENGINEER. THE COST OF THIS WORK SHALL BE INCLUDED IN THE PAY ITEM FOR "TEMPORARY TRAFFIC SIGNAL INSTALLATION".
2. OTHER METHODS MAY BE USED WITH PRIOR APPROVAL FROM DISTRICT 1, ILLINOIS DEPARTMENT OF TRANSPORTATION.

THE ENVIRONMENTAL FIRM IS REQUIRED TO CONTINUOUSLY MONITOR FOR WORKER PROTECTION AND SOIL CONTAMINATION AT SEVERAL AREAS. SEE SPECIAL PROVISION AND SUPPLEMENTAL SPECIFICATIONS FOR DETAILS.

NOTE:  
THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

**RESTORATION OF WORK AREA:**

RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENTS, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

FILE NAME = ...Phase Two\DI60C06-shr-TS.dgn	USER NAME = Plotted by flin	DESIGNED - FML	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TEMPORARY TRAFFIC SIGNAL INTERCONNECTION IL RT 31 (STATE ST) FROM STEPHEN DIMEO DRIVE TO BIG TIMBER RD./ADELAIDE DR.</b>			F.A.U. RTE. 3887	SECTION R-VB-R	COUNTY KANE	TOTAL SHEETS 83	SHEET NO. 32
	PLOT SCALE = 60.00' / IN.	DRAWN - FML	REVISED -		SCALE: 1" = 50'	SHEET NO.	OF	SHEETS	STA. 67+00	TO STA. 82+10	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT
PLOT DATE = 7/22/2011	CHECKED - KC	REVISED -			CONTRACT NO. 60C06							
	DATE - 07/22/2011	REVISED -										