



THE ENVIRONMENTAL FIRM IS REQUIRED TO CONTINUOUSLY MONITOR FOR WORKER PROTECTION AND SOIL CONTAMINATION AT SEVERAL AREAS. SEE SPECIAL PROVISION AND SUPPLEMENTAL SPECIFICATIONS FOR DETAILS.

SCHEDULE OF QUANTITIES

ITEM	UNIT	QUANTITY
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	140
CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	240
ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1750
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	140
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1750
DRILL EXISTING HANDHOLE	EACH	3
JUNCTION BOX EMBEDDED IN STRUCTURE 18" X 12" X 6"	EACH	2
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1750

FILE NAME = ...Phase Two\016006-sht-TS.dgn	USER NAME = Plotted by flin	DESIGNED - FML	REVISED -
		DRAWN - FML	REVISED -
	PLOT SCALE = 20.00 / IN.	CHECKED - KC	REVISED -
	PLOT DATE = 7/22/2011	DATE - 07/22/2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INTERCONNECT SCHEMATIC
IL RT 31
FROM STEPHEN DIMEO DRIVE TO BONCOSKY RD.**

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 3887	SECTION R-VB-R	COUNTY KANE	TOTAL SHEETS 83	SHEET NO. 34
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60C06	