STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

℄ Beam 1

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk of South Abut	66+77.53	-27.92	801.26	801.26
CL Brg South Abut	66+81.11	-27.92	801.24	801.24
A	66+91.11	-27.92	801.21	801.23
B	67+01.11	-27.92	801.16	801.20
C	67+11.11	-27.92	801.10	801.16
D	67+21.11	-27.92	801.04	801.09
E	67+31.11	-27.92	800.97	801.00
F	67+41.11	-27.92	800.89	800.90
CL Pier 1	67+54.11	-27.92	800.78	800.78
G	67+64.11	-27.92	800.68	800.69
H	67+74.11	-27.92	800.58	800.61
I	67+84.11	-27.92	800.47	800.52
J	67+94.11	-27.92	800.35	800.41
K	68+04.11	-27.92	800.22	800.29
L	68+14.11	-27.92	800.08	800.14
M	68+24.11	-27.92	799.94	799.98
N	68+34.11	-27.92	799.79	799.81
CL Pier 2	68+47.36	-27.92	799.58	799.58
O	68+57.36	-27.92	799.41	799.42
P	68+67.36	-27.92	799.23	799.26
Q	68+77.36	-27.92	799.05	799.09
R	68+87.36	-27.92	798.86	798.91
S	68+97.36	-27.92	798.66	798.71
T	69+07.36	-27.92	798.45	798.49
CL Brg North Abut	69+20.36	-27.92	798.17	798.17
Bk of North Abut	69+23.53	-27.92	798.10	798.10

West Gutter Line

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk of South Abut	66+74.00	-25.00	801.31	801.31
CL Brg South Abut	66+77.58	-25.00	801.30	801.30
A	66+87.58	-25.00	801.27	801.29
B	66+97.58	-25.00	801.22	801.25
C	67+07.58	-25.00	801.17	801.21
D	67+17.58	-25.00	801.11	801.14
E	67+27.58	-25.00	801.04	801.06
F	67+37.58	-25.00	800.97	800.97
CL Pier 1	67+50.58	-25.00	800.86	800.86
G	67+60.58	-25.00	800.76	800.77
H	67+70.58	-25.00	800.66	800.68
I	67+80.58	-25.00	800.55	800.59
J	67+90.58	-25.00	800.43	800.48
K	68+00.58	-25.00	800.31	800.36
L	68+10.58	-25.00	800.18	800.22
M	68+20.58	-25.00	800.04	800.07
N	68+30.58	-25.00	799.89	799.90
CL Pier 2	68+43.83	-25.00	799.68	799.68
O	68+53.83	-25.00	799.52	799.52
P	68+63.83	-25.00	799.34	799.36
Q	68+73.83	-25.00	799.16	799.19
R	68+83.83	-25.00	798.97	799.01
S	68+93.83	-25.00	798.78	798.81
T	69+03.83	-25.00	798.57	798.60
CL Brg North Abut	69+16.83	-25.00	798.29	798.29
Bk of North Abut	69+20.00	-25.00	798.22	798.22

℄ Beam 2

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk of South Abut	66+71.08	-22.58	801.36	801.36
CL Brg South Abut	66+74.66	-22.58	801.35	801.35
A	66+84.66	-22.58	801.31	801.33
B	66+94.66	-22.58	801.27	801.31
C	67+04.66	-22.58	801.22	801.26
D	67+14.66	-22.58	801.16	801.20
E	67+24.66	-22.58	801.10	801.12
F	67+34.66	-22.58	801.03	801.03
CL Pier 1	67+47.66	-22.58	800.92	800.92
G	67+57.66	-22.58	800.83	800.84
H	67+67.66	-22.58	800.73	800.75
I	67+77.66	-22.58	800.62	800.66
J	67+87.66	-22.58	800.51	800.56
K	67+97.66	-22.58	800.39	800.44
L	68+07.66	-22.58	800.26	800.30
M	68+17.66	-22.58	800.12	800.15
N	68+27.66	-22.58	799.97	799.99
CL Pier 2	68+40.91	-22.58	799.77	799.77
O	68+50.91	-22.58	799.60	799.61
P	68+60.91	-22.58	799.43	799.45
Q	68+70.91	-22.58	799.25	799.28
R	68+80.91	-22.58	799.07	799.10
S	68+90.91	-22.58	798.87	798.91
T	69+00.91	-22.58	798.67	798.69
CL Brg North Abut	69+13.91	-22.58	798.40	798.40
Bk of North Abut	69+17.08	-22.58	798.33	798.33

℄ Beam 3

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk of South Abut	66+64.63	-17.25	801.46	801.46
CL Brg South Abut	66+68.21	-17.25	801.45	801.45
A	66+78.21	-17.25	801.42	801.44
B	66+88.21	-17.25	801.38	801.42
C	66+98.21	-17.25	801.34	801.38
D	67+08.21	-17.25	801.29	801.32
E	67+18.21	-17.25	801.23	801.25
F	67+28.21	-17.25	801.16	801.17
CL Pier 1	67+41.21	-17.25	801.06	801.06
G	67+51.21	-17.25	800.97	800.98
H	67+61.21	-17.25	800.88	800.90
I	67+71.21	-17.25	800.77	800.81
J	67+81.21	-17.25	800.67	800.71
K	67+91.21	-17.25	800.55	800.60
L	68+01.21	-17.25	800.42	800.47
M	68+11.21	-17.25	800.29	800.32
N	68+21.21	-17.25	800.15	800.16
CL Pier 2	68+34.46	-17.25	799.95	799.95
O	68+44.46	-17.25	799.79	799.80
P	68+54.46	-17.25	799.63	799.64
Q	68+64.46	-17.25	799.45	799.48
R	68+74.46	-17.25	799.27	799.31
S	68+84.46	-17.25	799.08	799.12
T	68+94.46	-17.25	798.88	798.91
CL Brg North Abut	69+07.46	-17.25	798.62	798.62
Bk of North Abut	69+10.63	-17.25	798.55	798.55

℄ Beam 4

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk of South Abut	66+58.18	-11.92	801.56	801.56
CL Brg South Abut	66+61.76	-11.92	801.55	801.55
A	66+71.76	-11.92	801.52	801.54
B	66+81.76	-11.92	801.49	801.53
C	66+91.76	-11.92	801.45	801.49
D	67+01.76	-11.92	801.40	801.44
E	67+11.76	-11.92	801.35	801.37
F	67+21.76	-11.92	801.29	801.29
CL Pier 1	67+34.76	11.92	801.19	801.19
G	67+44.76	-11.92	801.11	801.12
H	67+54.76	-11.92	801.02	801.04
I	67+64.76	-11.92	800.92	800.96
J	67+74.76	-11.92	800.82	800.87
K	67+84.76	-11.92	800.71	800.76
L	67+94.76	-11.92	800.59	800.63
M	68+04.76	-11.92	800.46	800.49
N	68+14.76	-11.92	800.32	800.34
CL Pier 2	68+28.01	-11.92	800.13	800.13
O	68+38.01	-11.92	799.98	799.98
P	68+48.01	-11.92	799.82	799.84
Q	68+58.01	-11.92	799.65	799.68
R	68+68.01	-11.92	799.47	799.51
S	68+78.01	-11.92	799.29	799.32
T	68+88.01	-11.92	799.10	799.12
CL Brg North Abut	69+01.01	-11.92	798.83	798.83
Bk of North Abut	69+04.18	-11.92	798.77	798.77

℄ Beam 5

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk of South Abut	66+51.74	-6.58	801.65	801.65
CL Brg South Abut	66+55.32	-6.58	801.64	801.64
A	66+65.32	-6.58	801.62	801.64
B	66+75.32	-6.58	801.60	801.63
C	66+85.32	-6.58	801.56	801.60
D	66+95.32	-6.58	801.52	801.55
E	67+05.32	-6.58	801.47	801.49
F	67+15.32	-6.58	801.41	801.42
CL Pier 1	67+28.32	-6.58	801.32	801.32
G	67+38.32	-6.58	801.25	801.25
H	67+48.32	-6.58	801.16	801.19
I	67+58.32	-6.58	801.07	801.11
J	67+68.32	-6.58	800.97	801.02
K	67+78.32	-6.58	800.86	800.91
L	67+88.32	-6.58	800.75	800.79
M	67+98.32	-6.58	800.63	800.65
N	68+08.32	-6.58	800.50	800.51
CL Pier 2	68+21.57	-6.58	800.31	800.31
O	68+31.57	-6.58	800.16	800.17
P	68+41.57	-6.58	800.01	800.02
Q	68+51.57	-6.58	799.84	799.87
R	68+61.57	-6.58	799.67	799.71
S	68+71.57	-6.58	799.49	799.53
T	68+81.57	-6.58	799.30	799.33
CL Brg North Abut	68+94.57	-6.58	799.05	799.05
Bk of North Abut	68+97.74	-6.58	798.98	798.98

TOP OF SLAB ELEVATIONS I
STRUCTURE NO. 045-0016

DESIGNED	DF
CHECKED	TAH
DRAWN	LAM
CHECKED	DF

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com
Job. No. 910

SHEET NO. S-7	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S-34 SHEETS	3887	R-VB-R	KANE	83	41
			CONTRACT NO. 60C06		
	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		