| SUMMARY OF QUANTITIES | | | URBAN | CONSTRUCTION TYPE CODE | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 0004 90% FED 10% STATE ROADWAY | 0021 90% FED 5% STATE 5% KANE T. SIGNALS | 0021 100% STATE LIGHTING/ SIGNAL INTERCONNECT | 0021 100% KANE COUNTY | 0021 100% CITY OF ELGIN E.V.P. | |
| 550A0410 | STORM SEWERS, CLASS A, TYPE 2 24" | FOOT | 2857 | 2857 | | | | | |
| 550A0430 | STORM SEWERS, CLASS A, TYPE 2 30" | FOOT | 10 | 10 | | | | | |
| 550A0480 | STORM SEWERS, CLASS A, TYPE 2 48" | FOOT | 424 | 424 | | | | | |
| 550A0500 | STORM SEWERS, CLASS A, TYPE 2 60" | FOOT | 18 | 18 | | | | | |
| 55100500 | STORM SEWER REMOVAL 12" | FOOT | 662 | 662 | | | | | |
| 55100700 | STORM SEWER REMOVAL 15" | FOOT | 240 | 240 | | | | | |
| 55100900 | STORM SEWER REMOVAL 18" | FOOT | 718 | 718 | | | | | |
| 55101200 | STORM SEWER REMOVAL 24" | FOOT | 852 | 852 | | | | | |
| 55101400 | STORM SEWER REMOVAL 30" | FOOT | 120 | 120 | | | | | |
| 60100060 | CONCRETE HEADWALLS FOR PIPE DRAINS | EACH | 10 | 10 | | | | | |
| 60107600 | PIPE UNDERDRAINS 4" | FOOT | 1000 | 1000 | | | | | |
| 60108100 | PIPE UNDERDRAINS 4" (SPECIAL) | FOOT | 100 | 100 | | | | | |
| 60201205 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 12 FRAME AND GRATE | EACH | 5 | 5 | | | | | |
| 60201330 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE | EACH | 6 | 6 | | | | | |
| 60204505 | CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE | EACH | 1 | 1 | | | | | |
| 60204905 | CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 12 FRAME AND GRATE | EACH | 1 | 1 | | | | | |
| 60205030 | CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 23 FRAME AND GRATE | EACH | 5 | 5 | | | | | |
| 60206600 | CATCH BASINS, TYPE B, TYPE 7 GRATE | EACH | 2 | 2 | | | | | |
| 60208230 | CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE | EACH | 3 | 3 | | | | | |
| 60218400 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 6 | 6 | | | | | |
| 60221100 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 6 | 6 | | | | | |
| 60221102 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE | EACH | 4 | 4 | | | | | |
| 60223800 | MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 2 | 2 | | | | | |
| 60224446 | MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 1 | 1 | | | | | |
| 60236900 | INLETS, TYPE A, TYPE 12 FRAME AND GRATE | EACH | 4 | 4 | | | | | |
| 60237460 | INLETS, TYPE A, TYPE 23 FRAME AND GRATE | EACH | 12 | 12 | | | | | |
| 60240315 | INLETS, TYPE B, TYPE 12 FRAME AND GRATE | EACH | 1 | 1 | | | | | |
| 60240327 | INLETS, TYPE B, TYPE 23 FRAME AND GRATE | EACH | 3 | 3 | | | | | |
| 60500040 | REMOVING MANHOLES | EACH | 16 | 16 | | | | | |
| 60500050 | REMOVING CATCH BASINS | EACH | 1 | 1 | | | | | |
| 60600095 | CLASS SI CONCRETE (OUTLET) | CU YD | 13 | 13 | | | | | |
| 60618760 | CONCRETE MEDIAN, TYPE M-4.12 | SQ FT | 30590 | 30590 | | | | | |

| SUMMARY OF QUANTITIES | | | URBAN | CONSTRUCTION TYPE CODE | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 0004 90% FED 10% STATE ROADWAY | 0021 90% FED 5% STATE 5% KANE T. SIGNALS | 0021 100% STATE LIGHTING/ SIGNAL INTERCONNECT | 0021 100% KANE COUNTY | 0021 100% CITY OF ELGIN E.V.P. | |
| 60624600 | CORRUGATED MEDIAN | SQ FT | 14220 | 14220 | | | | | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 266 | 266 | | | | | |
| 6330121D | REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A | FOOT | 632 | 632 | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 12 | 12 | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | |
| 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 5210 | 5210 | | | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 983 | 983 | | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 29750 | 29750 | | | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 4750 | 4750 | | | | | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 550 | 550 | | | | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 265 | 265 | | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 14344 | 14344 | | | | | |
| * 72000100 | SIGN PANEL - TYPE 1 | SQ FT | 55 | | 55 | | | | |
| * 72000200 | SIGN PANEL - TYPE 2 | SQ FT | 25 | | 25 | | | | |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 511 | 511 | | | | | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 17538 | 17538 | | | | | |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 2580 | 2580 | | | | | |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 320 | 320 | | | | | |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 135 | 135 | | | | | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 351 | 351 | | | | | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 10850 | 10850 | | | | | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 286 | 286 | | | | | |
| * 80400100 | ELECTRIC SERVICE INSTALLATION | EACH | 1 | | | 1 | | | |
| * 80400200 | ELECTRIC UTILITY SERVICE CONNECTION | L SUM | 1 | | | 1 | | | |
| * 80500020 | SERVICE INSTALLATION-POLE MOUNTED | EACH | 1 | | 1 | | | | |
| * 81000600 | CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL | FOOT | 2157 | | 1101 | 1056 | | | |
| * 81000700 | CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 81 | | 81 | | | | |
| 81000800 | CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL | FOOT | 76 | | 76 | | | | |
| 81001000 | CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL | FOOT | 144 | | 144 | | | | |

* SPECIALTY ITEMS

Rev.

| FILE NAME = | USER NAME = poclechal | DESIGNED - | REVISED - |
|---|---|---|---|
| c:\pw_work\pwidot\poclechal\d0126931\N10008-Design.dgn | | DRAWN - | REVISED - |
| | PLOT SCALE = 50.0000 ' / In. | CHECKED - | REVISED - |
| | PLOT DATE = 6/23/2011 | DATE - | REVISED - |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**
**IL 72 AT RANDALL ROAD**

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 341 | 62-N-1 | KANE | 148 | 4 |
| | | CONTRACT NO. 60K09 | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |