

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	0004	0021	0021	0021	0021	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	0004	0021	0021	0021	0021
				90% FED 10% STATE ROADWAY	90% FED 5% STATE 5% KANE T. SIGNALS	100% STATE LIGHTING/ SIGNAL INTERCONNECT	100% KANE COUNTY	100% CITY OF ELGIN E.V.P.					90% FED 10% STATE ROADWAY	90% FED 5% STATE 5% KANE T. SIGNALS	100% STATE LIGHTING/ SIGNAL INTERCONNECT	100% KANE COUNTY	100% CITY OF ELGIN E.V.P.
* D2002472	EVERGREEN, PINUS FLEXILIS VANDERWOLF'S PYRAMID (VANDERWOLF'S PYRAMID LIMBER PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	23	23					* X8360215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	30			30		
* K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	5	5					* X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	9274			9274		
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	20	20					* XX004913	REMOVE FIBER OPTIC CABLE FROM CONDUIT	FOOT	7190		7190			
* X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	1139				1139		* XX007251	INTERSECTION VIDEO TRAFFIC MONITORING SYSTEM WITH PTZ CAMERA	EACH	1				1	
X0325167	POROUS GRANULAR EMBANKMENT, SUBGRADE 24 INCH	SO YD	333	333					* XX008453	ETHERNET SWITCH, TYPE 1	EACH	1				1	
* X0326148	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	16			16			* XX007953	NETWORK CONFIGURATION	L SUM	1		1			
X0327001	PERMANENT DITCH CHECK WITH 12" PIPE	EACH	1	1					Z0001050	AGGREGATE SUBGRADE 12"	SO YD	25575	25575				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4	4					X6015000	REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4	4				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3					Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	5	5					Z0022800	FENCE REMOVAL	FOOT	100	100				
X4067112	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N70	TON	400	400					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	2512	2512					* Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	20			20		
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	6680	6680					Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1		1			
X6331009	REMOVE AND REPLACE STEEL PLATE BEAM GUARDRAIL, SPECIAL	FOOT	630	630					Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	2425	2425				
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	790	790				
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SO FT	1966	1966					Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1			
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	59500	59500													
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	9500	9500													
X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	1100	1100													
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	530	530													
* X7800605	URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	472	472													
* X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	12212	12212													
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	2170	2170													
* X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	230	230													
* X7800680	URETHANE PAVEMENT MARKING - LINE 24"	FOOT	130	130													
* X8210015	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, 400 WATT	EACH	20			20											
* X8250084	LIGHTING CONTROLLER, SINGLE DOOR, CONSOLE TYPE	EACH	1			1											

* SPECIALTY ITEMS