


SUMMARY						
LOCATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION AND PLACEMENT	BENCHING EARTH EXCAVATION
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STA. 0+00.00 TO 1+50.00	0.00	0.00	0.00	0.00	0.00	0.0
STA. 1+50.00 TO 1+82.79	19.36	14.52	-1.34	13.18	3.15	0.0
STA. 1+82.79 TO 2+00.00	19.81	14.86	-1.51	13.35	3.34	0.0
STA. 2+00.00 TO 2+50.00	52.06	39.05	-14.64	24.41	13.57	0.0
STA. 2+50.00 TO 3+00.00	36.14	27.10	-80.52	-53.41	54.57	87.8
STA. 3+00.00 TO 3+50.00	16.63	12.47	-110.18	-97.70	61.40	117.1
STA. 3+50.00 TO 4+00.00	6.17	4.63	-112.31	-107.68	36.18	72.5
STA. 4+00.00 TO 4+50.00	3.34	2.51	-188.67	-186.16	63.78	138.1
STA. 4+50.00 TO 4+54.81	0.35	0.26	-21.94	-21.67	8.38	18.7
STA. 4+54.81 TO 4+84.81	2.64	1.98	-164.32	-162.34	67.59	153.9
STA. 4+84.81 TO 7+00.00	0.00	0.00	0.00	0.00	0.00	0.0
STA. 7+00.00 TO 7+10.33	0.88	0.66	-26.27	-25.61	9.60	26.3
STA. 7+10.33 TO 7+40.33	7.44	5.58	-97.25	-91.67	39.89	105.4
STA. 7+40.33 TO 7+50.00	3.45	2.59	-13.05	-10.46	7.24	16.7
STA. 7+50.00 TO 8+00.00	23.78	17.83	-55.37	-37.54	30.62	0.0
STA. 8+00.00 TO 8+50.00	18.06	13.55	-116.54	-102.99	63.41	77.6
STA. 8+50.00 TO 9+00.00	22.60	16.95	-232.81	-215.86	112.90	181.8
STA. 9+00.00 TO 9+50.00	52.11	39.08	-140.07	-100.99	67.05	104.2
STA. 9+50.00 TO 9+69.13	27.59	20.69	-24.46	-3.77	18.42	31.7
TOTAL	312.42	234.32	-1401.24	-1,166.92	661.08	1,131.8

FURNISHED EXCAVATION SHRINKAGE FACTOR = 0.25

FILE NAME =	DESIGNED - JCP	REVISED -	 <small>800 WEST FULTON STREET CHICAGO, ILLINOIS 60611-1208</small> <small>TEL 312 454 9100 FAX 312 559 1217 WEB www.sepsteintotal.com</small>	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
...ADI-xxxxx-sh007-500.dgn	DRAWN - JCP	REVISED -						332	0101.1 BR-3	COOK	60	7	
PLOT TIME = 11:08:01 AM	CHECKED - TRP	REVISED -			SCALE: N/A			SHEET NO. 1 OF 1 SHEETS STA. TO STA.			CONTRACT NO. 62421		
PLOT DATE = 6/30/2011	DATE - 07/01/2011	REVISED -			ILLINOIS FED. AID PROJECT								