

**BEAM 6**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
BK W. ABUT.	4+92.19	16.88	651.18	651.18
CL BRG. W. ABUT.	4+94.37	16.88	651.21	651.21
A	5+04.37	16.88	651.36	651.37
B	5+14.37	16.88	651.49	651.51
C	5+24.37	16.88	651.60	651.62
D	5+34.37	16.88	651.71	651.71
CL PIER 1	5+43.54	16.88	651.79	651.79
E	5+53.54	16.88	651.86	651.87
F	5+63.54	16.88	651.92	651.94
G	5+73.54	16.88	651.96	651.99
H	5+83.54	16.88	651.99	652.02
I	5+93.54	16.88	652.01	652.02
CL PIER 2	6+04.96	16.88	652.01	652.01
J	6+14.96	16.88	651.99	652.00
K	6+24.96	16.88	651.96	651.98
L	6+34.96	16.88	651.91	651.94
M	6+44.96	16.88	651.85	651.87
N	6+54.96	16.88	651.77	651.79
CL PIER 3	6+66.37	16.88	651.67	651.67
O	6+76.37	16.88	651.56	651.57
P	6+86.37	16.88	651.44	651.46
R	6+96.37	16.88	651.30	651.32
S	7+06.37	16.88	651.15	651.17
CL BRG.E ABUT	7+15.54	16.88	651.00	651.00
BK E. ABUT	7+17.72	16.88	650.96	650.96

*Notes:*

1. Work this sheet with sheets S3, S4 and S5.
2. For top of slab elevations at West Approach, see sheet S7.
3. For top of slab elevations at East Approach, see sheet S8.

E-S

7-1-10

FILE NAME * ...\\0162121-006-TOS.ElevIV.dgn	DESIGNED <i>EV</i>	REVISED -	 800 WEST FULTON STREET CHICAGO, ILLINOIS 60601-1209 TEL 312 454 9100 FAX 312 558 1217 WEB www.sepsteincorp.com	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TOP OF SLAB ELEVATIONS IV STRUCTURE NO. 016-2121	F.A.P. RTE. 332	SECTION 0101.1 BR-3	COUNTY COOK	TOTAL SHEETS 60	SHEET NO. 21		
PLOT TIME * 5:17:25 PM	DRAWN <i>JCP</i>	REVISED -				SHEET NO. 56 OF 529 SHEETS				CONTRACT NO. 62421		
PLOT DATE * 6/29/2011	CHECKED <i>PC</i>	REVISED -				ILLINOIS FED. AID PROJECT						
	DATE <i>07 01 2011</i>	REVISED -										