



 UNDERMINED AREA TO BE FILLED WITH TREMIE CONCRETE

NOTES:

CONTRACTOR WILL HAVE THE OPTION TO DO WORK FROM EITHER THE BRIDGE OR A BARGE.

CONTRACTOR WILL NOT BE ALLOWED TO DO ANY EXCAVATION AT THE WORK AREA

PLACE GROUT BAGS TO AN ELEVATION ABOVE THE BOTTOM OF THE FOOTING SUFFICIENT TO ACT AS FORM DURING PLACEMENT OF TREMIE CONCRETE

COST OF TREMIE CONCRETE INCLUDED IN THE COST OF SUBSTRUCTURE REPAIR (GROUT BAGS)

BILL OF MATERIALS

ITEM	UNIT	QUANTITY
SUBSTRUCTURE REPAIR (GROUT BAGS)	L SUM	1

FILE NAME =	USER NAME = mdyja	DESIGNED - RTB	REVISED -
c:\pwwork\pwwork\madyja\0148931\0111504	shd-pln.dgn	DRAWN -	REVISED -
PLOT SCALE = 1/8" = 1' / in.	CHECKED -	DATE -	REVISED -
PLOT DATE = 7/8/2011			

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCOUR REPAIRS
RUBY ST OVER DES PLAINES RIVER**

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	M-BDR-1	WILL	66	9
CONTRACT NO. 62714				
ILLINOIS FED. AID PROJECT				