

SUMMARY OF QUANTITIES

IDOT PAY ITEM	DESCRIPTION	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	44
20200100	EARTH EXCAVATION	CU YD	260
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	50
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	553
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7
25200110	SODDING, SALT TOLERANT	SQ YD	553
25200200	SUPPLEMENTAL WATERING	UNIT	10
28000400	PERIMETER EROSION BARRIER	FOOT	955
28000510	INLET FILTERS	EACH	15
35101598	AGGREGATE BASE COURSE, TYPE B 3"	SQ YD	21
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	873
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	437
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	98
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	21
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	160
42400800	DETECTABLE WARNINGS	SQ FT	96
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	21
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	185
44000600	SIDEWALK REMOVAL	SQ FT	534
*56400400	FIRE HYDRANT TO BE RELOCATED	EACH	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	193
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
X0326862	STRUCTURES TO BE ADJUSTED	EACH	7
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	8
*X8140115	HANDHOLE TO BE ADJUSTED	EACH	2
XX008404	RECORD DRAWINGS	L SUM	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	50
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	113

* INDICATES SPECIALTY ITEM

EARTHWORK SUMMARY TABLE

Earthwork Summary Table				
Station	Earth Ex	Fill	Topsoil Strip*	Topsoil Place
	CY	CY	CY	CY
312+00.				
312+23.77	0.0	0.0	0.0	0.0
312+50.	4.0	0.0	1.7	0.2
312+76.32	4.0	0.0	1.8	0.2
313+00.	3.5	0.0	1.6	0.0
313+50.	11.8	0.3	6.7	1.1
314+00.	8.7	0.8	6.7	2.2
314+31.38	5.9	0.6	2.1	0.7
314+50.	3.9	0.1	1.2	0.4
315+00.	11.1	0.1	6.7	2.2
315+50.	5.9	0.1	3.3	1.1
316+00.	5.3	0.1	2.4	0.8
316+50.	10.2	0.3	4.4	1.3
317+00.	4.9	0.2	2.0	0.5
318+50.				
318+81.89	10.3	0.0	3.3	0.6
319+00.	6.0	0.0	2.2	0.6
319+24.58	4.1	0.0	1.5	0.4
319+50.	2.8	0.0	1.6	0.4
320+00.	5.5	0.1	3.1	0.8
320+50.	5.0	0.1	2.7	1.2
321+00.	9.7	0.3	5.4	2.4
321+50.	9.4	0.3	5.4	2.3
321+84.9	3.3	0.1	1.9	0.8
322+00.	0.0	0.0	0.0	0.0
322+50.	4.7	2.7	2.7	1.2
322+86.84	3.5	2.0	2.0	0.9
323+50.	6.3	3.5	3.5	1.6
323+99.78	9.8	4.8	4.8	1.9
324+00.	0.0	0.0	0.0	0.0
Totals	160.0*	16.0	81.0*	26.0

* PAID FOR AS EARTH EXCAVATION