SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	QUANTITY CONSTRUCTION CODE 0004
20200100	EARTH EXCAVATION	CU YD	95
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	276
25000210	SEEDING, CLASS 2A	ACRE	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23
25100630	EROSION CONTROL BLANKET	SQ YD	276
25200110	SODDING, SALT TOLERANT	SQ YD	42
25200200	SUPPLEMENTAL WATERING	UNIT	1
28000400	PERIMETER EROSION BARRIER	FOOT	225
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	207
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	63
40600300	AGGREGATE (PRIME COAT)	TON	1
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70	TON	24
48101200	AGGREGATE SHOULDERS, TYPE B	TON	89
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION - STANDARD 701501	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION - STANDARD 701606	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION - STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION - STANDARD 701801	L SUM	1
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	225
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	668
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	80
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	37
• 78001100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	219
• 78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,113
• 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	6
• 81400100	HANDHOLE	EACH	1
• 81603050	UNIT DUCT, 600V, 3-1/C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	15

• SPECIALTY ITEMS

CODE NO.	PAY ITEM	UNIT	QUANTITY CONSTRUCTION CODE 0004
• 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	21
• 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	8
• 84200804	REMOVAL OF POLE FOUNDATION	EACH	1
• 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1
• 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
• 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	421
• 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	421
• 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT.	EACH	1
• 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4
• 87900200	DRILL EXISTING HANDHOLE	EACH	1
• 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2
• 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1
• 88500100	INDUCTIVE LOOP DETECTOR	EACH	1
• 88600100	DETECTOR LOOP, TYPE 1	FOOT	114
• 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	77.1
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	237

• SPECIALTY ITEMS

COPYRIGHT © 2011, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS PROFESSIONAL ENGINEER
LICENSE NO. - 184.00121 - EXPIRES 4/30/2013
488cac 7/5/2011 4:32:52 PM
...\dgn\tr-ver\P0F22x34.pit
...\CADD-SURVEY\PLOTS\BBM.tbl
s:\Moderns\Chpk\070050-Poder at Governors\4-Phase II\Design\CADD-SURVEY\DRAWINGS\D0040-SOQ.dgn

BAXTER & WOODMAN Consulting Engineers	USER NAME = 488cac	DESIGNED - CAC	REVISED - PER IDOT 6-9-10
		DRAWN - BCD	REVISED - PER IDOT 5-10-11
	FILE NAME = 100140-SOQ.sht	CHECKED - TMS	REVISED -
	PLOT DATE = 7/5/2011	DATE - 04-22-11	REVISED -

VILLAGE OF RICHTON PARK, ILLINOIS
FAU 3778 GOVERNORS HIGHWAY
INTERSECTION IMPROVEMENTS

SUMMARY OF QUANTITITES

SCALE: NONE | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3778	07-00042-00-CH	COOK	20	3
FED. ROAD DIST. NO.	C-91-177-07	CONTRACT NO. 63489		
	ILLINOIS	FED. AID PROJECT	CMM-8003(776)	