

# SCHEDULE OF QUANTITIES

TEMPORARY RAMP		
STATION	SQ YD	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 47+00	7	12' X 5'
RT 49+25	7	12' X 5'
RT 50+74	7	12' X 5'
PER 51+94	18	16' X 10'
RT 53+50	7	12' X 5'
STAGE 1 TOTAL	46	
STAGE 2		
LT 47+00	7	12' X 5'
RT 49+25	7	12' X 5'
RT 50+74	7	12' X 5'
PER 51+94	16	14' X 10'
LT 53+50	7	12' X 5'
STAGE 2 TOTAL	44	
PROJECT TOTAL	90	

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"		
STATION	SQ YD	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 47+00 TO 49+06	220	
RT 50+94 TO 53+50	274	
STAGE 1 TOTAL	494	
STAGE 2		
LT 47+00 TO 49+06	331	
LT 50+94 TO 53+50	410	
STAGE 2 TOTAL	741	
PROJECT TOTAL	1,235	

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)		
STATION	SQ YD	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 49+06 TO 49+25	30	
RT 50+63 TO 50+94	55	
STAGE 1 TOTAL	85	
STAGE 2		
LT 49+06 TO 49+37	70	
LT 50+72 TO 50+94	44	
STAGE 2 TOTAL	114	
PROJECT TOTAL	199	

AGGREGATE SHOULDERS, TYPE B 6"		
STATION	SQ YD	REMARKS
INDIANA AVENUE		
PER 51+94	19	FINAL STAGE
PER 52+50	18	FINAL STAGE
PROJECT TOTAL	37	

HOT-MIX ASPHALT SHOULDERS, 6"		
STATION	SQ YD	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 47+00 TO 49+46	274	
RT 50+33 TO 51+76	136	
RT 52+12 TO 53+50	132	
STAGE 1 TOTAL	542	
STAGE 2		
LT 47+00 TO 49+67	262	
LT 50+54 TO 52+33	210	
LT 52+67 TO 53+50	70	
STAGE 2 TOTAL	542	
PROJECT TOTAL	1,084	

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS		
STATION	FOOT	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 48+78 TO 49+03	25	STAGE 1
LT 50+97 TO 51+22	25	STAGE 2
PROJECT TOTAL	50	

TRAFFIC BARRIER TERMINAL, TYPE 6		
STATION	EACH	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 49+03 TO 49+48	1	
RT 50+31 TO 50+76	1	
STAGE 1 TOTAL	2	
STAGE 2		
LT 49+24 TO 49+69	1	
LT 50+52 TO 50+97	1	
STAGE 2 TOTAL	2	
PROJECT TOTAL	4	

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		
STATION	EACH	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 48+26 TO 48+78	1	
RT 50+76 TO 51+28	1	
STAGE 1 TOTAL	2	
STAGE 2		
LT 48+72 TO 49+24	1	
LT 51+22 TO 51+74	1	
STAGE 2 TOTAL	2	
PROJECT TOTAL	4	

GUARDRAIL REMOVAL		
STATION	FOOT	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 48+73 TO 49+74	101	
RT 50+17 TO 50+67	50	
STAGE 1 TOTAL	151	
STAGE 2		
LT 49+36 TO 49+86	50	
LT 50+29 TO 51+30	101	
STAGE 2 TOTAL	151	
PROJECT TOTAL	302	

FURNISHING AND ERECTING RIGHT OF WAY MARKERS		
STATION	EACH	REMARKS
INDIANA AVENUE		
47+50 RT 38.54'	1	
47+50 RT 61.44'	1	
47+50 LT 41.49'	1	
47+50 LT 58.59'	1	
53+55 RT 40.04'	1	
53+55 RT 63.57'	1	
53+55 LT 39.96'	1	
53+55 LT 56.43'	1	
PROJECT TOTAL	8	

TEMPORARY BRIDGE TRAFFIC SIGNALS		
STATION	EACH	REMARKS
INDIANA AVENUE		
RT 45+70	0.2	
LT 45+90	0.2	
LT 51+95	0.2	PER 51+94
RT 54+50	0.2	
LT 54+75	0.2	
PROJECT TOTAL	1	

SHORT TERM PAVEMENT MARKINGS		
STATION	FOOT	REMARKS
INDIANA AVENUE		
47+00 TO 53+50	65	4" STRIPES 4' @ 40' CENTERS (YLW)
RT 47+00 TO 53+50	26	4" DIAG. STRIPES 4' @ 100' CENTERS (WHT)
LT 47+00 TO 53+50	26	4" DIAG. STRIPES 4' @ 100' CENTERS (WHT)
PROJECT TOTAL	117	

TEMPORARY PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
INDIANA AVENUE		
STAGE 1		
45+30 TO 54+50	921	EDGE LINE (WHT)
STAGE 1 TOTAL	921	
STAGE 2		
45+80 TO 55+15	938	EDGE LINE (WHT)
47+00 TO 53+52	651	EDGE LINE (WHT)
STAGE 2 TOTAL	1,589	
PROJECT TOTAL	2,510	

TEMPORARY PAVEMENT MARKING - LINE 24"		
STATION	FOOT	REMARKS
INDIANA AVENUE		
RT 45+20	12	STOP BAR (WHT)
PER 51+95	12	STOP BAR (WHT)
LT 55+25	12	STOP BAR (WHT)
PROJECT TOTAL	36	

WORK ZONE PAVEMENT MARKING REMOVAL		
STATION	SQ FT	REMARKS
INDIANA AVENUE		
STAGE 1	307	TEMP. PVT. MARKINGS
STAGE 2	530	TEMP. PVT. MARKINGS
STOP BARS	72	TEMP. PVT. MARKINGS
FINAL STAGE	40	SHORT TERM PVT. MARKINGS
PROJECT TOTAL	949	

TEMPORARY CONCRETE BARRIER		
STATION	FOOT	REMARKS
INDIANA AVENUE		
LT 48+80 TO 51+20	240	STAGE 1
PROJECT TOTAL	240	

RELOCATE TEMPORARY CONCRETE BARRIER		
STATION	FOOT	REMARKS
INDIANA AVENUE		
RT 48+80 TO 51+20	240	STAGE 2
PROJECT TOTAL	240	

THERMOPLASTIC PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
INDIANA AVENUE		
LT 47+00 TO 49+26	226	CENTERLINE (YLW)
RT 47+00 TO 49+26	60	CENTERLINE SKIP DASH (YLW)
LT 47+00 TO 49+32	232	EDGE LINE (WHT)
RT 47+00 TO 49+21	221	EDGE LINE (WHT)
LT 50+74 TO 53+50	276	CENTERLINE (YLW)
RT 50+74 TO 53+50	70	CENTERLINE SKIP DASH (YLW)
LT 50+79 TO 53+50	271	EDGE LINE (WHT)
RT 50+68 TO 53+50	282	EDGE LINE (WHT)
PROJECT TOTAL	1,638	

POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"		
STATION	FOOT	REMARKS
INDIANA AVENUE		
LT 49+26 TO 50+74	147	CENTERLINE (YLW)
RT 49+26 TO 50+74	40	CENTERLINE SKIP DASH (YLW)
LT 49+32 TO 50+79	147	EDGE LINE (WHT)
RT 49+21 TO 50+68	147	EDGE LINE (WHT)
PROJECT TOTAL	481	

See Sheets 14 - 32 for Locations of Structural Pay Items

FILE = S:\Structure\10330004-Indiana Avenue\Design\10330004Cover.dgn

REVISION	DATE	BY	REMARKS

DRAWN	L.G.N.
CHECKED	D.L.B.
APPROVED	B.K.C.

**ILLINOIS DEPARTMENT OF TRANSPORTATION**  
**BRIDGE REPLACEMENT**  
**INDIANA AVENUE (CH 24) OVER TRIM CREEK**



WILL COUNTY

**SCHEDULE OF QUANTITIES**  
**STRUCTURE NO. 099-3378**

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
01-00042-07-BR	WILL	58	07
STA. 47+00	STA. 53+50		
WHA #: 1033004	DATE: 6/9/2011		

CONTRACT NO. 63617