

SCHEDULE OF QUANTITIES

RAISED REFLECTIVE PAVEMENT MARKER		
STATION	EACH	REMARKS
INDIANA AVENUE		
RT 47+00 TO 49+56	3	TWO-WAY AMBER MARKER
LT 47+00 TO 49+56	3	ONE-WAY AMBER MARKER
RT 50+44 TO 53+50	4	TWO-WAY AMBER MARKER
LT 50+44 TO 53+50	4	ONE-WAY AMBER MARKER
PROJECT TOTAL	14	

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)		
STATION	EACH	REMARKS
INDIANA AVENUE		
RT 49+56 TO 50+44	2	TWO-WAY AMBER MARKER
LT 49+56 TO 50+44	2	ONE-WAY AMBER MARKER
PROJECT TOTAL	4	

GUARDRAIL MARKERS, TYPE A		
STATION	EACH	REMARKS
INDIANA AVENUE		
RT 48+26 TO 49+49	4	MONODIRECTIONAL CRYSTAL
LT 48+72 TO 49+69	3	MONODIRECTIONAL CRYSTAL
RT 50+31 TO 51+28	3	MONODIRECTIONAL CRYSTAL
LT 50+52 TO 51+74	4	MONODIRECTIONAL CRYSTAL
PROJECT TOTAL	14	

TERMINAL MARKER - DIRECT APPLIED		
STATION	EACH	REMARKS
INDIANA AVENUE		
RT 48+26	1	
LT 48+72	1	
RT 51+28	1	
LT 51+74	1	
PROJECT TOTAL	4	

TOPSOIL FURNISH AND PLACE, SPECIAL		
STATION	CU YD	REMARKS
INDIANA AVENUE		
RT 47+00 TO 53+50	185	STAGE 1
LT 47+00 TO 53+50	123	STAGE 2
PROJECT TOTAL	308	

TOPSOIL EXCAVATION		
STATION	CU YD	REMARKS
INDIANA AVENUE		
RT 47+00 TO 53+50	262	STAGE 1
LT 47+00 TO 53+50	190	STAGE 2
PROJECT TOTAL	452	

PAVEMENT REMOVAL (SPECIAL)		
STATION	SQ YD	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 47+00 TO 49+77	214	
RT 50+17 TO 53+50	248	
STAGE 1 TOTAL	462	
STAGE 2		
LT 47+00 TO 49+86	532	
LT 50+20 TO 53+50	621	
STAGE 2 TOTAL	1,153	
PROJECT TOTAL	1,615	

AGGREGATE SHOULDER REMOVAL		
STATION	CU YD	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 47+00 TO 49+75	20	APPROX. 8"
RT 50+16 TO 53+50	25	APPROX. 8"
STAGE 1 TOTAL	45	
STAGE 2		
LT 47+00 TO 49+87	21	APPROX. 8"
LT 50+28 TO 53+50	24	APPROX. 8"
STAGE 2 TOTAL	45	
PROJECT TOTAL	90	

AGGREGATE SUBGRADE 12"		
STATION	SQ YD	REMARKS
INDIANA AVENUE		
STAGE 1		
RT 47+00 TO 49+06	243	
RT 50+94 TO 53+50	302	
STAGE 1 TOTAL	545	
STAGE 2		
LT 47+00 TO 49+06	354	
LT 50+94 TO 53+50	439	
STAGE 2 TOTAL	793	
PROJECT TOTAL	1,338	

HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"		
STATION	SQ YD	REMARKS
INDIANA AVENUE		
PER 51+94	130	STAGE 1
PEL 52+50	118	STAGE 2
PROJECT TOTAL	248	

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3		
STATION	EACH	REMARKS
INDIANA AVENUE		
RT 48+80	1	STAGE 1
RT 51+20	1	STAGE 1
PROJECT TOTAL	2	

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3		
STATION	EACH	REMARKS
INDIANA AVENUE		
RT 48+80	1	STAGE 2
RT 51+20	1	STAGE 2
PROJECT TOTAL	2	

FILE = S:\Struct\1033004-Indiana Avenue.Dwg\1033004Cover.dgn

See Sheets 14 - 32 for Locations of Structural Pay Items

CONTRACT NO. 63617

REVISION	DATE	BY	REMARKS	DRAWN	CHECKED	APPROVED	ILLINOIS DEPARTMENT OF TRANSPORTATION BRIDGE REPLACEMENT INDIANA AVENUE (CH 24) OVER TRIM CREEK	WILLET HOFMANN ASSOCIATES INC ENGINEERING ARCHITECTURE LAND SURVEYING 809 EAST 2ND STREET, DIXON, IL 61021-0367 T: 815-284-3381 DESIGN FIRM: #184-000918	WILL COUNTY	SCHEDULE OF QUANTITIES STRUCTURE NO. 099-3378	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				L.G.N.	D.L.B.	B.K.C.					01-00042-07-BR	WILL	58	08
											STA. 47+00 - STA. 53+50			
											WHA #: 1033D04	DATE: 6/9/2011		