

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNITS	TOTAL QUANTITY		CONSTRUCTION TYPE CODE
			STP 0005	TRAINEE 0042	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	200	200	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	600	600	
21101615	TOPSOIL, FURNISH AND PLACE, 4"	SQ YD	500	500	
25000100	SEEDING, CLASS 1	ACRE	0.1	0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9	
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	9	9	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9	
25100630	EROSION CONTROL BLANKET	SQ YD	500	500	
28000510	INLET FILTERS	EACH	60	60	
35501330	HOT-MIX ASPHALT BASE COURSE, 11-1/2"	SQ YD	7754	7754	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6852	6852	
40600300	AGGREGATE (PRIME COAT)	TON	135	135	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10	
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75 N50	TON	2878	2878	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	848	848	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1560	1560	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	5120	5120	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5-INCH	SQ FT	1911	1911	
42400800	DETECTABLE WARNINGS	SQ FT	192	192	
44000100	PAVEMENT REMOVAL	SQ YD	7754	7754	
44000159	HOT MIX ASPHALT SURFACE REMOVAL, 2-1/2"	SQ YD	67676	67676	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	62	62	
44000600	SIDEWALK REMOVAL	SQ FT	1911	1911	
44201670	CLASS D PATCHES, TYPE 1, 2 INCH	SQ YD	500	500	
44201690	CLASS D PATCHES, TYPE 1, 4 INCH	SQ YD	500	500	
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	10	10	
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	52	52	
67100100	MOBILIZATION	LSUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	20	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	20000	20000	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1165	1165	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12000	12000	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8860	8860	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	580	580	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	807	807	
Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	1165	1165	
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4730	4730	
Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	11115	11115	
Δ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	580	580	
Δ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	807	807	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	700	700	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24	24	
Δ 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3142	3142	
* XX007860	AGGREGATE BASE COURSE, SPECIAL	SQ YD	7754	7754	
* X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	4741	4741	
* X0325110	BIAXIAL GEOGRID	SQ YD	7542	7542	
* X0326160	POROUS GRANULAR EMBANKMENT, SUBGRADE (SPECIAL)	CU YD	200	200	
* X0326911	TRANSVERSE DRAINS COMPLETE	EACH	38	38	
* X3112900	SUBBASE GRANULAR MATERIAL, (SPECIAL)	CU YD	4609	4609	
* X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6	6	
* X4023000	TEMPORARY ACCESS (ROAD)	EACH	8	8	
* X4430200	REFLECTIVE CRACK CONTROL TREATMENT, SPECIAL	FOOT	19394	19394	
* X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	16	16	
* X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	LSUM	1	1	
* Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	38	38	
* Z0076600	TRAINEES	HOURS	500		500
	* SPECIAL PROVISION Δ SPECIALTY ITEMS				

FILE NAME =	USER NAME = _USER_	DESIGNED - J.W	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N:\dgn\BB\B084Boughton\Resur\facings\sheet\BB04SummaryofQuantities.dgn	DRAWN - G.R	REVISED -	7586			11-00056-00-RS	WILL	35	3	
PLOT SCALE = 1.00 ft / IN.	CHECKED - E.J / D.R.	REVISED -	SCALE: SHEET NO. 3 OF 35 SHEETS STA. TO STA.			CONTRACT NO. 63621				
PLOT DATE = 7/22/2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							