


- NOTES.
1. PROPOSED LIGHTING UNIT SHALL BE CONNECTED TO EXISTING LIGHTING SYSTEM ALONG HARLEM AVE.
 2. EXISTING LIGHTING UNIT SHALL BE REPLACED WITH NEW 35' MH POLE, 12' MA, 250W HPS MCIII LUMINAIRE. LIGHT POLE SHALL BE INSTALLED ON EXISTING FOUNDATION AND RECONNECTED TO EXISTING CIRCUIT.
 3. PROPOSED PEDESTRIAN LIGHTING UNITS SHALL BE SET BACK AT EDGE SIDEWALK.
 4. SETBACKS SHOWN ARE MEASURED FROM EDGE OF PAVEMENT TO CENTER OF POLE/FOUNDATION.
 5. UNIT DUCT SHALL BE BORED AND PULLED.



LTC-03

AMES Engineering, Inc.
 CONSULTING ENGINEERS
 1341 Warren Avenue
 Downers Grove, IL 60515
 (630) 737-1987 (F); (630) 470-8891 (R)
 www.amesengineering.com

| | | | | | | | | | | | |
|----------------------|--------------------|-----------------|-----------|---|---|---|-----------------|--------|--------------|-----------|--|
| FILE NAME = | USER NAME = #USER# | DESIGNED - BL | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | VILLAGE OF NILES LIGHTING IMPROVEMENTS LIGHTING PLAN MILWAUKEE AVE. AT OAKTON STREET | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| #FILE# | | DRAWN - RV | REVISED - | | | 3513 | 10-00-111-00-LS | COOK | 62 | 31 | |
| PLOT SCALE = #SCALE# | | CHECKED - MSA | REVISED - | | | SCALE: 1"=30'-0" SHEET NO. OF SHEETS STA. TO STA. | | | | | |
| PLOT DATE = #DATE# | | DATE - 06-17-11 | REVISED - | | | CONTRACT NO. 63622 [ILLINOIS] FED. AID PROJECT | | | | | |