


NUMBER	ITEM	UNIT	TOTAL	80% FED 20% STATE ROADWAY 0005	SN 037-0174 80% FED 20% STATE 0011	037-1184 80% FED 20% STATE 0040
20200100	EARTH EXCAVATION	CU YD	15,465	15,465		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	500	500		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	23,700	23,700		
25000210	SEEDING, CLASS 2A	ACRE	2.75	2.75		
25000310	SEEDING, CLASS 4	ACRE	2.5	2.5		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	250	250		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	250	250		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	250	250		
& 25000750	MOWING	ACRE	2.75	2.75		
25100115	MULCH, METHOD 2	ACRE	2.75	2.75		
25100630	EROSION CONTROL BLANKET	SQ YD	7,635	7,635		
25100900	TURF REINFORCEMENT MAT	SQ YD	676	676		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3,600	3,600		
28000305	TEMPORARY DITCH CHECKS	FOOT	100	100		
28000400	PERIMETER EROSION BARRIER	FOOT	1,337	1,337		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
28100109	STONE RIPRAP, CLASS A5	SQ YD	608		608	
28200200	FILTER FABRIC	SQ YD	1,097	489	608	
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	489	489		
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	832	832		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	45	45		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	81	81		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	260	260		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	216	216		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	64	64		
44000100	PAVEMENT REMOVAL	SQ YD	304	304		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	337	337		
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	1,736	1,736		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1
50105220	PIPE CULVERT REMOVAL	FOOT	440	440		
50200100	STRUCTURE EXCAVATION	CU YD	426		426	
50300100	FLOOR DRAINS	EACH	12		12	
50300225	CONCRETE STRUCTURES	CU YD	79		79	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	299		299	
50300260	BRIDGE DECK GROOVING	SQ YD	643		643	
50300280	CONCRETE ENCASUREMENT	CU YD	6		6	
50300300	PROTECTIVE COAT	SQ YD	810		810	

NUMBER	ITEM	UNIT	TOTAL	80% FED 20% STATE ROADWAY 0005	SN 037-0174 80% FED 20% STATE 0011	037-1184 80% FED 20% STATE 0040
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	3,204		3,204	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	84,920		77,800	7,120
50800515	BAR SPLICERS	EACH	1,004		1,004	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1,316		1,316	
51202305	DRIVING PILES	FOOT	1,316		1,316	
51203600	TEST PILE STEEL HP12X53	EACH	2		2	
51500100	NAME PLATES	EACH	1		1	
52100520	ANCHOR BOLTS, 1"	EACH	24		24	
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2			2
54215559	METAL END SECTIONS 24"	EACH	2	2		
54248510	CONCRETE COLLAR	CU YD	3.7			3.7
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	159	159		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	100		100	
60100915	PIPE DRAINS 6"	FOOT	100	100		
60801024	FLAP GATE 24"	EACH	2	2		
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4	4		
# 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	200	200		
# 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
# 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3		
# 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1		
63200310	GUARDRAIL REMOVAL	FOOT	386	386		
63500105	DELINEATORS	EACH	6	6		
66500105	WOVEN WIRE FENCE, 4'	FOOT	102	102		
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	20	20		
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	174	174		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,803	3,803		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,359	1,359		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	800	800		

SPECIALTY ITEMS
& NON PARTICIPATING - 100% STATE

FILE NAME = S:\JUL_15\3089-63799\6346\027\Micro\Sheet\Sheet_S001.dgn



1170 SOUTH HOUBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME = raymondk PLOT SCALE = 20.0000' / 1" IN. PLOT DATE = 7/21/2011	DESIGNED - DRAWN - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -
---	---	--	--

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.P RTE. 585	SECTION 128 BR	COUNTY HENRY	TOTAL SHEETS 106	SHEET NO. 5
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 64C20