

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROCK ISLAND COUNTY					
				L2AED		L2AED		01C0D	07P0D
				80% FED 20% STATE 0040	80% FED 20% STATE 0005	80% FED 20% STATE 0005	50% STATE 50% VILLAGE 0005	100% VILLAGE 0005	
				QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	650	650					
61101017	STORM SEWERS PROTECTED, CLASS A, 15"	FOOT	102	102					
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	6	6					
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	3	3					
63200310	GUARDRAIL REMOVAL	FOOT	3289	3,289					
63500105	DELINEATORS	EACH	10	10					
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	105	105					
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	5	5					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2		2				
X7014490	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION NO.1	EACH	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	7,844		7,343	501			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,307		1,224	83			
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	280,315		264,010	16,089		216	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	122		122				
78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	501		459	42			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	28			28			

* SPECIALTY ITEMS

* 221,213 & 220
** ROCK ISLAND & MERCER COUNTY

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
o:\pw_work\pw\dot\cushmanbw\d0184077\02	2307-sht-schedule.dgn	DRAWN -	REVISED -			*	(19,20)RS-2	**	231	5	
	PLOT SCALE = 50,0000' / 1in.	CHECKED -	REVISED -			CONTRACT NO. 64D72					
	PLOT DATE = Mon Jun 27 13:34:08 2011	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					