

SUMMARY OF QUANTITIES

| CODE NUMBER | ITEM | UNIT | TOTAL QUANTITY | Rock Island County | L'AEED | L'AEED | 07C0D | 07P0D |
|---------------------|--|-----------------|----------------|------------------------------|------------------------------|------------------------------|----------------------------------|----------------------|
| | | | | L'AEED | ROCK ISLAND COUNTY | MERCER COUNTY | ROCK ISLAND COUNTY | ROCK ISLAND COUNTY |
| | | | | 80% FED 20% STATE 0040 | 80% FED 20% STATE 0005 | 80% FED 20% STATE 0005 | 50% STATE 50% VILLAGE 0005 | 100% VILLAGE 0005 |
| * A2006714 | TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED | EACH | 24 | 24 | | | | |
| * A2006914 | TREE, QUERCUS PALUSTRIS (PIN OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED | EACH | 24 | 24 | | | | |
| * A2007814 | TREE, TILIA AMERICANA (AMERICAN LINDEN / BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED | EACH | 24 | 24 | | | | |
| * X0322118 | REMOVE CONCRETE FLARED END SECTIONS | EACH | 6 | 6 | | | | |
| X0322352 | SEEDING MOBILIZATION | EACH | 3 | 3 | | | | |
| X0323660 | DROP BOX NO.1 | EACH | 1 | 1 | | | | |
| X0323661 | DROP BOX NO.2 | EACH | 1 | 1 | | | | |
| X0323662 | DROP BOX NO.3 | EACH | 1 | 1 | | | | |
| X0323663 | DROP BOX NO.4 | EACH | 1 | 1 | | | | |
| X0323664 | DROP BOX NO.5 | EACH | 1 | 1 | | | | |
| X4060627 | LEVELING BINDER (MACHINE METHOD) IL-9,5FG, N50 | TON | 8,047 | | 7,450 | 535 | 29 | 33 |
| X4401198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SQ YD | 100,931 | | 94,429 | 6,502 | | |
| X5015225 | PIPE CULVERT REMOVAL (SPECIAL) | FOOT | 82 | 82 | | | | |
| Z0005400 | BREAKER-RUN CRUSHED STONE | TON | 1,181 | 1,181 | | | | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | | | | |
| Z0020900 | ESTABLISHING AND REFERENCING LAND SECTION MARKERS | EACH | 15 | 15 | | | | |
| Z0023600 | FILLING EXISTING CULVERTS | EACH | 3 | 3 | | | | |
| Z0025500 | FURNISHING AND INSTALLING PROPERTY MARKERS | EACH | 4 | 4 | | | | |
| Z0028415 | GEOTECHNICAL REINFORCEMENT | SQ YD | 1867 | | 1867 | | | |
| Z0028700 | GRANULAR SUBGRADE REPLACEMENT | CU YD | 312 | | 312 | | | |
| Z0034105 | MATERIAL TRANSFER DEVICE | TON | 18,522 | | 17,375 | 1,147 | | |
| 54260048 | GRADED CULVERT END SECTION, 48" | EACH | 1 | 1 | | | | |
| 54260084 | GRADED CULVERT END SECTION, 84" | EACH | 1 | 1 | | | | |

* SPECIALTY ITEMS

| | | | |
|---|--------------------------------------|------------|-----------|
| FILE NAME = | USER NAME = cushmanbw | DESIGNED - | REVISED - |
| os:\pw\work\pwsdot\cushmanbw\d0184077\022307-sht-schedule.dgn | | DRAWN - | REVISED - |
| | PLOT SCALE = 50.0000' / 1" | CHECKED - | REVISED - |
| | PLOT DATE = Thu Jun 30 10:27:08 2011 | DATE - | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

* 221,213 & 220
** ROCK ISLAND & MERCER COUNTY

| | | | | |
|---------------------------|-------------|--------|-----------------|--------------|
| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| * | (19,20)RS-2 | ** | 231 | 6 |
| CONTRACT NO. 64D72 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |

Rev.