

SCHEDULE OF QUANTITIES

44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT LOCATION MERCER COUNTY STA 984+40 TO 7+85 ROCK ISLAND COUNTY STA 7+85 TO 375+00	FOOT 2505 <hr/> 36715 39220	COMMENTS LOCATIONS TO BE DETERMINED BY RESIDENT ENGINEER LOCATIONS TO BE DETERMINED BY RESIDENT ENGINEER						
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1 LOCATION STA 22+91	EACH 1 <hr/> 1	COMMENTS SEE SPECIAL PROVISIONS FOR DETAILS						
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2 LOCATION STA 138+30.17	EACH 1 <hr/> 1	COMMENTS SEE SPECIAL PROVISIONS FOR DETAILS						
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3 LOCATION STA 304+86	EACH 1 <hr/> 1	COMMENTS SEE SPECIAL PROVISIONS FOR DETAILS						
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4 LOCATION STA 323+61	EACH 1 <hr/> 1	COMMENTS SEE SPECIAL PROVISIONS FOR DETAILS						
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5 LOCATION STA 363+91	EACH 1 <hr/> 1	COMMENTS SEE SPECIAL PROVISIONS FOR DETAILS						
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6 LOCATION STA 370+27	EACH 1 <hr/> 1	COMMENTS SEE SPECIAL PROVISIONS FOR DETAILS						
50104400	CONCRETE HEADWALL REMOVAL LOCATION STA 319+65.00 RT	EACH 1 <hr/> 1	COMMENTS						
51500100	NAME PLATES LOCATION STA 23+03 STA 138+19 STA 304+96 STA 323+50 STA 363+65	EACH 1 1 1 1 1 <hr/> 5	COMMENTS						
54001061	GRATED BOX CULVERT END SECTIONS, CULVERT NO. 01 LOCATION STA 23+03 LT	EACH 1 <hr/> 1	COMMENTS						
54001062	GRATED BOX CULVERT END SECTIONS, CULVERT NO. 02 LOCATION STA 138+19 LT	EACH 1 <hr/> 1	COMMENTS						
54010804	PRECAST CONCRETE BOX CULVERTS 8' X 4' LOCATION STA 138+19 34' LT & 32' RT @ 28° SKEW	FOOT 66 <hr/> 66	COMMENTS						
54010808	PRECAST CONCRETE BOX CULVERTS 8' X 8' LOCATION STA 23+03 39' LT & 37' RT @ 27° SKEW	FOOT 76 <hr/> 76	COMMENTS						
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36" LOCATION STA 323+50 RT	EACH 1 <hr/> 1	COMMENTS						
542A1129	PIPE CULVERTS, CLASS A, TYPE 2 84" LOCATION STA 363+65 51' LT & 60' RT @ 22° SKEW	FOOT 111 <hr/> 111	COMMENTS						
542A1921	PIPE CULVERTS, CLASS A, TYPE 3 36" LOCATION STA 323+50 45' LT & 68' RT	FOOT 113 <hr/> 113	COMMENTS						
542A1933	PIPE CULVERTS, CLASS A, TYPE 3 48" LOCATION STA 304+96 67' LT & 84' RT @ 35° SKEW	FOOT 151 <hr/> 151	COMMENTS						
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15" LOCATION STA 18+09 25' RT STA 21+06 34' RT STA 24+85 40' RT STA 313+19 36' LT STA 315+34 36.5' RT	FOOT 127 46 52 50 46 <hr/> 321	COMMENTS FIELD ENTRANCE PRIVATE ENTRANCE FIELD ENTRANCE PRIVATE ENTRANCE FIELD ENTRANCE						
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18" LOCATION STA 54+63 28' RT STA 132+00 28' RT STA 161+00 26' LT	FOOT 48 50 52 <hr/> 150	COMMENTS 195TH ST. 210TH ST. N. West St.						
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24" LOCATION STA 370+37 42' RT STA 371+03 47' RT	FOOT 72 54 <hr/> 126	COMMENTS FIELD ENTRANCE FIELD ENTRANCE						
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15" LOCATION STA 24+03 59.5' LT STA 365+44 46.5' LT	FOOT 82 62 <hr/> 144	COMMENTS FIELD ENTRANCE FIELD ENTRANCE						
54213450	END SECTIONS 15" LOCATION STA 18+09 RT STA 21+06 RT STA 24+03 LT STA 24+85 RT STA 313+19 LT STA 315+34 RT STA 365+44 LT	EACH 2 2 2 2 2 2 2 <hr/> 14	COMMENTS						
54213453	END SECTIONS 18" LOCATION STA 54+63 RT STA 132+00 RT STA 161+00 LT	EACH 2 2 2 <hr/> 6	COMMENTS						
54213459	END SECTIONS 24" LOCATION STA 370+37 RT STA 371+03 RT	EACH 1 1 <hr/> 2	COMMENTS						
54213471	END SECTIONS 36" LOCATION STA 370+00 RT	EACH 1 <hr/> 1	COMMENTS						

* 221,213 & 220
** ROCK ISLAND & MERCER COUNTY

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct\pwork\pwork\cushmanbw\d8184877\02	2307-sht-schedule.dgn	DRAWN -	REVISED -			*	(19,20)RS-2	**	231	15	
	PLOT SCALE = 50.0000' / 1in.	CHECKED -	REVISED -								
	PLOT DATE = Thu Jun 30 08:53:45 2011	DATE -	REVISED -								
						SCALE:		SHEET NO. OF SHEETS		STA. TO STA.	
						ILLINOIS FED. AID PROJECT CONTRACT NO. 64D72					