

SCHEDULE OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	REMARKS
78001180	PAINT PAVEMENT MARKING - LINE 24"			
	LOCATION			
	190th Ave West	White	(2 Apl.) 32.00	Stop Bar
	105th St West	White	(2 Apl.) 50.00	Stop Bar
	176th Ave West	White	(2 Apl.) 40.00	Stop Bar
	TOTAL		122	
78100100	RAISED REFLECTIVE PAVEMENT MARKERS			
	LOCATION			
	MERCER COUNTY			
	STA 983+72 TO 7+85		42	Two-way amber @ 80' centers, 40' centers around curve per std.
	ROCK ISLAND COUNTY			
	STA 7+85 TO 375+00		459	Two-way amber @ 80' centers
	TOTAL		501	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
	LOCATION			
	MERCER COUNTY			
	STA 983+72 TO 7+85		28	
	TOTAL		28	
X0322118	REMOVE CONCRETE FLARED END SECTIONS			
	LOCATION			
	STA 298+18.69	LT & RT	2	36" LT & RT
	STA 319+65.00	LT & RT	2	36" LT & 30" RT
	STA 374+38	LT & RT	2	30" LT & RT
	TOTAL		6	
X0323660	DROP BOX NO.1			
	LOCATION			
	STA 23+03	RT	1	
	TOTAL		1	
X0323661	DROP BOX NO.2			
	LOCATION			
	STA 138+19	RT	1	
	TOTAL		1	
X0323662	DROP BOX NO.3			
	LOCATION			
	STA 304+96	LT	1	
	TOTAL		1	
X0323663	DROP BOX NO.4			
	LOCATION			
	STA 323+50	LT	1	
	TOTAL		1	
X0323664	DROP BOX NO.5			
	LOCATION			
	STA 363+65	LT	1	
	TOTAL		1	
X5015225	PIPE CULVERT REMOVAL (SPECIAL)			
	LOCATION			
	STA 54+63	RT	32	
	STA 161+00	LT	50	
	TOTAL		82	
Z0020900	ESTABLISHING AND REFERENCING LAND SECTION MARKERS			
	LOCATION			
	STA 27+98.07	2.9' LT	1	
	STA 28+67.00	2.8' LT	1	
	STA 54+19.47	1.7' RT	1	
	STA 54+64.07	1.8' RT	1	
	STA 80+42.03	7.6' RT	1	
	STA 81+19.51	7.6' RT	1	
	STA 105+79.15	7.8' RT	1	
	STA 107+05.45	7.8' RT	1	
	STA 132+00.75	8.0' RT	1	
	STA 133+68.71	8.0' RT	1	
	STA 207+49.04	1.7' LT	1	
	STA 233+89.13	3.7' LT	1	
	STA 313+35.20	15.9' LT	1	
	STA 314+03.36	16.5' LT	1	
	STA 366+46.07	13.4' LT	1	
	STA 367+52.42	12.4' LT	1	
	TOTAL		15	

Z0023600	FILLING EXISTING CULVERTS			
	LOCATION			
	STA 298+18.69	Existing 2' x 3' Box 40' in length	1	
	STA 319+65.00	Existing 2' x 3' Box 72' in length	1	
	STA 374+38	Existing 2' x 2.5' Box 46' in length	1	
	TOTAL		3	
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS			
	LOCATION			
	STA 17+94.52	38.67' RT	1	
	STA 300+59.80	34.57' LT	1	
	STA 366+60.41	32.66' RT	1	
	STA 370+61.87	32.64' RT	1	
	TOTAL		4	
Z0028415	GEOTECHNICAL REINFORCEMENT			
	LOCATION			
	STA 201+50 TO 208+50		1867	
	TOTAL		1867	
Z0028700	GRANULAR SUBGRADE REPLACEMENT			
	LOCATION			
	STA 201+50 TO 208+50		312	
	TOTAL		312	See detail Sheet
	GRATED CULVERT END SECTIONS 48"			
	LOCATION			
	STA 304+96	RT	1	
	TOTAL		1	
	GRATED CULVERT END SECTIONS 84"			
	LOCATION			
	STA 363+65	RT	1	
	TOTAL		1	

* 221,213 & 220
** ROCK ISLAND & MERCER COUNTY

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\p\dot\cushmanbw\0184077\02	2307-sht-schedule.dgn	DRAWN -	REVISED -			*	(19,20)RS-2	**	231	19	
	PLOT SCALE = 50.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 64D72					
	PLOT DATE = Thu Jun 30 08:55:12 2011	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	