

EARTHWORK /AGGREGATE SCHEDULE

EARTHWORK SCHEDULE

LOCATION	20200100			
	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)
	(CU YD)	(CU YD)	(CU YD)	(CU YD)
17+00.00 TO 19+00.00	102.3	76.7	53.1	23.6
19+00.00 TO 25+00.00	5706.5	4279.9	1270.5	3009.4
25+00.00 TO 28+00.00	2834.8	2126.1	56.7	2069.4
131+00.00 TO 135+50.00	1637.5	1228.1	32.6	1195.5
135+50.00 TO 141+50.00	3086.4	2314.8	614.4	1700.4
141+50.00 TO 144+00.00	898.6	674.0	99.7	574.3
297+75.00 TO 302+00.00	3141.7	2356.3	431.8	1924.5
302+00.00 TO 308+00.00	8830.4	6622.8	1792.0	4830.8
308+00.00 TO 314+00.00	4378.2	3283.7	87.3	3196.4
314+00.00 TO 320+00.00	2816.1	2112.1	688.0	1424.1
320+00.00 TO 326+00.00	6156.9	4617.7	1220.4	3397.3
326+00.00 TO 327+50.00	771.8	578.9	42.8	536.1
354+00.00 TO 359+00.00	11676.5	8757.4	75.7	8681.7
359+00.00 TO 365+00.00	7711.9	5783.9	3576.0	2207.9
365+00.00 TO 371+00.00	17366.3	13024.7	1228.0	11796.7
371+00.00 TO 375+00.00	4904.8	3678.6	256.2	3422.4
TOTALS	82020.7	61515.5	11525.2	49990.3

AGGREGATE SCHEDULE

LOCATION	REMARKS	WIDTH	AREA	Z0005400 BREAKER RUN CRUSHED STONE			
				FOOT	SQ FT	INCHES	TON
IL 251							
Culvert		23	+	3	2032	12"	154.3
Culvert		138	+	19	1412	48"	428.8
Culvert		304	+	93	1580	12"	120.0
Culvert		323	+	50	977	24"	148.4
Culvert		363	+	65	2170	24"	329.5
Total					4727		1181

* 221,213 & 220
** ROCK ISLAND & MERCER COUNTY