

# SUMMARY OF QUANTITIES

| SUMMARY     |  |       |                | RURAL             |
|-------------|--|-------|----------------|-------------------|
|             |  |       |                | 0040              |
| CODE NUMBER | ITEM   | UNIT  | TOTAL QUANTITY | 80% FED 20% STATE |
| 20100110    | TREE REMOVAL (6 TO 15 UNITS DIAMETER)        | UNIT  | 216            | 216               |
| 20100210    | TREE REMOVAL (OVER 15 UNITS DIAMETER)        | UNIT  | 49             | 49                |
| 20200100    | EARTH EXCAVATION                             | CU YD | 1720           | 1720              |
| 20201200    | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL  | CU YD | 115            | 115               |
| 20400800    | FURNISHED EXCAVATION                         | CU YD | 510            | 510               |
| * 25000210  | SEEDING, CLASS 2A                            | ACRE  | 1.25           | 1.25              |
| * 25000310  | SEEDING, CLASS 4                             | ACRE  | 0.25           | 0.25              |
| Δ 25000750  | MOWING                                       | ACRE  | 1.25           | 1.25              |
| * 25100125  | MULCH METHOD 3                               | ACRE  | 1.25           | 1.25              |
| * 25100630  | EROSION CONTROL BLANKET                      | SQ YD | 250            | 250               |
| * 25100900  | TURF REINFORCEMENT MAT                       | SQ YD | 319            | 319               |
| 28000250    | TEMPORARY EROSION CONTROL SEEDING            | POUND | 654            | 654               |
| 28000305    | TEMPORARY DITCH CHECKS                       | FOOT  | 169            | 169               |
| 28000400    | PERIMETER EROSION BARRIER                    | FOOT  | 1461           | 1461              |
| 28000500    | INLET AND PIPE PROTECTION                    | EACH  | 6              | 6                 |
| 28100107    | STONE RIPRAP, CLASS A4                       | SQ YD | 307            | 307               |
| 28200200    | FILTER FABRIC                                | SQ YD | 307            | 307               |
| 31100100    | SUBBASE GRANULAR MATERIAL, TYPE A            | TON   | 507            | 507               |
| 35101400    | AGGREGATE BASE COURSE, TYPE B                | TON   | 145            | 145               |
| 40603310    | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON   | 63             | 63                |
| 40800050    | INCIDENTAL HOT-MIX ASPHALT SURFACING         | TON   | 16             | 16                |
| 44201359    | CLASS C PATCHES, TYPE IV, 10 INCH            | SQ YD | 232            | 232               |
| 44213200    | SAW CUTS                                     | FOOT  | 953            | 953               |
| 48101200    | AGGREGATE SHOULDERS, TYPE B                  | TON   | 223            | 223               |
| 48203023    | HOT-MIX ASPHALT SHOULDERS, 6 1/2"            | SQ YD | 347            | 347               |
| 50100300    | REMOVAL OF EXISTING STRUCTURES NO. 1         | EACH  | 1              | 1                 |

\* SPECIALTY ITEMS      Δ 100% STATE

|  |                      |            |           |   |                              |                    |                     |           |              |           |                           |
|--|----------------------|------------|-----------|---|------------------------------|--------------------|---------------------|-----------|--------------|-----------|---------------------------|
| FILE NAME =  | USER NAME = hensonke | DESIGNED - | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES</b> | F.A.P. RTE.        | SECTION             | COUNTY    | TOTAL SHEETS | SHEET NO. |                           |
| 01\pwork\pwork\hensonke\0133232\020809-sht-500.dgn |                      | DRAWN -    | REVISED - |   |                              | 309                | 15T-1               | WHITESIDE | 74           | 3         |                           |
| PLOT SCALE = 50.0000' / 1"                         |                      | CHECKED -  | REVISED - |   |                              | CONTRACT NO. 64F23 |                     |           |              |           |                           |
| PLOT DATE = Fri Jun 24 07:43:08 2011               |                      | DATE -     | REVISED - |   |                              | SCALE:             | SHEET NO. OF SHEETS | STA.      | TO STA.      |           | ILLINOIS FED. AID PROJECT |