

SUMMARY OF QUANTITIES

SUMMARY				RURAL 0040
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2
50105220	PIPE CULVERT REMOVAL	FOOT	151	151
50300225	CONCRETE STRUCTURES	CU YD	19.7	19.7
50800105	REINFORCEMENT BARS	POUND	21560	21560
50800515	BAR SPLICERS	EACH	47	47
51500100	NAME PLATES	EACH	2	2
54003000	CONCRETE BOX CULVERTS	CU YD	121.1	121.1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	136	136
54213450	END SECTIONS 15"	EACH	6	6
54390310	INSERTION CULVERT LINER 60"	FOOT	244	244
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	3.4	3.4
60100935	PIPE DRAINS 10"	FOOT	40	40
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	10	10
61133100	FIELD TILE JUNCTION VAULT, 2' DIA.	EACH	1	1
63500105	DELINEATORS	EACH	5	5
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	16	16
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2211	2211
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26	26

*** SPECIALTY ITEMS**

FILE NAME = c:\pwork\pwork\hensonka\d0133232\0286629-sht-S00.dgn	USER NAME = hensonka	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 309	SECTION 15T-1	COUNTY WHITESIDE	TOTAL SHEETS 74	SHEET NO. 4
PLOT SCALE = 50,0000' / 1"	PLOT DATE = Fri Jun 24 07:43:09 2011	DRAWN -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 64F23 ILLINOIS FED. AID PROJECT				
CHECKED -	DATE -	REVISED -	REVISED -							