

SCHEDULE OF QUANTITIES

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	REMARKS
1	LT. STA. 1277 + 63	Entrance Pipe (CE) SN 098-1019 Entrance Pipe (FE) Entrance Pipe (FE) SN 098-1020 SN 098-1021
1	LT. STA. 1281 + 24	
1	LT. STA. 1283 + 16	
1	RT. STA. 1283 + 90	
1	LT. STA. 1334 + 42	
1	LT. STA. 1503 + 73	
<u>6</u>	TOTAL	

31100100 SUBBASE GRANULAR MATERIAL, TYPE A

TON	LOCATION	REMARKS
272.1	LT. STA. 1278 + 33 to 1283 + 45	runaround (Calc'd as 4" Thick) runaround (Calc'd as 4" Thick)
234.4	RT. STA. 1279 + 5 to 1283 + 45	
<u>506.5</u>	TOTAL	

35101400 AGGREGATE BASE COURSE, TYPE B

TON	LOCATION	REMARKS
49.5	LT. STA. 1277 + 91	CE w/ MB Turnout (Calc'd as 8" Thick) FE (Calc'd as 8" Thick) FE (Calc'd as 8" Thick)
61.4	LT. STA. 1282 + 92	
34.0	LT. STA. 1283 + 72	
<u>145.0</u>	TOTAL	

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

TON	LOCATION	REMARKS
27.5	LT. STA. 1278 + 33 to 1283 + 45	Pre-Stage 1 - Shoulder Stage 1 - shoulder Stage 2 - shoulder in patch area
30.3	RT. STA. 1279 + 5 to 1283 + 45	
4.5	LT. STA. 1280 + 83 to 1281 + 63	
<u>62.3</u>	TOTAL	

40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING

TON	LOCATION	REMARKS
15.2	LT. STA. 1277 + 91	CE w/ MB Turnout
<u>15.2</u>	TOTAL	

44201359 CLASS C PATCHES, TYPE IV, 10 INCH

SQ YD	LOCATION	REMARKS
115.6	LT. STA. 1280 + 83 to 1281 + 63	Stage 2 - 13' wide Stage 3 - 13' wide
115.6	LT/RT 1280 + 83 to 1281 + 63	
<u>231.1</u>	TOTAL	

44213200 SAW CUTS

FOOT	LOCATION	REMARKS
512	LT. STA. 1278 + 33 to 1283 + 45	To be used at the RE's discretion To be used at the RE's discretion
441	LT. STA. 1279 + 5 to 1283 + 45	
<u>953</u>	TOTAL	

48101200 AGGREGATE SHOULDERS, TYPE B

TON	LOCATION	REMARKS	
9.3	LT. STA. 1277 + 16 to 1277 + 75	SN 098-1020, to be used as needed by R.E. SN 098-1021, to be used as needed by R.E.	
40.1	LT. STA. 1278 + 7 to 1282 + 95		
16.1	LT. STA. 1283 + 14 to 1284 + 16		
27.6	RT. STA. 1277 + 16 to 1278 + 26		
20.2	RT. STA. 1278 + 26 to 1279 + 54		
28.0	RT. STA. 1279 + 54 to 1282 + 95		
24.9	RT. STA. 1282 + 95 to 1284 + 16		
16.2	LT. STA. 1280 + 83 to 1281 + 63		
20.0	LT/RT 1334 + 42		
20.0	LT/RT 1503 + 73		
<u>222.5</u>	TOTAL		

48203023 HOT-MIX ASPHALT SHOULDERS, 6 1/2"

SQ YD	LOCATION	REMARKS
327.8	LT. STA. 1278 + 33 to 1283 + 45	Pre-Stage 1 Stage 1 Stage 2
293.7	RT. STA. 1279 + 5 to 1283 + 45	
53.3	LT. STA. 1280 + 83 to 1281 + 63	
<u>347.0</u>	TOTAL	

50104400 CONCRETE HEADWALL REMOVAL

EACH	LOCATION	REMARKS
1	LT. STA. 1278 + 48	Existing Ditch Culvert (15" RCP) Existing Ditch Culvert (15" RCP)
1	LT. STA. 1279 + 98	
<u>2</u>	TOTAL	

50105220 PIPE CULVERT REMOVAL

FOOT	LOCATION	REMARKS
151	LT. STA. 1278 + 48 to 1279 + 98	Existing Ditch Culvert (15" RCP)
<u>151</u>	TOTAL	