

# SCHEDULE OF QUANTITIES

78001110 PAINT PAVEMENT MARKING - LINE 4"

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"			
FOOT		LOCATION	REMARKS
695	LT/RT	1277 + 65 to 1284 + 58	Stage 1 Edge Line
412	LT	1279 + 34 to 1283 + 44	Stage 1 Edge Line
688	LT/RT	1277 + 94 to 1284 + 80	Stage 2 Edge Line
416	RT	1279 + 6 to 1283 + 20	Stage 2 Edge Line
2211	TOTAL		

FOOT	LOCATION	REMARKS
360 **	C.L. 1277 + 16 to 1284 + 17	Centerline Skips - Stage 3 (Qty. 18)
1402 **	LT. STA. 1277 + 16 to 1284 + 17	Edge Line - Stage 3
1402 **	RT. STA. 1277 + 16 to 1284 + 17	Edge Line - Stage 3
120 **	C.L. 1333 + 35 to 1335 + 60	Centerline Skips - Stage 3 (Qty. 6)
450 **	LT. STA. 1333 + 35 to 1335 + 60	Edge Line - Stage 3
450 **	RT. STA. 1333 + 35 to 1335 + 60	Edge Line - Stage 3
200 **	C.L. 1502 + 0 to 1505 + 75	Centerline Skips - Stage 3 (Qty. 10)
750 **	LT. STA. 1502 + 0 to 1505 + 75	Edge Line - Stage 3
750 **	RT. STA. 1502 + 0 to 1505 + 75	Edge Line - Stage 3
5884	TOTAL ** (Quantities figured on 2 Applications)	

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"			
FOOT		LOCATION	REMARKS
13	RT. STA.	1277 + 46	Stop Bar Stage 1
13	LT. STA.	1285 + 6	Stop Bar Stage 1
26	TOTAL		

78300100 PAVEMENT MARKING REMOVAL

70301000 WORKZONE PAVEMENT MARKING REMOVAL			
SQ. FT.		LOCATION	REMARKS
26	RT. STA.	1277 + 46	Removal of Stage 2 Stop Bar
26	LT. STA.	1285 + 6	Removal of Stage 2 Stop Bar
229.4	LT/RT	1277 + 65 to 1284 + 58	Removal of Stage 1 Edge Line
136.0	LT	1279 + 34 to 1283 + 44	Removal of Stage 1 Edge Line
227.0	LT/RT	1277 + 94 to 1284 + 80	Removal of Stage 2 Edge Line
137.3	RT	1279 + 6 to 1283 + 20	Removal of Stage 2 Edge Line
781.6	TOTAL		

SQ. FT.	LOCATION	REMARKS
21.2	C.L. 1277 + 46 to 1280 + 0	Removal of Skip Dashes Stage 1 (Qty. 6)
21.3	C.L. 1282 + 50 to 1285 + 6	Removal of Skip Dashes Stage 1 (Qty. 6)
132.7	LT. STA. 1279 + 34 to 1283 + 32	Removal of Edge Line Stage 1
130.3	RT. STA. 1279 + 15 to 1283 + 6	Removal of Edge Line Stage 2
305.5	TOTAL	

A2006514 TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED

EACH	LOCATION	REMARKS
8.0	TO BE DETERMINED BY THE LANDSCAPE ARCHITECT	
8.0	TOTAL	

70400100 TEMPORARY CONCRETE BARRIER			
FOOT		LOCATION	REMARKS
137.5	RT/LT	1279 + 15 to 1280 + 54	Stage 1
137.5	LT	1280 + 54 to 1281 + 94	Stage 1
137.5	LT/RT	1281 + 94 to 1283 + 33	Stage 1
412.5	TOTAL		

B2001114 TREE, CERCIS CANADENSIS (EASTERN REDBUD), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED

EACH	LOCATION	REMARKS
6.0	TO BE DETERMINED BY THE LANDSCAPE ARCHITECT	
6.0	TOTAL	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER			
FOOT		LOCATION	REMARKS
125	LT/RT	1279 + 28 to 1280 + 54	Stage 2
137.5	RT	1280 + 54 to 1281 + 94	Stage 2
125	RT/LT	1281 + 94 to 1283 + 20	Stage 2
387.5	TOTAL		

B2004114 TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED

EACH	LOCATION	REMARKS
6.0	TO BE DETERMINED BY THE LANDSCAPE ARCHITECT	
6.0	TOTAL	

C2001748 SHRUB, CORNUS SERICEA CARDINAL (CARDINAL REDOSIER DOGWOOD), 4' HIEGHT, BALLEDAND BURLAPPED

EACH	LOCATION	REMARKS
6.0	TO BE DETERMINED BY THE LANDSCAPE ARCHITECT	
6.0	TOTAL	