

EARTHWORK SCHEDULE

LOCATION			20200100				20400800	25000210	25000310	25100125	28000250
			EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	FURNISHED EXCAVATION	SEEDING, CLASS 2A	SEEDING, CLASS 4	MULCH METHOD 3	TEMPORARY EROSION CONTROL SEEDING
			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(ACRE)	(ACRE)	(ACRE)	(POUND)
1277+00	TO	1284+50	410.4	307.8	754.0	-446.2	446.2	0.57	0.07	0.57	413.0
1333+50	TO	1335+50	465.7	349.3	410.2	-60.9	60.9	0.13		0.13	91.0
1502+00	TO	1506+00	844.4	807.8	807.8	0.0	0.0	0.31	0.1	0.31	241.0
TOTALS			1720.5	1464.9	1972.0	-507.1	507.1	1.01	0.19	1.01	745.0