

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	STP		HSIP										
				ROADWAY 0005	ROADWAY 0005	80% FED/ 20% STATE	90% FED/ 10% STATE	90% FED/ 6.67% STATE/ 3.33% CITY	90% FED/ 5% STATE/ 5% CITY	90% FED/ 5% STATE/ 5% CITY	90% FED/ 10% STATE	90% FED/ 5% STATE/ 5% CITY	90% FED/ 10% STATE	90% FED/ 10% STATE	100% CITY	100% CITY
						TRAFFIC SIGNALS SYCAMORE STREET 0021	TRAFFIC SIGNALS PINE STREET 0021	TRAFFIC SIGNALS LOCUST STREET 0021	TRAFFIC SIGNALS IL 38 0021	TRAFFIC SIGNALS TAYLOR STREET 0021	TRAFFIC SIGNALS INTERCONNECT 0021	LIGHTING 0021	LIGHTING 0021	LIGHTING 0021	EMERGENCY VEHICLE PREEMPTION 0021	UTILITIES 0043
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16	16	---	---	---	---	---	---	---	---	---	---	---	---
20200100	EARTH EXCAVATION	CU YD	325	325	---	---	---	---	---	---	---	---	---	---	---	---
20800150	TRENCH BACKFILL	CU YD	3	3	---	---	---	---	---	---	---	---	---	---	---	---
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10	---	---	---	---	---	---	---	---	---	---	---	---
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10	---	---	---	---	---	---	---	---	---	---	---	---
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10	---	---	---	---	---	---	---	---	---	---	---	---
25200110	SODDING, SALT TOLERANT	SQ YD	791	791	---	---	---	---	---	---	---	---	---	---	---	---
25200200	SUPPLEMENTAL WATERING	UNIT	17	17	---	---	---	---	---	---	---	---	---	---	---	---
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	453	456	---	---	---	---	---	---	---	---	---	---	---	---
35400510	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 11"	SQ YD	342	342	---	---	---	---	---	---	---	---	---	---	---	---
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2709	2709	---	---	---	---	---	---	---	---	---	---	---	---
40600300	AGGREGATE (PRIME COAT)	TON	66	66	---	---	---	---	---	---	---	---	---	---	---	---
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	102	102	---	---	---	---	---	---	---	---	---	---	---	---
40600525	LEVELING BINDER (HAND METHOD), N50	TON	17	17	---	---	---	---	---	---	---	---	---	---	---	---
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	---	---	---	---	---	---	---	---	---	---	---	---
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3567	3567	---	---	---	---	---	---	---	---	---	---	---	---
40600990	TEMPORARY RAMP	SQ YD	930	930	---	---	---	---	---	---	---	---	---	---	---	---
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	225	225	---	---	---	---	---	---	---	---	---	---	---	---
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	30	30	---	---	---	---	---	---	---	---	---	---	---	---
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	95	95	---	---	---	---	---	---	---	---	---	---	---	---
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	14413	14413	---	---	---	---	---	---	---	---	---	---	---	---
42400800	DETECTABLE WARNINGS	SQ FT	1022	1022	---	---	---	---	---	---	---	---	---	---	---	---
44000100	PAVEMENT REMOVAL	SQ YD	81	81	---	---	---	---	---	---	---	---	---	---	---	---
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2'	SQ YD	33521	33521	---	---	---	---	---	---	---	---	---	---	---	---
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	219	219	---	---	---	---	---	---	---	---	---	---	---	---
44000300	CURB REMOVAL	FOOT	149	149	---	---	---	---	---	---	---	---	---	---	---	---
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2306	2306	---	---	---	---	---	---	---	---	---	---	---	---
44000600	SIDEWALK REMOVAL	SQ FT	14338	14338	---	---	---	---	---	---	---	---	---	---	---	---
44201361	CLASS C PATCHES, TYPE I, 11 INCH	SQ YD	3	3	---	---	---	---	---	---	---	---	---	---	---	---
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	10256	10256	---	---	---	---	---	---	---	---	---	---	---	---
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	13	13	---	---	---	---	---	---	---	---	---	---	---	---
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	21	21	---	---	---	---	---	---	---	---	---	---	---	---
55100400	STORM SEWER REMOVAL 10"	FOOT	8	8	---	---	---	---	---	---	---	---	---	---	---	---
56109210	WATER VALVES TO BE ADJUSTED	EACH	2	---	---	---	---	---	---	---	---	---	---	---	---	2
56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1	---	---	---	---	---	---	---	---	---	---	---	---	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2	2	---	---	---	---	---	---	---	---	---	---	---	---

* - SPECIALTY ITEM

FILE NAME = 0366983-SHT-S00.DGN

USER NAME = ---

DESIGNED - DJD

REVISED - ---

DRAWN - NV

REVISED - ---

CHECKED - DJD

REVISED - ---

DATE - 01/11

REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: 1"=20'

SHEET NO. ___ OF ___ SHEETS STA. TO STA.

F.A.P. RTE. 68

SECTION (28)N, TS & I

COUNTY DEKALB

TOTAL SHEETS 120 SHEET NO. 3

CONTRACT NO. 66983

FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT